


Status report on the Survey and Alignment of the Accelerators at CERN

- PS and SPS
- LEIR
- CTF3 / CLIC
- CNGS
- LHC
- Conclusion

*On behalf of M. Jones, H. Mainaud Durand, D. Missiaen, J.P. Quesnel
and their colleagues of the “Large Scale Metrology Group” at CERN*

Accelerator chain of CERN (operating or approved projects)




p (proton)
 ion
 neutrons
 \bar{p} (antiproton)
 proton/antiproton conversion
 neutrinos


AD Antiproton Decelerator
 PS Proton Synchrotron
 SPS Super Proton Synchrotron

LHC Large Hadron Collider
 n-ToF Neutrons Time of Flight
 CNGS CERN Neutrinos Grand Sasso

■ PS



- ◆ Repair of 30 magnets
- ◆ Complete smoothing of all 100 magnets





- Repair of the polyurethane jacks
- Smoothing of all the 216 quadrupoles and the SSS
- 100m long stretched wires and offset measurements up to 1.3m.


Accelerator chain of CERN (operating or approved projects)




- For injection of ions
- Transformation of LEAR machine (used for pbars)
- Metrology based on a square of 4 pillars
- Straight sections reconfigured
- New injection and ejection lines

CLIC Test Facility


CTF3 complex



ASSO
RN



The protons beam line
extracted from the
SPS, and the target
station





■ Geodetic aspects

- ◆ Determine Grand Sasso in CCS with GPS (Italy, Switzerland, France, CERN).
- ◆ Modelling of the geoid
- ◆ Calculation of the beam trajectory with MAD-X

■ Alignment


- ◆ Underground ref. network
 - Gyro + mekometer + wire offsets + leveling
- ◆ Total station + direct leveling
- ◆ Smoothing with stretched wire

■ Metrology on the target and the horn with the laser tracker.





LHC / Injection line TI8



TI8

- Length : 2 km
- 400 magnets and beam positioning monitors
- Slope ~3.5%
- Tunnel diameter: 3m

■ Geodetic network :


- ⊕Angles
- ⊕Gyroscopic measurements every 120m
- ⊕Mekometer for distances
- ⊕Direct leveling

■ Alignment :

- ⊕Total station from the network for XY
- ⊕Direct leveling for Z
- ⊕Smoothing with stretched wire

LHC / Injection line test


First shot, no correctors



Vacuum chamber



LHC / Cryogenic line



- Poor flexibility of the bellows (articulations not independent)
- Inaccurate construction of the service modules (several cm !)
- Tilted plane of the machine not considered
- Generates parasitic stresses on the SSS → risks of misalignments
- ~200 jumper connections

■ Typical example of work where Survey has been neglected

- ◆ No theoretical geometrical definition of the line
- ◆ Bad geometrical quality of the critical elements
- ◆ No attention paid to positioning (staff, references, positionners)

Define the theoretical position of the line in XYZ



Calculate the theoretical position of the elements

For 1 sector (made by CERN),
Alignment based on classical total station methods

Measure the real shape of the service modules, and install alignment targets



Develop positionners

For the contractor part: draw the positions on the floor and check the critical elements

■ The line is installed is 100% installed and the last sector is under test.



LHC / Fiducialisation of magnets

■ Fiducialisation

- ◆ Control of the shape of the cryomagnets
- ◆ Determination of the fiducials
 - W.r.t. mechanical axis for dipoles
 - W.r.t. mechanical and magnetic axis for SSS

■ Cartography of the ends

- ◆ Position of the pipes / fiducials
- ◆ Position of the BPMs / fiducials

■ ~70% achieved (87% for fiducialisation of the dipoles).

■ Random tests of stability of the cold masses after transport in the tunnel

■ Additional works for assembly and controls

- ◆ Special magnets (low beta quads...)
- ◆ Special elements (RF cavities, DFBs, Wigglers...)

■ All the information stored in EDMS and MTF

LHC / Alignment of the ring

- 60% of the magnets installed, 54% aligned
- Periodic controls of the network (leveling + radial meas. with stretched wire)
- Alignment : with total station and leveling, and then radial smoothing with long wires
- Final smoothing (H +V) when cooled.
- Most positive aspects:
 - ◆ The installation process: marking, align the jacks.
 - ◆ Jacks/targets
 - ◆ Methodology / flexibility / accuracy




LHC / Alignment of the ring



LHC / insertion magnets

Layout of the LEP tunnel including future LHC infrastructures.




LHC / insertion magnets



- Permanent monitoring with HLS and WPS
- Length of the networks: 120m
- The jacks are motorized
- Permanent link with the experiments

LHC / insertion magnets

- The group is responsible for the design, the hardware (instrumentation + motors), the installation, the software, the electronics, the measurements, the data acquisition and storage
- Collaboration with RRCAT (India) for the actuators, and Control group for the data acquisition from the control room







LHC / As-built measurements

- Scan with the Leica HDS3000
- Main goal: avoid any topological conflict at each step of the installation.
- Clouds of points are imported into CATIA, where surface meshes are fitted.
- Then the theoretical mock-up can be merged with the scans thanks to a unique geo-referenced system.
- 8 km of tunnel have been scanned with a point every ~20mm in XYZ.


LHC / As built measurements



LHC / As built measurements



LHC / As built measurements



■ Technical aspects

- ◆ Need for metrological controls of the elements
 - Responsibility of the quality controls to be taken by professionals
 - Redundancy is absolutely necessary
 - Introduce the measurements as early as possible during the manufacturing process
 - To be able to control at CERN by CERN even if controls have been made by the manufacturer
- ◆ Define vocabulary “Tolerance / Accuracy...etc”
- ◆ Make CAD and Geodetic considerations compatible by using a unique coordinate system



Our experience

■ Installation process

- ◆ A key role for surveyors (from the very beginning to the very end). Full process of the installation to be studied.
- ◆ We contributed to the design of the elements very early on, and we concentrated on targets, supports, access, free space. This influenced the alignment methodology (and the cost) a lot.
- ◆ Maximum flexibility for maximum efficiency
 - Define correctly the work and conditions, but lots of changes will occur
 - Choice of the methods of alignment to generate a minimum of constraints

■ Database

- ◆ The integrity is absolutely necessary. Hard to reach.
- ◆ Write a software spy to detect unannounced changes.

■ Management

◆ External contracts

- 1 contract for the fiducialisation of the magnets, 1 for the alignment works in the tunnels.
- Result oriented contracts for the repetitive work
- Special works carried out by CERN staff
- CERN provides tools, instruments, software, and has defined all the procedures in detail.

◆ International collaborations

- US labs for special magnets, RRCAT from India for adjustment supports of magnets.

◆ Management tools

- Definition of a WBS
- Efficient tool for managing the budget costs, thanks to the flexibility left to the users

- A lot of work has been done in 2 years
- To maintain the quality is always a challenge
- The standardization of the methods has revealed its efficiency.
- It is a team effort.

