


Fabrication Status of the Quarter Scale Scintillating Strip Muon Detector Prototype Planes

Mitch Wayne
University of Notre Dame

Motivation

- Fabrication of quarter-size planes ($1.4\text{m} \times 2.8\text{m}$) will exercise all the steps required to make full-sized planes
- Quarter-size planes are more manageable, easier to transport, etc.
- Conserves raw materials – scintillating strips and fiber
- Will have four detectors ready by end of summer for use in beam tests and/or cosmic ray telescope

Assembly Concept




- Dimensions: 2.2cm x 1.4m x 2.8m
- 64 active strips with wave shifting fiber readout

Production Plan

- Build four units
 - Two units with single splice and WLS metalized one end (S+ [/////], S- [\\\\\\\\\\])
 - Two units with double splice (D+,D-)
- A few features
 - Thermally straighten fiber ends
 - Paint ends of tiles with BC620
 - Bond WLS in grooves with Epon815,TETA
 - Use MINOS 64 channel cookie


Thermal Splicing

- Splicing machine (U. of Mississippi design) used at Fermilab lab 7




Progress on Fiber Splicing

First test with “non-standard” fiber




Second test with 1.2 mm fibers - 90 % average



Fiber preparation

- 1.2mm Clear waveguide, spooled
- 1.2mm Wavelength Shifter, spooled
- Visual inspection with LED on end
- Measured on cutting template
- A clean, razor cut is made with 'HandiCutter'
- All fiber used will be characterized before and after splicing to assure quality



Fiber testing

- Fibers characterized with respect to each other
- Acceptance cut is 70% of average for group
- LED, photodiode, water couplant
- Three test runs each




Digitization
and readout

photodiode



green LED

Light Test of Waveshifting Fiber




44 separate pieces - no rejected fiber

Sigma of $\sim 10\%$

Thermal Fiber Straightening



- The quality and strength of a splice is improved by joining two perfectly flat, square ends because:
 - Fiber can be fixtured and fly cut more perfectly square if the natural bend of spooled fiber is removed.
 - Straight fiber can be fixtured more accurately in the splicing device.
- Temperature increased to 65°C and held for 1 hour.
- After cooling to room temperature, fiber retains straightness.

* Thermal treatment is also helpful to reduce stress on fibers when routing requires tight turns




Straightened Fiber

- The natural curvature of fiber off the spool.
- 30cm of each end straightened




Light Transmission after Straightening


- Clear fiber shows an average 12% net improvement after straightening one end and 22% after both.



- WLS fiber shows an average 22% net improvement after both ends were straightened.



Light Transmission – Composite Fibers




Spliced fibers tested with bend radii of 20, 9, 6 and 3 cm – no degradation of light transmission


LED Test of Spliced Fibers

photodiode

UV LED



Spliced Fiber - LED Test



Schedule, Manpower

- First detector plane completed by end of May
- Three more planes completed by the end of summer with the help of the team below plus additional manpower from Quarknet
- The team: Mike McKenna
Mark Vigneault
Sarah Schlobohm
Tom Burger

