


# Beam Dumps

SNOWMASS, 15 August, 2005

R. Sugahara  
KEK


- These are results studied by GLC Conventional Facility Study Group.  
(Study on ILC beam dump system is going to be started.)
- Radiation problem was studied in detail by S. Ban et al. of KEK Radiation Science Center.
- System and layout were studied and designed under the cooperation with Nikken Sekkei Ltd., Hitachi Engineering Co., Ltd. and Hitachi High-Technologies Corporation.



## Apertures ? Shields ?

Background neutrons, photons to be estimated by the BDS-SIM.

Better with large crossing angle of 20 mrad ?



Beam Dump  
1.6m-dia. x 10m

# Spec. for Water Beam Dump System

Dumped power of 500 GeV beam

--> 12 MW ( e+, e- 11 MW, Gamma 1 MW)

Dimension: 9 m long x 1.6 m diameter  
(25 radiation length)

Water pressure: 1 M Pa

Water flow: 333 m<sup>3</sup>/h

Amount of water in the dump: 20 m<sup>3</sup>

Recovery tank: 60 m<sup>3</sup> ... three times larger than beam dump

Amount of H<sub>2</sub> production in the water: 3L/s

--> H<sub>2</sub> Recombiner : 10 L/s ... three times larger than H<sub>2</sub> production

H<sub>2</sub> Recombiner must be placed higher than Beam Dump, and  
Recovery Tank must be lower than Beam Dump.

# Radiation issues

To estimate radioactivity in the water,  
Cross Section Calculation Code : PICA3/GEM

Amount of Radioactivity in the water

Be-7:	60 TBq
C-11:	96 TBq
N-13:	72 TBq
O-15:	280 TBq

Air ventilation system

Exchange the air in the dump hall (3200 m<sup>3</sup>) in 1.5 hours

Activation in soil around the dump hall

Na-22 in the soil is less than IAEA Exemption Level, 10 Bq/g


# Radiation issues contd.

Amount of Radioactivity in Ion-exchangers

Estimated using the data for the KEK Proton Synchrotron  
Cooling Water System


Nuclei	Half life	Amount of activity(GBq)	Dose $\mu\text{Sv/h@1m}$
Be-7	53.29Day	60000	428000
Co-58	70.86Day	57.6	7550
Co-57	271.7Day	14.7	258
Mn-54	312.1Day	12.9	1430
Co-56	77.23Day	4.96	2100
Co-60	5.271Year	1.59	485
Total			440000 $\mu\text{Sv/h}$

## Flow chart of cooling water system




# Purifier for primary cooling system (Two systems for safety)

## A system




## B system







# Flow chart for air conditioner



# Layout



**Cross-section View at A-A**

Rooms on the second floor

- (1) Operation room
- (2) H<sub>2</sub> recombiner room


- (3) Electricity room
- (4) Air conditioner room

- (5) Secondary cooling system
- (6) Primary cooling system

# Layout of 1F


Beam dump

(6) Primary cooling system




Recovery tank for  
beam dump water

## Layout of 1FB



# Layout of 2F

(2) H2 recombiner room (4) Air conditioner room



(1) Operation room (5) Secondary cooling system

# Summary


- Detailed study on following items is needed:
  - Beam dump structure
  - Beam window
  - Scenario how to change the beam window
  - How to move used beam dump to the storage room
  - How to move used radio-activated equipment to the storage room
  - Maintenance scenario for each equipment
  - etc. ....
- Need to study the case that tritium water in the beam dump leaks in the air.  
How to remove the water from the air completely.
- Need to update to ILC version
  - Beam power: 11MW --> 23MW
  - Power of bremsstrahlung-gamma: 1MW --> 2MW



# Dumpline : Layout

## GLC 1TeV

K. Kubo



Beam Spot  
at the 2nd FP

