

ISAC-II SC-Linac Cryogenic System at TRIUMF

Igor Sekachev
TRIUMF, Canada

Cryogenics Operations Workshop
May, 2006



Outline:

- Overview
- Cryogenic Design
- Cryomodules
- Refrigerator Commissioning
- Beam Acceleration with one Cryomodule
- SC-Linac and He-Distribution Installation
- SC-Linac Commissioning – Beam Acceleration
- Summary and Future

Overview





Cryogenics at TRIUMF




Quality
precise

Detector installed in solenoidal super conducting magnet, with end door of magnet yoke opened. Also shown are electronics and cables to read out the detector information.







Stage 0 - 2005 (Commissioned April, 2006)



Stage 1 - 2008



Cryogenic Design



Cryogenic Loads (Phase 1)

13W	13W	13W	13W	13W	Static Loads
32W	32W	32W	32W	32W	Active Loads




← Medium Beta →



Distribution	< 72W	< 4.0gm/sec
Static Loads	65 W	3.6gm/sec
Active Loads	160 W	8.9gm/sec
Total	300W	16.5gm/sec

Phase-1 Refrigerator (530W)

- ❑ Linde TCF50
 - ❑ 530W @ 4.5K and 0.7gm/sec liquefaction with LN2 pre-cooling
- ❑ Choice based on the following specification:
 - ❑ Expected Normal Loads
 - 140W static and 160W active → 300W
 - ❑ Cooldown mode (maximum liquefaction)
 - Phase 1 – 5.2gm/sec (150liq-ltr/hour)
 - ❑ Pressure variation specification
 - $dP/dt < 1 \text{ Torr/sec}$
 - $\Delta P < \pm 10 \text{ Torr}$




ISAC-II Cryogenics

The ISAC - II Accelerator Floor


Cold Box




LHe Dewar



Refrigerator Room



Compressor Room



Buffer Tank



Phase-1 Refrigeration (530W)

❑ LINDE supply

- ✓ Cold box
- ✓ Main compressor
- ✓ Recovery compressor
- ✓ ORS and gas management system
- ✓ Commissioning – March, 2005


❑ TRIUMF supply

- ✓ Installation of Linde components
- ✓ Helium dewar – Chalk River
- ✓ Buffer tank – 30000 USgallon
- ✓ Warm piping
- ✓ Cold distribution (DeMaCo)
- ✓ Helium purity meter

LINDE TCF50 Commissioned (Feb. 2005)




Cold Distribution




- Parallel supply feed from dewar through main header (4.5K)
- Cold helium return (<20K) during normal operation
- Warm helium return (>20K) to compressor suction used during cooldown

He Cold Distribution – Cryomodule


- Individual, vacuum jacketed, LN2 cooled lines for supply and return
- Field joints used to join supply and return for cryomodule to main trunk-line




Cold Distribution (Phase-1)



Nitrogen Distribution




Medium Beta Cryomodules



Medium Beta Cryomodule

- ❑ Cold mass suspended from lid
- ❑ LN2 cooled thermal shield, mu metal liner
- ❑ 120 L helium reservoir
- ❑ Single vacuum space for RF and thermal isolation



Lid Assembly in Assembly Frame



Vacuum Tank

- 1.9cm thick stainless steel (316L) with external reinforcing ribs
- L=176cm, W=99cm, H=196cm
- All services through 44 flanged ports on lid

Cryomodule Top Plate



Cryomodule Vacuum Tank



Assembly Frame

- For clean room assembly of cryomodule lid and contents including RF cavities and solenoid
- Top mounting surface and end plates mimic the vacuum tank top flange and beam ports for pre-alignment of cavities

Cryomodule Assembly Frame



Nitrogen Heat Shield

- 10mm ID copper tube soldered to copper sheet arranged in a box-like structure
- Copper, nickel-plated to reduce emissivity
- Solder applied on hot table without flux in inert gas environment
- Copper cooling tubes run in series
 - $L=36\text{m}$
 - $\Delta P=1.9\text{PSI}$ warm and 0.1PSI cold

Hot Table for Fluxless Soldering




LN2 Box being lowered into Cryomodule



Helium Reservoir and Mounting Frame

- Helium reservoir
 - 120 Ltr
 - 316L electropolished stainless steel
- Mounting frame
 - 316L electropolished stainless
 - Supports cavities and solenoid
 - Suspended from struts on lid

Helium Reservoir



Mounting Frame and Support Struts



Medium Beta Cavity

- ❑ Prototype developed in collaboration with LNL, Italy and fabricated at Zanon, Italy
- ❑ Twenty cavities manufactured by Zanon
- ❑ Four cavities chemically polishing at CERN
- ❑ Remaining 16 cavities polished at JLAB
- ❑ All cavities tested at TRIUMF

Chemical Polishing at CERN




Prototype Cavity



Frequency Measure at Zanon



Four Cavities at TRIUMF



RF Systems

□ RF power

- Provide useable bandwidth by overcoupling
- Require $P_f=200\text{W}$ at cavity for $f_{1/2}=20\text{Hz}$ at $E_a=6\text{MV/m}$, $\beta=200$

□ Coupling loop

- Developed LN2 cooled loop
- $<0.5\text{W}$ to LHe for $P_f=250\text{W}$


□ Mechanical tuner

- Precise (0.3~Hz), fast ($>50\text{Hz/sec}$) tuner with dynamic range of 8kHz and coarse range of 32kHz


□ Tuning plate

- Spun, slotted, 'oil-can' tuning plate to improve tuning range

Forward power required for $E_a=6\text{MV/m}$ and given bandwidth





Coupling Loop



Mechanical Tuner



Cryomodule Components




Superconducting Solenoids

- ❑ Beam Focusing in the SC-Linac is provided by superconducting solenoids ($B \leq 9\text{T}$)
- ❑ End fringe fields controlled with active 'bucking' coils ($B_{\text{cavity}} \leq 0.1\text{T}$)
- ❑ Solenoids for Medium and High-beta Cryomodules fabricated at Accel, Germany
 - See table for specifications

Prototype Solenoid at Accel





	Low β	Med β	High β
Field	9T	9T	9T
Bore	26mm	26mm	26mm
Number	4	5	3
Eff. Length	16cm	34cm	45cm




Cryomodule Alignment

- ❑ the tolerance on solenoid and cavity misalignments are $\pm 200 \mu\text{m}$ and $\pm 400 \mu\text{m}$ respectively
- ❑ collaboration with INFN, Milano, Italy on the development of a Wire Position Monitor for cold alignment measurement with precision of $20 \mu\text{m}$
 - Stripline monitor attached to each device driven by RF signal along a reference wire

WPM Monitors on Cavities




Wire Position Stripline Monitor




Cryomodule Distribution

- Cryomodule cooled by forcing helium to bottom of each cold element through a distribution spider




Cryomodule Cold Tests




Medium Beta Cryomodule

- ❑ Cryogenic alignment tests
- ❑ RF cold tests
- ❑ Acceleration test - Clean Room - Nov, 2004
- ❑ Acceleration test - Vault - June, 2005





Cryomodule Assembly in Clean Room



CRYOMODULE Assembly in ISAC-II Clean Room



CRYOMODULE Cold Test in ISAC-II Clean Room




He & N2 Gas Flow Meters



Vaporizers


Medium Beta Cryomodule

- Thermometry (29 Lakeshore silicone diodes)




Cryomodule Pre-cool Test

- Cryomodule cooled with Helium April 23, 2004
- Pre-cool manifold and 'spider' worked well to cool cavities and solenoid uniformly




Pre-cool Temperatures (Helium Space)



- solenoid top
- solenoid bottom
- cavity 1
- cavity 2
- cavity 3
- cavity 4
- helium reservoir (upstream)
- helium reservoir (downstream)
- Helium flow (ltr/hour)

Cryomodule Cooldown Data (Aug. 2005)



- Cryomodule (SCB1) cooled with LINDE TCF-50
- Three-position valve on `spider' worked well to cool cavities and solenoid



Cryomodule Static Load – Test 1, 2


- April 25, 2004 – First cooldown
 - After thermalization, boil-off equivalent to **11W** static load

- July 2, 2004 – Second cooldown
 - After thermalization, boil-off equivalent to **16W** static load




Cryomodule Static Load – Test 3

- Nov. 3, 2004 – Third cooldown
 - 180ltr LHe accumulated in cryomodule
 - After thermalization boil-off equivalent to **13W** static load





LN2 Consumption

- Regulated exhaust flow at constant pressure
 - 6.2 Ltr/hr produced 80K shield
 - 4.7 Ltr/hr warmed shield to about 120K





Alignment Calibration

- Optical targets in first and last cavity were periodically measured with telescope to calibrate the temperature contraction of WPM brackets





Alignment Repeatability

- Cryomodule thermally cycled three times from room temperature to LN2 temperature
 - WPM data analyzed to note repeatability of alignment at cold temperatures
 - Alignment repeatable to within 80 microns vertically and to within 120 microns horizontally




Cavity Performance

- All cavities locked simultaneously at ISAC-II specifications (6 MV/m and 106.08 MHz)
- Low level Q values all $>1e9$
 - Mu metal field reduction is adequate
- Cavity performance matches single cavity tests with high pressure rinsing and clean techniques during assembly



Solenoid Test

- Base Q's measured before solenoid test
- Ramp up solenoid to 9T
 - Cavities 2 and 3 on
 - No quench of cavities or solenoid
 - No change in cavity Q
- Cold mass warmed above transition
- Q's measured after second cooldown
 - No change; $Q > 1e9$
 - Residual field tolerable



No negative impact on cavities from operation of solenoid


Refrigerator Commissioning

Feb – March, 2005

Helium / Water Heat Exchanger



Commissioning Hardware



- Transfer line

- For liquid removal/recovery test
- Liquid goes through large water bath heat exchanger and back to compressor suction

- Gas vent line


- For measured liquifaction load
- Gas is drawn off through smaller water bath heat exchanger, then through gas meter and flow valve and back to compressor suction

- Dewar equipped with 650W heater and level probe

- Dewar static loss less than 0.5W (25 year old Cryofab dewar)


Liquefaction Test

- Measure rise in level while monitoring dewar pressure (want 1.3Bar – 990 Torr)
- Displaced vapour returned back to cold box and enhances liquefaction




Refrigeration Test

- Measure heater power required to maintain constant level
 - Adjust bleed valve to set liquefaction load (20 Ltr/hr)
 - Maintain constant dewar pressure ~ 1.3 Bar



Refrigeration Acceptance Test


- Dewar heater power is raised until a constant level is reached at a constant dewar pressure.



Parameter	With LN2
Refrigeration (W)	610
Guaranteed	530
Liquifaction (g/s)	6
Time (hr)	24
LN2 (l/hr)	55
Pressure (Torr)	1045


- Refrigeration is 350W without LN2 and no liquefaction load

Liquefaction Test in Normal Mode



Acceptance test

- Demonstrated **225 Ltr/hr** based on rising level in the dewar
- Collected a total of 825ltr for 221min
- Linde guaranteed **180 Ltr/hr**




Parameter	With LN2
Rising level (l/hr)	225
Rising level (g/s)	7.5
Time (min)	221
LN2 (l/hr)	80
Pressure (Torr)	991


Power Saving Modes (with LN2)

Mode	Refrig (W) or (6g/s)	Freq (Hz)	Discharge P (Bar)	Wall Power
Normal	610	60	13	1.0
Eco1	375	40	13	0.70
Eco2	280	35	11.8	0.59
Standby	190	29	11.5	0.53



Refrigerator Power vs. Compressor Speed



Power Test




Mode Switch Test




Measurements

- Starting from normal mode the plant was switched to Eco1 then Eco2 then Standby stopping for two hours in each mode.
- Each mode was achieved without excessive transient
- Equilibrium was established after ~1/2 hr
- An instability in the suction pressure was observed for the three low power modes up to a maximum of +/- 10 mbar for Standby mode


Suction Pressure Stability




Normal Mode ± 1.5 mbar



Eco1 Mode ± 4.5 mbar



Eco2 Mode ± 6 mbar



Standby Mode ± 7 mbar

- Modulation in suction pressure was observed for the three lower power modes
- Frequency of modulation $\sim 1/40$ Hz
- Linde improved instability in the suction pressure by correcting the main compressor settings


March 8, 2005

Nice cold champagne!




**ISAC-I Beam Acceleration
with one Cryomodule
(Vault Test – June, 2005)**


SCB1 Vault Test




Vault Test Plumbing



Helium Flow Schematic



Refrigerator Operation



Refrigerator operated in continuous mode after an initial startup period.


LHe level in cryomodule and supply dewar regulated manually by supply transfer line valve and heaters in each volume

Refrigerator warmed up after two-week successful run

Acceleration – July 7, 2005

- Injected $^{26}\text{Mg}6+$ from ISAC at 1.5MeV/u into SCB1
- Measured final energy with Si detector
- Achieved 3.5MV acceleration from three cavities
 - Corresponds to average values of $E_a=7.4\text{MV/m}$ and $E_p=37\text{MV/m}$
 - One cavity not operational

SCB1 Acceleration



**SC-Linac
and
Helium Distribution System
Installation**

ISAC-II SC-Linac Installation (Nov, 2005)




He-Distribution Installation (Nov, 2005)




Field Joint






SC-Linac Commissioning

LINAC Commissioning, April 2006




Medium Beta Cryomodule



Lid Assembly in Assembly Frame



Helium Control




- Dewar heater power is used to calibrate the rf power required for acceleration
- Helium supply valves for each module regulate on the level in each module
- Dewar heater used to regulate level in the supply dewar
- Dewar heater reduced by 80W when cavities turned on

The Good News

- All cavities locked with most requiring only automated start-up
- Set-point of 1800 gives an average gradient of 5.6MV/m at 80 of RF power (4W/cavity)
- Set point of ~2000 should give an average gradient above 6MV/m for ~7W/cavity
- First acceleration demonstrated with over 220MeV Ca40

First Beam Acceleration Results



- ^{40}Ca beam at $10+$ is accelerated through ISAC-DTL to 1.5MeV/u
- Beam is accelerated through the twenty ISAC-II superconducting cavities to reach a final energy of $\sim 5.5\text{MeV/u}$ or a total energy of 220MeV
- Average cavity gradient is 5.6MV/m with an average rf power consumption of 4W/cavity – a total RF power of 80W

Summary of Cold Tests

□ Cryomodule cold tests very successful

- Established cold alignment
- Proved cryogenic and RF integrity
- Pre-test for linac controls and acceleration

□ Highlights

- All cavity Q's $> 1e9$
- 20 cavities locked simultaneously at ISAC-II specifications ($E_a=6\text{MV/m}$, $E_p=30\text{MV/m}$ at 106.08MHz)
- 9T solenoids operated without effecting adjacent cavities
- Static load is within design limits (13W) for all 5 Cryomodules
- Accelerated 2.8MeV alphas to 9.4MeV (Nov, 2004)
- Accelerated beam $^{26}\text{Mg}^{6+}$ delivered from ISAC-I (June, 2005)
- Accelerated beam $^{40}\text{Ca}^{10+}$ to 220 MeV with SC-Linac (Apr, 2006)

Summary

- LINDE TCF50 installed, commissioned and now operational with He distribution system, supplied by DeMaCo.
- SC-Linac (first stage) commissioned in April, 2006. The first beam accelerated.
- Second stage of SC-Linac and second 500W class refrigerator planned for installation in 2007 - 2008.

Thank You

