

SLAC-TN-88-2  
June 1988

QUALITY ASSURANCE

MANUAL \*

Volume II

Appendices

JUSSI E. OIJALA

*Stanford Linear Accelerator Center*

*Stanford University, Stanford, California, 94309*

\*-----  
Work supported by the Department of Energy, contract DE-AC03-76SF00515

**I N D E X**      **VOLUME II: Appendices**

<b>Appendix A:</b>	<b>1</b>
<b>Quality Assurance Policies and Standards in Mechanical Systems</b>	
A.1: Policy for Quality Review of Machine Components	2
A.2: Project Engineering Standards, General Drafting Instructions, DS-016-110-01	4
A.3: Quality Assurance Practices for the Survey and Alignment Group	18
A.4: Examples of Documentation in Production	21
A.5: Examples of MOSG Installation and Removal Procedures	32
A.6: Example of a Weekly Status Report	47
<b>Appendix B:</b>	<b>49</b>
<b>Quality Assurance Policies and Standards in Klystron &amp; Microwave Department</b>	
B.1: Quality Assurance Procedures for Incoming Materials	50
B.2: Summary of QA Activities During Different Stages of Tube Manufacturing	57
B.3: Quality Assurance in Klystron Manufacturing	59
B.4: Quality Assurance Procedures in Klystron Testing	62
B.5: Documentation Process for a Single Part (Anode Housing) in Klystron & Microwave Department	64
<b>Appendix C:</b>	<b>156</b>
<b>Quality Assurance Policies and Standards in Electronics Department</b>	
C.1: List of Procedures and Standards in Electronics Production	157
C.2: Examples of Documentation in the Electronics Department	160
<b>Appendix D:</b>	<b>167</b>
<b>Quality Assurance Policies and Standards in Plant Engineering</b>	
D.1: Quality Assurance Plans and Policies of Different Groups in Plant Engineering	168
<b>Appendix E:</b>	<b>177</b>
<b>Quality Assurance Policies and Standards in Accelerator Department</b>	
E.1: Quality Assurance in Software Engineering	178
E.1a: Examples of Documentation in Software Design Review	179
E.1b: SLC Coding Standards (VAX Fortran)	184
E.2: Examples of Documentation in Accelerator Department	191
<b>Appendix F:</b>	<b>198</b>
<b>Quality Assurance Policies and Standards in Research</b>	

<b>Appendix G:</b>	199
<b>Quality Assurance Policies and Standards in Purchasing</b>	
G.1: Examples of Documentation in Purchasing	200
<b>Appendix H:</b>	204
<b>Quality Assurance Policies and Standards in Experimental Facilities Department</b>	
H.1: Examples of Documentation in EFD	205
<b>Appendix I:</b>	244
<b>Quality Assurance Policies and Standards in Special Projects</b>	
I.1: Quality Assurance in SLD Project	245
I.1a: General Quality Control/Quality Assurance Instructions for SLD	246
I.1b: A List of Technical Specifications	248
I.1c: Examples of Documentation in SLD	252
I.2: Quality Assurance in Mark II Project	328
I.2a: Personnel, Management, Funding, and Time Scale Issues in Mark II Project	329
I.2b: Mark II Articles of Organization	335
I.2c: Mark II Publication Policies	338
I.3: Quality Assurance in Mark III Project	342
I.3a: Examples of Documentation in Mark III Project	343
I.4: Quality Assurance in Polarization Project	352
I.4a: Proposal for Polarization at the SLC	353
<b>Appendix J:</b>	378
<b>Quality Assurance Policies and Standards in SSRL</b>	
<b>Appendix K:</b>	379
<b>Other Quality Assurance Issues</b>	
K.1: Unusual Occurrence Reporting System	380
K.2: SLAC Committees	385
K.2a: Mechanical Engineering Safety Inspection	386
K.2b: Hazardous Equipment Approval Information	389
K.3: SLAC Standards	394
K.3a: A List of Standards by the SLAC Drafting Standards Review Group	395

**APPENDIX A**

**Quality Assurance Policies and Standards in Mechanical Systems**

## **Appendix A.1: Policy for Quality Review of Machine Components**

1. Design projects for any of the SLAC machines (SPEAR, PEP, LINAC, Damping Rings, BSY, Arcs, and Final Focus) shall be reviewed by the Machine Operations Support Group (MOSG). A formal design review shall be held for major projects and shall include consideration of:
  - A. Engineering factors - stresses, thermal problems, etc.
  - B. Design factors - function, alignment, I&C interfaces, etc.
  - C. Fabrication - tolerances, materials, etc.
  - D. Installation plans
  - E. Schedule and budget
2. All final designs of new components and major design changes that affect the function or installation must be approved by the respective MOSG area engineer and the area operations manager (Accelerator Department). Installation and assembly drawings must be signed by the area engineer.
3. All vacuum component drawings must be reviewed and approved by the Vacuum Group.
4. All magnet drawings must be reviewed and approved by the Electronics/Power Supply Group.
5. All supports must be reviewed by the Alignment Group.
6. Installation drawings are to be reviewed by the installation technician supervisor.
7. All drawings of hardware to be installed in one of the machines or tooling to fabricate hardware must be reviewed by the MOSG Design Group Supervisor before release to the MFD, Purchasing or Document Control. The review will be for overall quality, completeness, and conformance to drawing standards. Drawing revisions need not be reviewed unless they reflect major design changes as defined above.
8. During the fabrication of components, MFD will maintain a file of prints which will be marked to indicate problems found and changes made in the course of the job. All changes must be approved by the responsible design engineer. These marked prints will be returned to the respective design group supervisors. The supervisors, along with the project engineers, are responsible for insuring that "as built" changes are made to the drawings.
9. During installation of components, MOSG technicians will mark prints with "as installed" information. These prints will also be forwarded to the Design Supervisors for drawing revision.

**Appendix A.2: Project Engineering Standards  
General Drafting Instructions  
DS-016-110-01**

(This is being updated on a continuous basis)

TABLE OF CONTENTS

SCOPE . . . . . 1  
 Purpose . . . . . 1  
 Exceptions . . . . . 1  
 Consulting . . . . . 1  
 Additional Drafting Standards . . . . . 1

APPLICABLE DOCUMENTS . . . . . 2  
 SLAC Standards - Design . . . . . 2  
 SLAC Fabrication and Process Standards . . . . . 3  
 Industry Standards . . . . . 4  
 OTHER . . . . . 6

REQUIREMENTS . . . . . 6  
 Format . . . . . 6  
 Drawing List . . . . . 8  
 Material List . . . . . 8  
 Checking . . . . . 9  
 Completed Drawings . . . . . 9  
 Policy for Archiving Manual and CADD Produced Drawings . . . . . 9

DRAFTING CATEGORIES . . . . . 10  
 Machine and Electro-Mechanical . . . . . 10  
 Piping . . . . . 11  
 Electrical/Electronic . . . . . 11  
 Architectural . . . . . 12  
 Structural . . . . . 12



## SCOPE

### 1.1 Purpose

This document describes requirements for drafting practices and shall apply to subcontract and formal project drawings.

### 1.2 Exceptions

SLAC Prototype Format drawings to be used by "in-house" shop services need not conform to these requirements except where specified in SLAC DS-016-110-10.

### 1.3 Consulting

Drafters shall consult with their supervisors when in doubt or in cases not covered by this standard.

### 1.4 Additional Drafting Standards

For additional drafting standards in specific disciplines, refer to the following:

1. DS-016-110-04 - Mechanical Engineering Design and Drafting
2. DS-016-110-05 - Electronics Engineering Printed Circuit Board Design and Drafting
3. DS-016-110-06 - CADD System Design and Drafting

APPLICABLE DOCUMENTS

The latest issue of the following documents shall form a part of this standard to the extent specified herein. SLAC Standards shall take precedence in event of conflict among SLAC Standards and Documents listed under paragraph 2.2 and 2.3.

2.1 SLAC Standards - Design

<u>Document No.</u>	<u>Title</u>
	<u>ARCHITECTURE</u>
DS-011-200-01	Building Concrete
DS-011-200-02	Building Masonry
	<u>ELECTRICAL</u>
	<u>Plant Facilities</u>
DS-013-140-01	General
DS-013-210-01	Service Voltages
DS-013-220-01	Equipment Phasing
DS-013-230-01	Wiring Identification
DS-013-230-02	Conduit Identification
DS-013-320-01	Receptacles and Plugs
DS-013-320-02	Wiring Methods - Fixed Installations
DS-013-320-04	Wiring Methods - Portable and Temporary Installations
DS-013-410-01	Motor Control Centers - Controls and Starters

DS-013-410-02 Electric Motors

DS-013-610-01 Light Intensity Values

ELECTRONICS AND MICROWAVE

Wiring

DS-014-110-01 Identification Coding, Insulated  
Hookup Wire

DS-014-110-02 Color Designation, Multi-  
Conductor, Paired Comm. Cable

Equipment

DS-014-200-01 Indicator Lights

General

DS-014-710-01 Color Code for Resistors

MECHANICAL UTILITIES

Plumbing

DS-015-300-02 Identification of Piping

DOCUMENT CONTROL

AP-041-300-01 Document Control Procedures

DS-016-110-10 SLAC Prototype Format

DS-016-310-01 Engineering Document Numbering System

2.2 SLAC Fabrication and Process Standards

FP-022-110-02 Painting Standards for Buildings and Surfaces

FP-022-110-03 Minimum Requirements for Paint Finishes

FP-022-110-04 Identification and Marking of Metallic  
and Non-Metallic Surfaces

FP-023-100-01 Welding of Metal and Metal Alloys

FP-023-100-02	Soft Soldering for Electronics
FP-023-100-03	Welding Aluminum Vacuum Systems
FP-023-100-04	Welding of OFHC High Vacuum Systems
FP-024-100-01	General Heat Treating Standards for Steels
FP-024-100-02	Heat Treatment for Aluminum
FP-027-100-01	Plating Standard for Corrosion Protection
FP-027-100-02	Chemical Film Treatment of Aluminum
FP-027-200-01	Metal Degreasing
FP-027-200-02	Surface Cleaning of Stainless Steels
FP-027-200-03	Surface Cleaning of Aluminum
FP-027-200-04	Surface Cleaning of High Carbon Steels
FP-027-200-05	Surface Cleaning of Low Carbon Steels
FP-027-200-06	Surface Cleaning of Copper
FP-027-200-07	Surface Cleaning of Magnesium
FP-028-100-01	Mechanical Engineering Safety Inspection - Pressure and Vacuum Vessels
FP-202-631-14	Fabrication of Ultra High Vacuum Components

### 2.3 Industry Standards

DOD-STD-100C	Engineering Drawing Practices
ANSI-Y1.1	Abbreviations for Use on Drawings and in Text
ANSI-Y14.1	Drawing Sheet Size and Format
ANSI-Y14.2Mx	Line Conventions and Lettering
ANSI-Y14.3	Multi and Sectional View Drawings
ANSI-Y14.4	American Drafting Standards Manual - Section 4 - Pictorial Drawing

ANSI-Y14.5M	Dimensioning and Tolerancing
ANSI-Y14.6	Screw Thread Representation
ANSI-Y14.6aM	Screw Thread Representation (Metric Supplement)
ANSI-Y14.13M	Mechanical Spring Representation
ANSI-Y14.15	Electrical and Electronics Diagrams
ANSI-Y14.15a	Interconnection Diagrams Supplement
ANSI-Y14.15b	Interconnection Diagrams Supplement
ANSI-14.17	Fluid Power Diagrams
ANSI-Y14.36	Surface Texture Symbols
ANSI-Y32.2	Graphic Symbols for Electrical and Electronics Diagrams
ANSI-Y32.4	Graphic Symbols for Plumbing Fixtures for Diagrams Used in Architecture and Building Construction
ANSI-Y32.9	Graphic Symbols for Electrical Wiring and Layout Diagrams Used in Architecture and Building
ANSI-Y32.16	Reference Designations for Electrical and Electronics Parts and Equipment
ANSI-Z32.2.3	Graphical Symbols for Pipe Fittings, Valves and Piping
ANSI-Z32.2.4	Heating, Ventilating, Air Conditioning
ANSI-C37.2	Electric Power System Device Function Numbers
ANSI/NFPA-172	Fire Protection Symbols for Architectural and Engineering Drawings.

2.4 OTHER

AIA	American Institute of Architects "Architectural Graphic Standards"
AISC	American Institute of Steel Construction Publication "Manual of Steel Construction"
ACI-315	American Concrete Institute Publication "Manual of Standard Practice for Detailing Reinforced Concrete Structures"
AWS-A2.1	Standard Welding Symbols.

REQUIREMENTS

3.1 Format

1. Size - Approved sizes are "A", "B", "C", "D", "E", "F", and "R" roll. Use of "A" size and "R" size drawings is discouraged. Roll size shall not exceed 36" in width nor 12 feet in length.
2. Drawing Numbering - Numbers shall be assigned to drawings per AP-041-300-01 and DS-016-310-01. Numbers shall be stenciled in space below title block. Letter and number heights shall be 1/4" on all drawings except 5/32" on "A" and "B" sizes.
3. Titles - Titles of drawings shall be stenciled in vertical, bold face within title block. Lettering heights shall be 3/16" on all drawings except 5/32" on "A" and "B" sizes. \*Minimum information shall be as follows:

<u>Definition</u>	<u>Example 1</u>	<u>Example 2</u>
a. Project	Beam Switchyard	Klystron Gallery
b. Associated System	AC Electric Services	Vacuum System
c. Subject	Coaxial Cable Layout	6" Valve

\* Abbreviated titles shall not be used unless approved by drafting supervisors. No two drawings containing the same base

document number shall have identical titles, except in the case of multiple sheet drawings.

4. Lettering and Line Work - Lettering and Line work shall be capable of clear reproduction during microfilming per ANSI Y14.2M.
5. Notes - Drawing notes shall be indicated in the following manner:

NOTES

1. CLEAN AND DEGREASE




2. STAMP P/N XX




3. TEST PER ST-XX

See Fig. 1 for preferred locations of notes. Numbers, enclosed by a 3/8" or 1/2" dia. circle and a square, shall be used for "flagging" special notes applying to specific areas of a drawing. A corresponding symbol shall be placed near affected area. Use of arrow leader shown above is recommended.

6. Revisions - Sequential numbers enclosed by the triangular symbol  shall be used for indicating revisions on the face of the drawing in area where the change occurred. The corresponding number shall be placed in revision box under "REV" column and change description and date inserted.


Entries shall be made in the revision block as follows:

REV	DESCRIPTION	DRN.	CHK.	APP.	DATE
	Dim. 5/8" was 1/4"; Deleted Note 1	VP	HYI	<i>Rbf</i>	4/13/88

7. Drawing sequence - Next assembly or next associated drawing shall be noted directly above title block, e.g., NEXT ASSEMBLY: SA-190-184-01. (Revision indicator is omitted from all referenced drawings.)
8. Orientation - All plant arrangement or installation plan views shall have "North Arrow", North direction always to top of sheet or to right side of sheet. Beam direction shall be indicated when showing portions of the Accelerator.

9.

Example



10. Scale - Drawing Scales shall be per DOD-STD-100C.
11. Abbreviations - All abbreviations shall be per ANSI-Y1.1.
12. Welding Symbols - Welding Symbols shall be per AWS A2.1
13. Views and Sectioning - Views and sections shall be per ANSI-Y14.3.

### 3.2 Drawing List

At the beginning of a given project, a tentative drawing list shall be prepared showing assigned drawing numbers and exact titles of drawings required to complete project. Allowance should be made for insertion of additional drawings as required. Drawing list shall be updated at end of project and shall become a formal document with an assigned document number (See Fig. 3). Drawing List number and title shall be first item listed.

### 3.3 Material List

All assembly and subassembly type drawings shall include a material list. Assembly material lists shall tabulate only subassemblies, parts and fasteners that are required for final assembly. Items not required for final assembly, and previously listed on subassembly material lists shall not be repeated. Subassembly material lists shall tabulate only required parts and materials. A Material List must be placed on the 8-1/2" X 11" M.L. form (Fig. ) or on the face of the drawing (Fig. ). (See Fig. 4).



### 3.4 Checking

Drawings shall be checked by a checker designated by a drafting supervisor prior to release for review and/or approval. Checkers shall use the following colors:

1. Red - to be used for deletions.
2. Green - to be used for additions.
3. Yellow - "Leave as is".
4. When checking has been completed, check prints shall be reviewed and approved by the responsible engineer, affected drawings revised, check prints returned to checker and tracings signed off.
5. When checking has been completed on markup prints, the markups shall be reviewed and approved by the cognizant engineer, affected drawings revised and signed off, and the markups returned to the checker.

### 3.5 Completed Drawings

Drawings, when approved, shall be incorporated into the document control system in accordance with AP-041-300-01.

### 3.6 Policy for Archiving Manual and CADD Produced Drawings

#### 1. Original Drawings

- a. No original drawing, (RO,CO) will be accepted into Document Control for storing unless it contains (1), the Designer/Drafter's name, which may be printed; (2), the Checker's full signature; (3), the Engineer's full signature, and (4), the full signature of the responsible person in the Approval block.

#### 2. Revised drawings

- a. For revised manually produced drawings, R1, R2, etc., the signatures will remain as is in the main title block area. The Revision Block area will require the Drafter's initials as well as the Checker's and the Approver's initials.

- b. For CADD produced Original drawings (CO), there will be no pen or pencil marks on the face of the drawing, other than the signatures as described in 1a, above.
- c. For CADD revised drawings (C1,C2,etc.), the only permissible pen or pencil marks on the face of the drawing will be at the Revision Block for Drafter/designer, Checker, and Approver initials. The Title Block signatures may or may not be signed but will be typed in by the CADD designer/Drafter.

### DRAFTING CATEGORIES

#### 4.1 Machine and Electro-Mechanical

The method of drafting to be used shall be per ANSI Standards (Reference Page 1).

- 1. Tolerances and Dimensions - Dimensioning shall be per ANSI-Y14.5M. All assemblies and weldments shall have their overall size dimensioned for reference purpose.
- 2. Screw Threads - Thread and hole call outs shall be per ANSI-Y14.6.
- 3. Surface Roughness - Finish call out shall be per ANSI-B46.1.
- 4. Item Call Out - Items on the face of an assembly or subassembly shall be identified by the appropriate material list item number enclosed in a 1/2" diameter circle with an arrowed leader pointing to the item, e.g.,



#### 4.2 Piping

1. Piping Detail Sheets (isometric) - Drawings showing piping details shall be shown on "B" size sheets and shall include a material list per Figure 6. Details shall be drawn in isometric form.
2. Piping Layout - Drawings showing installation of complete systems conform to Figure 7. Piping layouts are comparable to a mechanical top assembly drawing.
3. Piping Diagrams - See Figure 8
4. Section and Details - See Figure 9
5. Instrument Piping - See Figure 10
6. Dimensioning - Layouts and details shall be dimensioned to the nearest foot -inch, e.g., 1'-10-1/2" or 6'-9". In cases where a dimension is less than a foot, it shall be indicated as: 6" or 2-1/2".
7. Symbols - Piping symbols shall be per ANSI-Z32.2.3.

#### 4.3 Electrical/Electronic

1. Symbols - For schematic and wiring diagrams, symbols shall be per ANSI-Y32.2. Component reference shall be per ANSI-Y32.16. For architectural type electrical drawings, symbols shall be per ANSI-Y32.9.
2. Schematic Diagrams - Drawings showing circuitry shall be arranged top to bottom, or left to right. Power or signal input shall be located at the extreme top or left on drawings, with output flowing toward or terminating at the bottom or right hand side, leaving the extreme right hand side open for notes (Fig. 11).
3. Equipment Drawings - Assembly or part drawings of equipment, chassis, or components shall conform to Paragraph 4.1.

#### 4.4 Architectural

Drawings and symbols shall conform to American Institute of Architects "Architectural Graphic Standards".

#### 4.5 Structural

Detail drawings shall conform to American Institute of Steel Construction "Structural Steel Detailing" and "Manual of Steel Construction" (Fig. 12a and Fig. 12b). Concrete structural drawings shall conform to American Concrete Institute "Manual of Standard Practice for Detailing Reinforced Concrete Structures" (ACI-315).

**Appendix A.3: Quality Assurance Practices for the Survey and Alignment Group**

Alignment at SLAC can be broken into two basic methods: that which produces coordinates with redundant observations and that which does not. In Method I observations are taken and then mathematically adjusted to produce best estimates for point coordinates. Method II entails the direct observation of calculated offsets using surveying instruments and optical tooling scales. The main aspects of quality assurance are discussed below:

### 1. Controlling Quality

Method I relies on redundant and independent observations, which are reduced as a group in a least-square adjustment. The result is not only coordinates but also statistics describing the quality of the whole survey and of each individual observation. This data can be analyzed using well established statistical methods, to determine if the data conforms with the requirements.

Method II, which will be gradually replaced by Method I, has no such statistical basis for error detection. In all cases check observations are taken to detect errors in measurements and calculations. In many cases extra reference marks are provided on instrumentation which provide independent checks. These are used whenever available.

### 2. Corrective Action

In Method I, blunder detection programs are utilized which flag possible erroneous observations for further examination. If no obvious problems can be found the offending data is reobserved. If the observation procedure is flawed, steps are taken to evaluate this and implement the necessary changes.

In Method II, calculations and observations are checked until a cause for the problem is found. After it is corrected, procedures are examined and corrected as necessary. If possible, further checking procedures are established.

Observational, computational and checking procedures are evaluated for both methods after failure occurs. If changes are warranted they are instituted immediately, if possible.

### 3. Worker Motivation

In both cases, an organized effort with clearcut goals and purposes must be maintained. The workers are motivated by not only an understanding for the need of quality assurance but more importantly by their pride in a job well done. This feeling can be fostered and maintained by a staff which approaches a project or problem in a systematic and logical manner with realistic short term and long term goals clearly stated.

#### 4. Evaluation of Effectiveness

If the program is working, standardized methods have fewer problems with better results and less time expended, and the workload of old problems is kept to a minimum.

Alignment and surveying methods can be presented for evaluation, including computational as well as observational methods. Also, paper as well as computer records of past projects can be examined for proper form and corrections of ongoing problems.

#### **Appendix A.4: Examples of Documentation In Production**

Shop Traveler Document (1)

SLAC Metal Stores Work Order (1)

Daily Time Report - Light Fabrication Shop (1)

Vacuum Lab Traveler (1)

Vacuum Process and Testing Traveler (1)

Job Description Form - Fabrication Shop (1)

Job Card, Plating Shop - Vacuum (1)

Job Card, Plating Shop - General (1)

Overtime Request - Mechanical Fabrication Shops (1)

Transport Box Specification - Plating Shop (1)



(CIC) CARLS IN CHARGE

Page No. 2  
01/20/88

JOB/TASK ROUTE SHEET  
Shop Traveler Document  
Tasks by Sequence Number  
=====

Job Title SLD-CENT.DRIFT CHAM. TRAY ASSY. (395) Priority 521  
Cus No SLD Cus Name SLD GROUP Contact J GRANDOV x3166 Job Open 01/19/88 Job Qty 1  
Job No 002472 Ref Code W.O. # 22-1376-B Coord KNIGHT Release 01/19/88 Est Start 02/02/88  
Assemble into Job - No sub-assemblies 0 Due Date 02/29/88 Est Finish 02/17/88

Seq No.	Work Center	Operation Description	Task Qty	Qty To Go	U/M	Time To Go	Estimated Start Date	Comments
0150	LIGHT FAB. MACH.	PF 241-316-15-CO AXLE,ROLLER	1	1	EA	1.5	02/08/88	GIVE PART TO REQUESTOR
0160	LIGHT FAB. MACH.	PF 241-316-16-CO LEVER,CRIMP	1	1	EA	2.0	02/09/88	GIVE PART TO REQUESTOR
0170	LIGHT FAB. MACH.	PF 241-316-17-CO ARM,TENSION ADJUST.	1	1	EA	1.5	02/09/88	GIVE PART TO REQUESTOR
0180	LIGHT FAB. MACH.	PF 241-316-18-CO YOKE,CRIMP	1	1	EA	6.0	02/09/88	GIVE PART TO REQUESTOR
0190	LIGHT FAB. MACH.	PF 241-316-19-CO AXEL,SPOOL	1	1	EA	1.0	02/10/88	GIVE PART TO REQUESTOR
0200	LIGHT FAB. MACH.	SA 241-316-20-CO BLOCK,ROLLER	1	1	EA	1.5	02/10/88	GIVE PART TO REQUESTOR
0210	LIGHT FAB. MACH.	PF 241-316-21-CO ROLLER	1	1	EA	1.0	02/10/88	MAT. ORDERED,GIVE PART TO REQUESTOR
0220	LIGHT FAB. MACH.	PF 241-316-22-CO FRAME,MOUNTING	1	1	EA	3.0	02/11/88	GIVE PART TO REQUESTOR
0230	LIGHT FAB. MACH.	PF 241-316-23-CO GUARD,SPOOL	2	2	EA	4.0	02/11/88	GIVE PART TO REQUESTOR
0240	LIGHT FAB. MACH.	PF 241-316-24-CO CAP,ROLLER	1	1	EA	1.0	02/12/88	GIVE PART TO REQUESTOR
0250	LIGHT FAB. MACH.	PF 241-316-25-CO BRACKET "A",MOTOR	1	1	EA	0.8	02/12/88	GIVE PART TO REQUESTOR
0260	LIGHT FAB. MACH.	PF 241-316-26-CO BRACKET "B", MOTOR	2	2	EA	1.5	02/12/88	GIVE PARTS TO REQUESTOR
0270	LIGHT FAB. MACH.	PF 241-316-27-CO BRACKET,MTG. PLATE	1	1	EA	3.0	02/12/88	GIVE PART TO REQUESTOR
0280	LIGHT FAB. MACH.	PF 241-316-28-CO SLEEVE,BUSHING	1	1	EA	1.0	02/15/88	GIVE PART TO REQUESTOR

# SLAC METAL STORES

## ISSUE—CUTTING ORDER

Work Order \_\_\_\_\_ Account No. \_\_\_\_\_ Date \_\_\_\_\_

Requested by \_\_\_\_\_  Pickup  
 Deliver to \_\_\_\_\_

NO. PIECES	MATERIAL	UNIT DIMENSIONS	

STORES  
USE ONLY

Date Required \_\_\_\_\_ Received by \_\_\_\_\_

Issued by \_\_\_\_\_ Date \_\_\_\_\_ Staff No. \_\_\_\_\_ Voucher No. \_\_\_\_\_

37713 104

Group No. \_\_\_\_\_

Metal Stores

DAILY TIME REPORT

SHOP 07E

DATE: \_\_\_\_\_

LIGHT FABRICATION

NAME: \_\_\_\_\_ STAFF NO.: \_\_\_\_\_

VACATION \_\_\_\_\_ SICK \_\_\_\_\_ PERSONAL \_\_\_\_\_ OTHER \_\_\_\_\_

JOB NUMBER	PRINT OR SKETCH NUMBER	ITEM NO	HOURS	% COMP.

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_

VACUUM GROUP  
BIN 13 GROUP 09  
BLDG 031 EXT. 2021

# VACUUM LAB TRAVELER

TRAVELER SERIAL# \_\_\_\_\_

This traveler contains information about vacuum group assemblies and parts. Please fill it out completely and log the information in the traveler log book. Keep this traveler with the assy. or part while it is being processed, or when it gets placed in storage.

DESCRIPTION OF PART: \_\_\_\_\_ DATE RCVD: \_\_\_\_\_  
QTY: \_\_\_\_\_ PART PRINT #: \_\_\_\_\_ PART ID# \_\_\_\_\_  
PROJECT NAME: \_\_\_\_\_ WORK ORDER# \_\_\_\_\_  
ORIGINATOR/PROJECT ENGR: \_\_\_\_\_ PH. EXT.# \_\_\_\_\_  
TECHS: \_\_\_\_\_

ASSEMBLY INFORMATION: Write in date, tech initials, information requested, etc.	SIGN-OFF:
MATERIAL: _____ MACHINED: _____	
VISUAL INSPECTION: _____ QC: _____	
CLEANING: _____ PRE-ASSY: _____	
BRAZING: _____ WELD I: _____	
LK CHK I: _____ COMPLETE ASSY: _____	
WELD II: _____ LK CHK II: _____	
3. BAKEOUT (Note temp, fragile parts, time, pressure, etc. Remember to make a plot 1/2 PURGE and fill out bakeout logsheet and give it to the project engr.): _____ _____	
PUMPDOWN: _____ VENT: _____	

OTHER SPECIAL INFORMATION TO BE NOTED:  
ELECTRONIC TESTING:  
CALIBRATION:  
ALIGNMENT:  
COMMENTS: \_\_\_\_\_

SUPERVISOR SIGN-OFF: \_\_\_\_\_ DATE: \_\_\_\_\_

If assy/part is complete, fill in completed assy date and description of part section of this form.  
If assy/part is removed from from lab to be installed, write date removed: \_\_\_\_\_  
If assy/part is stored, indicate where stored: \_\_\_\_\_  
If assy/part is removed from lab to go to another shop, indicate what shop: \_\_\_\_\_  
Date removed: \_\_\_\_\_ removed by whom: \_\_\_\_\_

Once assy/part has been removed from lab, make a copy of this traveler, file the copy in the traveler log book and LEAVE THIS TRAVELER WITH THE assy/part! Thank You.

VACUUM GROUP  
BIN 13 GRP 09  
BLDG 031  
EXT: 2021

# PROCESS + TESTING TRAVELER

All outside groups requesting work from the vacuum group, please fill out the upper portion of this form.

DESCRIPTION OF PARTS: \_\_\_\_\_ QUANTITY: \_\_\_\_\_

PART PRINT#: \_\_\_\_\_ W.O.#: \_\_\_\_\_

PROJECT NAME: \_\_\_\_\_

REQUESTER/ORIGINATOR: \_\_\_\_\_ GROUP: \_\_\_\_\_

PHONE EXT: \_\_\_\_\_ ONCE COMPLETE DELIVER TO: \_\_\_\_\_

DATE SUBMITTED: \_\_\_\_\_ DATE REQUIRED: \_\_\_\_\_

OPERATION TO BE PERFORMED BY VACUUM GROUP: \_\_\_\_\_

INSTRUCTIONS: (Note temperature, baking time, delicate parts, acceptable leak check rates, etc.)

---

---

---

---

---

---

---

---

---

---

----- This portion to be completed by the vacuum group -----

TECHNICIAN: \_\_\_\_\_ VISUAL INSPECTION: \_\_\_\_\_

DATE STARTED: \_\_\_\_\_ DATE COMPLETE: \_\_\_\_\_

SUPERVISOR SIGN-OFF: \_\_\_\_\_ DELIVER TO (PICK-UP BY): \_\_\_\_\_

NOTES: (Leak check data, weld notes, remarks for shop, problems, etc.) \_\_\_\_\_

---

---

---

---

Once processing is complete, please make a copy of this traveler for your supervisor, and leave this document with the part.

**FABRICATION SHOP  
JOB DESCRIPTION FORM**

JOB # \_\_\_\_\_

FABRICATING SHOP \_\_\_\_\_ DATE REQ'D. \_\_\_\_\_  
 JOB SUBMITTED BY \_\_\_\_\_ EXT. \_\_\_\_\_ PAGE 1 - \_\_\_\_\_  
 DELIVERY TO OR NOTIFY \_\_\_\_\_ EXT. \_\_\_\_\_ PAGE 1 - \_\_\_\_\_  
 WORK ORDER NO. \_\_\_\_\_ DATE SUBMITTED \_\_\_\_\_

NO. REQ'D	DRAWING NUMBER	DESCRIPTION

PARTS & MATERIALS SUPPLIED BY REQUESTOR		
ABOVE DRAWING NUMBER	ITEM NO. ON DWG.	DESCRIPTION

ADDIT. INFO: \_\_\_\_\_  
 \_\_\_\_\_

# JOB CARD PLATING SHOP

TAG NO: \_\_\_\_\_

FOR PLATING SHOP USE ONLY	
TIME	BY

SUBMITTED BY: \_\_\_\_\_ EXT. \_\_\_\_\_ DATE: \_\_\_\_\_

DELIVER TO: \_\_\_\_\_ EXT. \_\_\_\_\_ BLDG: \_\_\_\_\_

ACCOUNT NO.: \_\_\_\_\_ W.O. NO. \_\_\_\_\_

EXPLANATION OF WORK:

a. DEGREASING ONLY \_\_\_\_\_

b. CLEAN FOR VACUUM \_\_\_\_\_

c. TYPE OF METAL TO BE CLEANED \_\_\_\_\_

d. TYPE OF BASE METAL TO BE PLATED \_\_\_\_\_

e. TYPE OF PLATING DESIRED \_\_\_\_\_

f. THICKNESS OF PLATING DESIRED \_\_\_\_\_

g. APPROXIMATE TIME REQUIRED \_\_\_\_\_

h. ADDITIONAL INSTRUCTIONS OR REMARKS \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**VACUUM  
GROUP**

FOR PLATING SHOP USE ONLY

PLATING SHOP JOB CARD

TIME	BY

SUBMITTED BY: \_\_\_\_\_ EXT: \_\_\_\_\_ DATE: \_\_\_\_\_

DELIVERED TO: \_\_\_\_\_ EXT. \_\_\_\_\_ BLDG: \_\_\_\_\_

ACCOUNT NO: \_\_\_\_\_ W.O. NO: \_\_\_\_\_

EXPLANATION OF WORK:

a. DEGREASING ONLY \_\_\_\_\_

b. CLEAN FOR VACUUM \_\_\_\_\_

c. TYPE OF METAL TO BE CLEANED \_\_\_\_\_

d. TYPE OF BASE METAL TO BE PLATED \_\_\_\_\_

e. TYPE OF PLATING DESIRED \_\_\_\_\_

f. THICKNESS OF PLATING DESIRED \_\_\_\_\_

g. APPROX. TIME REQUIRED \_\_\_\_\_

h. ADDITIONAL INSTRUCTIONS OR REMARKS \_\_\_\_\_

---



---



---



---



---



---



---

CHECK GROUP

CRYOGENICS-----	<input type="checkbox"/>
ELECTRONICS-----	<input type="checkbox"/>
INJECTION LAB-----	<input type="checkbox"/>
MECH. ENG.-----	<input type="checkbox"/>
PEL-----	<input type="checkbox"/>
SPRL-----	<input type="checkbox"/>
SSRL-----	<input type="checkbox"/>
TUBE SHOP-----	<input type="checkbox"/>
VACUUM GROUP-----	<input type="checkbox"/>
WELD SHOP-----	<input type="checkbox"/>
OTHER :	<input type="checkbox"/>
_____	<input type="checkbox"/>



MECHANICAL FABRICATION SHOPS

OVERTIME REQUEST

<u>Employee Name</u>	<u>Hours To Be Worked</u>	<u>Charged to W.O. or Acct. No.</u>	<u>Job Description</u>	<u>Date O.T. Worked</u>

30

SUPERVISOR: \_\_\_\_\_

APPROVED BY: \_\_\_\_\_

From: CLEANING AND PLATING SHOP - MFS Department

TO OUR CUSTOMERS

To prevent the possibility of damage, we would like to suggest that you transport parts to be cleaned in fiberglass tote boxes. These boxes are very durable and can easily be cleaned before loading them with your cleaned parts.

The sizes listed below will fit our storage shelves and are recommended.

LEWIS "STACK-N-NEST" TOTE BOXES

	<u>PRICE OF BOXES</u> (1-19 quantities)	<u>PRICE OF COVERS</u> (each)
Code # SN 1610-5 - 16" x 10" x 5" deep	\$9.32 ea	#CO 1610-1 - \$6.28 ea
Code # SN 12-6 - 18" x 12" x 6" deep	11.31 ea	#CO 1812-1 6.53 "
Code # SN 1812-8 18" x 12" x 8" deep	12.94 ea	#CO 2013-1 6.53 "
Code # SN 2217-10 22" x 17" x 10" deep	19.62 ea	#CO 2217-1 10.66 "

TOTE BOXES ARE AVAILABE FROM:

Advanced Handling Systems of Northern California  
526 Laurelwood Road  
Santa Clara, California 95051

Phone: (408) 988-1833

COLORS AVAILABLE ARE: GREEN, GRAY, BLUE, AND RED.

**Appendix A.5: Examples of MOSG Installation and Removal Procedures**

## **9.4' ACCELERATOR SECTION INSTALLATION PROCEDURE**

**Robert R. Wurster**

**March 10, 1986**

**9.4' ACCELERATOR SECTION INSTALLATION  
PROCEDURE MANUAL  
(REFER TO DRAWING ID 238-010-59  
ID 902-675-52 RO  
SA 750-214-05)**

- 1) Assemble all tools required per ACCELERATOR INSTALLATION TOOL LIST.
  - 2) Verify that the sector is under N2 purge. (A sintered bronze exit should be provided.)
  - 3) Verify 'Z' location of downstream accelerator support belly band. (The distance from center of welded mount to center of belly band on the light-pipe will be the same as the distance between end support centers on the 9.4' accelerator section being installed.)
  - 4) Fit belly band to light pipe and install hardware finger-tight. (This will allow adjustment in 'Z' if necessary.) All hardware will be secured during alignment process.
  - 5) Install alignment mounting hardware finger-tight.
  - 6) Verify serial number and orientation of 9.4' accelerator section to be installed.
  - 7) Place (stongback) locating tool #1 on light pipe just upstream of belly band.
  - 8) Place (stongback) locating tool #2 on light pipe at upstream end of installation location. NOTE: GREAT CARE MUST BE TAKEN TO INSURE THAT THE LOCATING TOOLS ARE LEVEL AND CENTERED SECURELY ON THE LIGHT PIPE.
- THE FOLLOWING PROCEDURE WILL REQUIRE ULTRA-CLEAN  
CONDITIONS AND THE USE OF CLEAN GLOVES (WHERE NOTED).
- 9) With foil ready, remove upstream eyelet peel-off from accelerator section to be installed and foil over exposed vacuum.
  - 10) Place 9.4' accelerator section on locating tools as far downstream as possible, using accelerator lifting fixture and the large hoist. SEE NOTE.

NOTE: IT MAY BE NECESSARY TO REMOVE BLANK FLANGES FROM BOTH THE INPUT WAVEGUIDE AND THE 9.4' ACCELERATOR INPUT TRANSITION TO ALLOW THE REQUIRED AMOUNT OF 'Z' MOVEMENT. FOIL, BAG AND TAPE OPEN FLANGES.

- 11) Remove foil and lint-free from upstream eyelets, place engagement ring on upstream accelerator section (properly oriented with scribed arrow up and pointed downstream) and roll 9.4' accelerator section upstream as far as possible (eyelets touching). NOTE: Some rough alignment using strongback alignment tools may be required to allow engagement of ring.
- 12) Secure alignment hardware between 9.4 accelerator end supports and light pipe mount/belly band.

THE FOLLOWING STEPS REQUIRES THE USE OF CLEAN GLOVES.

- 13) While wearing clean gloves, install waveguide load with clean gasket per Waveguide Flange Assembly Procedure. NOTE: 2 BOLTS ON EACH FLANGE ADJACENT TO EACH OTHER WILL BE INSTALLED BACKWARDS TO ALLOW CLEARANCE FOR FUTURE INSTALLATIONS (SEE DRAWING \* ID-902-675-52 RO Note 2).
- 14) Install Waveguide load sheet metal support bracket. Safety wire load to support.
- 15) Align 9.4' accelerator section. (TO BE PERFORMED BY THE PRECISION ALIGNMENT TEAM.)
- 16) Install load transfer blocks between 9.4' accelerator section and upstream accelerator section. Brass shim washers must be inserted between load transfer blocks and accelerator end supports (on the upper bolts only).
- 17) Check alignment of upstream accelerator section and adjust as required. (TO BE PERFORMED BY THE PRECISION ALIGNMENT TEAM.)
- 18) When alignment is completed, remove all strongback locating tools.


- 19) Weld eyelet joining the 9.4' accelerator section with the upstream accelerator section. Inspect weld twice.
- 20) Remove foil from input waveguide flange and accelerator input transition flange.

**PROCEED IMMEDIATELY TO NEXT STEP**

- 21) Using hardware on the vacuum manifold 'Y' supports nearest the input waveguide pump-out, align the input waveguide flange and the accelerator input transition flange.

**THE FOLLOWING PROCEDURE WILL REQUIRE ULTRA-CLEAN CONDITIONS AND THE USE OF CLEAN GLOVES.**

- 22) Using clean gloves and gasket, secure Skarpaas flanges between 9.4' accelerator section and input waveguide per Waveguide Flange Assembly Procedure.
- 23) Fit a QE magnet support belly band at the downstream end of the 9.4' accelerator section per drawing ID 238-010-59. Install hardware finger-tight. (NOTE: Hardware will be secured during the alignment process.)
- 24) Downstream accelerator sections must now be realigned in 'Z' (The dimension between 'A' input and 'C' input / 'B' input and 'D' input must be returned to original settings taken during the Accelerator Removal Procedure.)



FOR QE/BPMO INSTALLATION, REMOVE EYELET PEEL-OFF FROM DOWNSTREAM END OF 9.4' ACCELERATOR SECTION, FOIL OVER EXPOSED EYELET AND PROCEED IMMEDIATELY TO STEP 25 OF THE "SLC INTER-GIRDER BPMO/QUAD INSTALLATION PROCEDURE" AND COMPLETE THAT MANUAL.

RETURN TO STEP 25 OF THIS MANUAL AFTER COMPLETION OF THE QE/BPMO INSTALLATION PROCEDURE MANUAL.

- 25) Align entire girder. (TO BE PERFORMED BY THE PRECISION ALIGNMENT TEAM.)



STATION# \_\_\_\_\_

BETA ACC. SWAP

\*22

Date      Tech

- \_\_\_\_\_ / \_\_\_\_\_ 1) Verify that sector is vented and under purge.
- \_\_\_\_\_ / \_\_\_\_\_ 2) Tag, shut off H2O supply and return.
- \_\_\_\_\_ / \_\_\_\_\_ 3) Cut, drain H2O lines at Acc. and W/G.
- \_\_\_\_\_ / \_\_\_\_\_ 4) Tag, remove W/G load and blank off.
- \_\_\_\_\_ / \_\_\_\_\_ 5) Label, disconnect wiring.
- \_\_\_\_\_ / \_\_\_\_\_ 6) Measure AC / BD dimensions and record.
- \_\_\_\_\_ / \_\_\_\_\_ 7) Machine, deburr eyelet(s) per Procedure Manual.
- \_\_\_\_\_ / \_\_\_\_\_ 8) Unbolt input W/G.
- \_\_\_\_\_ / \_\_\_\_\_ 9) Remove Acc. section per Procedure Manual.
- \_\_\_\_\_ / \_\_\_\_\_ 10) Boroscope Acc. apertures.
- \_\_\_\_\_ / \_\_\_\_\_ 11) Install Belly-band and level.
- \_\_\_\_\_ / \_\_\_\_\_ 12) Verify new Acc. serial number/eyelet measurements.
- \_\_\_\_\_ / \_\_\_\_\_ 13) Install Acc. section.
- \_\_\_\_\_ / \_\_\_\_\_ 14) Install W/G load.
- \_\_\_\_\_ / \_\_\_\_\_ 15) Align Acc. section.
- \_\_\_\_\_ / \_\_\_\_\_ 16) Weld eyelet(s) and inspect twice.
- \_\_\_\_\_ / \_\_\_\_\_ 17) Bolt-up Input W/G and top castings.
- \_\_\_\_\_ / \_\_\_\_\_ 18) Plumb H2O lines to Acc. and W/G.
- \_\_\_\_\_ / \_\_\_\_\_ 19) Turn on H2O supply and return, remove tags and check for leaks.
- \_\_\_\_\_ / \_\_\_\_\_ 20) Connect wiring.

AC Dimension \_\_\_\_\_ BD Dimension \_\_\_\_\_ ACC. # \_\_\_\_\_

**ACCELERATOR SECTION REMOVAL PROCEDURE**

**Robert R. Wurster**

**March 12, 1986**

**ACCELERATOR SECTION REMOVAL PROCEDURE  
(REFER TO DRAWING AD 771-001-R1)**

- 1) Assemble all tools per ACCELERATOR REMOVAL/INSTALLATION TOOL LIST.
- 2) Tag demagnetizing power plug (located at the last fiat rack in each sector) "OUT OF SERVICE". Date and sign tag.
- 3) Tag and turn off power supply to any and all magnets / beam line equipment located within the designated work area (girder, sector, etc.). NOTE: The supervisor at sector 10 (Ext. 2133) will take responsibility for this step.
- 4) Tag "OUT OF SERVICE" and shut off all supply cooling H2O to accelerator sections, magnets and beamline equipment to be removed. Date and sign tag.
- 5) Tag "OUT OF SERVICE" and shut off all return H2O from items in previous step. Date and sign tag.
- 6) Label all electrical leads on magnets and beamline equipment designated for removal. Disconnect leads.
- 7) Cut demagnetizing jumper wires between accelerator sections to be removed or modified.

**THE FOLLOWING STEPS COVER THE PROCEDURE FOR EACH  
ACCELERATOR SECTION TO BE REMOVED.**

- 8) Tag (with location information) and disconnect pipe union at the valve on return header. Drain H2O away from beam pipe into container for disposal. (THERE IS ONE (1) RETURN LINE FROM EVERY OTHER INPUT WAVEGUIDE AND EVERY OTHER WAVEGUIDE LOAD WITH THE ORDER OF OCCURENCE CHANGING EVERY GIRDER. eg. Input, Load, Input, Load -- Load, Input, Load, Input etc.)
- 9) Tube cut or hack saw return flex line at the waveguide load or input wave guide leaving a length of straight pipe and an elbow on the flex.
- 10) Place loose flex line in a safe storage area until time for reinstallation.

- 11) Tube cut or hack saw supply line at accelerator allowing enough lead-out pipe for easy solder reconnection but not so much so as to cause an inconvenient protrusion while handling accelerator section. Drain H<sub>2</sub>O away from beam pipe into container for disposal.
- 12) Secure supply flex line away from beam pipe.
- 13) Cut water jumpers between accelerator and waveguide load, and/or waveguide load and input waveguide, with the latter cut being made reasonably close to the input waveguide. (This will allow clearance when removing the accelerator section.)
- 14) Cork, bag and tape all open H<sub>2</sub>O lines to prevent accidental contamination of vacuum systems.
- 15) Verify that the sector is vented and under N<sub>2</sub> purge. (A sintered bronze exit should be provided.)

WHERE AN 'A', 'B', OR 'C' SECTION IS TO BE REMOVED AN ACCURATE MEASUREMENT IN 'Z' MUST BE TAKEN TO INSURE THAT ACCELERATOR SECTIONS MOVED FOR THE PURPOSE OF CLEARANCE ONLY, BE RETURNED TO THEIR ORIGINAL POSITIONS.


FOLLOW STEPS 16 OF THIS MANUAL.

WHERE ONLY THE 'D' SECTION IS DESIGNATED FOR REMOVAL ON A GIVEN GIRDER PROCEED TO STEP 19 OF THIS MANUAL.

(MEASUREMENT IS NOT REQUIRED).

- 16) Using a 100' tape, measure the distance between 'A' input and 'C' input (from side of input waveguide transition to side of input waveguide transition) and record. Repeat for 'B' input to 'D' input dimension and record. ACCURACY IS IMPORTANT TO A TOLERANCE OF +/- 1/32 inch. (SEE DRAWING BELOW.)

TYPICAL GIRDER



- 17) Cut the wire that secures the load to the sheet metal support bracket. Remove support and store for future installation.
- 18) Remove all but two (2) bolts (opposite each other) from the waveguide load to accelerator flanged connection.

THE FOLLOWING PROCEDURE WILL REQUIRE ULTRA-CLEAN CONDITIONS AND THE USE OF CLEAN GLOVES (WHERE NOTED).

- 19) With foil, blanking flanges and blank gaskets ready, remove the load and foil both the accelerator and the load.

PROCEED IMMEDIATELY TO THE NEXT STEP

- 20) While wearing clean gloves, install blank gasket and flange on both the accelerator and the waveguide load. (Refer to FLANGE ASSEMBLY PROCEDURE.)

FOR REMOVAL OF ACCELERATOR SECTIONS BEGINNING A GIRDER ('A' SECTION) OR ENDING A GIRDER ('D' SECTION),  
COMPLETE STEP \*7 THRU \*24 IN THE  
"SLC INTER-GIRDER BPMQ & QUAD INSTALLATION PROCEDURE."  
PROCEED TO STEP 21 OF THIS MANUAL UPON COMPLETION OF  
THE AFORE MENTIONED STEPS.

FOR REMOVAL OF ALL OTHERS ('B' & 'C' SECTIONS) PROCEED TO  
STEP 21 OF THIS MANUAL.

- 21) Wash down accelerator eyelets and surrounding area using ethyl alcohol or equivalent.
- 22) Cover any nearby magnets, components, etc. that metal chips could damage.
- 23) Remove the four (4) bolts that surround the welded eyelet, securing the accelerator end supports.
- 24) Remove four (4) bolts, tag and remove the top castings of the accelerator to waveguide support (to allow access).
- 25) Using a hand held cutting burr (pencil type), carefully machine eyelet. Cut just deep enough to separate eyelet using a degreased knife and a small ball-peen hammer to assist. (.070 inch has been set as a standard depth of cut.)

WHERE ONE (1) ACCELERATOR SECTION IS TO BE REMOVED, TWO EYELETS MUST BE CUT. WHERE TWO (2) ACCELERATOR SECTIONS IN SUCCESSION ARE TO BE REMOVED, THREE (3) EYELETS MUST BE CUT. ETC.

- 26) After eyelet is separated, deburr the outside edges of the eyelet using a degreased file (6-8" flat).
- 27) Cover each eyelet with foil after deburring to prevent accidental contamination of the vacuum system.

IN ORDER TO REMOVE AN ACCELERATOR SECTION, ALL SECTIONS LOCATED DOWNSTREAM WITHIN THAT GIRDER MUST BE SHIFTED DOWNSTREAM TO ALLOW THE DISENGAGEMENT OF THE ALIGNMENT RING LOCATED BETWEEN SECTIONS.

IF THE 'D' SECTION IS SLATED FOR REMOVAL, (BEING THE LAST SECTION ON THE GIRDER) ONLY IT WILL MOVE, ALLOWING THE REMOVAL OF THE RING BETWEEN SECTION 'D' AND SECTION 'C'.

IF THE 'B' SECTION IS SLATED FOR REMOVAL, SECTIONS 'C' & 'D' MUST BE SHIFTED DOWNSTREAM AND THE RING BETWEEN SECTIONS 'B' & 'C' REMOVED. THEN SHIFT SECTION 'B' DOWNSTREAM AND REMOVE THE RING BETWEEN SECTIONS 'A' & 'B'.

- 28) Place (strongback) locating tool #1 under the downstream end of the accelerator section to be removed and the downstream end of the accelerator section immediately upstream (WHERE THE 'B', 'C' OR 'D' SECTION IS TO BE REMOVED).
- 29) Place (strongback) locating tool #2 under the upstream end of the accelerator section to be removed and both ends of any sections located downstream within that girder.
- 30) Carefully align and level all locating tools before proceeding to next step. NOTE: GREAT CARE MUST BE TAKEN TO INSURE THAT THE LOCATING TOOLS ARE CENTERED ON THE LIGHT PIPE (30 INCH DIAMETER ALUMINUM WELDED PIPE) AND FIRMLY SUPPORTING THE ACCELERATOR STRONGBACK.
- 31) Remove alignment hardware securing the accelerator sections (to be moved and/or removed) to the light pipe. Retain hardware for reinstallation.

NO ACCELERATOR SECTIONS SHALL REMAIN ON THE LOCATING  
TOOLS UNATTENDED

- 32) Loosen four (4) each bolts securing the strongback alignment end plates (on the section to be removed) with the compression blocks located between two (2) adjacent strongbacks as follows:

'A' section - downstream end of section only.

'B' section - both ends of section.

'C' section - both ends of section.

'D' section - upstream end of section only.

DO NOT AT THIS TIME REMOVE ANY BOLTS OR BRASS SHIM  
WASHERS.

- 33) Make a foil basket under the eyelets of the accelerator section to be removed. (This is a safety measure to prevent the accidental dropping of the engagement ring located between accelerator sections within a girder.)
- 34) Locate a screw-jack between accelerator section to be REMOVED (downstream end) and the section(s) to be MOVED. In the case of a 'D' section, locate the screw-jack at the upstream end.
- 35) Remove loosened bolts and brass shim washers from compression blocks between accelerator sections. Document location of shims for future installation.
- 36) Remove all but the top bolt on the input waveguide to accelerator flanged connection on the section(s) to be MOVED (if any) and the section(s) to be REMOVED.
- 37) Wrap a large quantity of foil loosely around the flange(s) as the last bolt is removed. This will retain the gasket between the flanges and serve as a cushion during the (re)moving sequence.

THE FOLLOWING PROCEDURE REQUIRES THE USE OF CLEAN  
GLOVES (WHERE NOTED).

- 38) With one (1) person (in clean gloves) holding a degreased scribe tool, and a second person operating the screw-jack, slowly separate the eyelets (APPROXIMATELY 1/4 INCH) until the engagement ring can be seen.

- 39) Carefully insert the point of the scribe into one of the holes on either side of the ring while continuing to jack the accelerator sections apart. As soon as the ring can clear the step that it is resting on, stop jacking and remove the ring.  
NOTE: (THIS SHOULD BE NO MORE THAN A 3/4 INCH SEPARATION.)

OBSERVE AND MARK ORIENTATION, BEAM DIRECTION (AN ARROW ON TOP POINTING DOWNSTREAM) AND LOCATION OF THE RING.

- 40) Wrap the ring in lint-free and foil. Label with the location and place in a zip-lok plastic bag.
- 41) Foil over all exposed vacuum (eyelets).

IN THE CASE OF THE 'A' SECTION, A TEMPORARY ALIGNMENT SUPPORT IS INSTALLED BETWEEN THE ACCELERATOR AND THE STRONGBACK APPROXIMATELY FOUR (4) INCHES FROM THE UPSTREAM END. THE STRONGBACK IS THEN CUT JUST UPSTREAM OF THE SUPPORT. THIS ALLOWS THE LASER ALIGNMENT PLATE TO REMAIN ON THE GIRDER.

- 42) Place a .030 inch (approximately) sheet of stainless steel between eyelets. Lift out the accelerator section(s) slated for removal using the Accelerator Lifting fixture and a large engine hoist.

USE EXTREME CAUTION.  
DO NOT BUMP EYELETS OR FLANGE FACES.

- 43) As soon as the accelerator section is clear of the light pipe, place in a transport tote and secure.

PROCEED IMMEDIATELY TO NEXT STEP.

- 44) While wearing CLEAN GLOVES, blank off the accelerator input transition flange and the input waveguide flange. (Refer to FLANGE ASSEMBLY PROCEDURE.)
- 45) Carefully remove the foil from the eyelet(s) to be deburred (both on and off the light pipe) and while wearing CLEAN GLOVES carefully plug the accelerator aperture(s) with lint-free.



- 46) Deburr accelerator eyelet(s) using a degreased file.  
NOTE: TAKE CARE NOT TO SCRATCH THE COPPER FACE OF THE ACCELERATOR END OR BUMP THE LINT-FREE PLUG.
- 47) Cover eyelet(s) with foil.
- 48) Vacuum up all metal chips. THIS MUST BE A THOROUGH JOB.
- 49) Remove foil and while wearing CLEAN GLOVES carefully pull out the lint-free plug(s). Watch for any evidence of metal chips.

THE FOLLOWING STEP REQUIRES ULTRA-CLEAN CONDITIONS AND THE USE OF CLEAN GLOVES.

- 50) View apertures and 1st three (3) accelerator cavities using a clean Boroscope. NOTIFY SUPERVISOR OF ANY CONTAMINATION.
- 51) FOIL, BAG AND TAPE ALL EYELETS (BOTH ON AND OFF THE LIGHT PIPE).
- 52) Use furniture dollies to transport section(s) to a designated site for removal by crane.
- 53) Any sections that are remaining on the light pipe should be moved back upstream and resecured with the alignment hardware.

NO ACCELERATOR SECTION SHALL REMAIN ON THE LOCATING TOOLS UNATTENDED.

**Appendix A.6: Example of a Weekly Status Report (MFD)**

LINAC STATUS REPORT

SHOP WORK STATUS REPORT

ITEM NO.	PART NAME	QTY	FILE NUMBER	CHARGE NUMBER	PRIORITY	ENGINEER RESPONSIBLE	RELEASE DATE	SHOP(S) RESPONSIBLE	REQUESTED DUE DATE	COMPUTER COMPLETION DATE	ESTIMATED COMPLETION DATE	% COMP OF EST	LABOR COST	STATUS
01	FAST VALVE CONVERSION	8	000823	K.O. # 06-7126-0	201	C PERKINS x2970	07/16/86	UMEN	11/30/86	02/29/88		0	0	RECONSIDER AFTER DOWN
02	SHOP WORK TO SUPPORT MAINTENANCE OF LINAC AND RINGS	1	001267	K.O. # 06-8101-0	902	AL LISIN x2322	02/20/87	THEN EREN RAEN RXLD UMEN FAEN	10/01/87	02/24/88	CLOSED	100	8446	CLOSED
02A	SHOP WORK TO SUPPORT MAINTENANCE OF LINAC	1	001963	ACCT # 12-0624	902	C PERKINS x2970	11/11/87	THEN UMEN	10/01/88		10/01/88	0	0	
02B	SHOP WORK TO SUPPORT MAINTENANCE OF DAMPING RINGS	1	001967	ACCT # 12-0622	902	C PERKINS x2970	11/11/87	THEN UMEN	10/01/88		10/01/88	0	0	
03	SHOP WORK TO SUPPORT BST	1	001969	ACCT # 12-0631	902	C PERKINS x2970	11/11/87	THEN UMEN	10/01/88		10/01/88	0	0	
04	SHOP WORK TO SUPPORT CID	1	001971	ACCT # 12-0621	902	C PERKINS x2970	11/11/87	THEN UMEN	10/01/88		10/01/88	0	0	
05	SEPTUM MAGNET (SUPPORTS AND INSPECTION & PROCESSING OF CONDUCTOR)	1	001457C	K.O. # 06-8145-0	203	BOB SUKIENKICKI	05/06/87	UMEN	07/17/87	12/09/87		61	5531	AT VACUUM
06	BAKEABLE FOCUSING LENS COILS	7	001947	K.O. # 06-6004-B	223	H FISCHER x2327	11/06/87	THEN	11/17/87	01/01/88	11/17/87	0	0	

POSITRON SOURCE STATUS REPORT

07A	CAPTURE SECTION IS	1	000985	K.O. # 06-8112-0	202	AL LISIN x2322	10/31/86	EREN UMEN	02/16/88	02/29/88	02/16/88	60	2707	WORKING / MAY HAVE INTERFERENCE WITH FURNACE DOWN
07B	VACUUM CRUSH SEAL BASKETS	12	001957	K.O. # 06-8112-0	224	B. SMITH x2638	11/10/87	EREN	11/23/87	12/04/87	11/23/87	0	0	
08	POSITRON SOURCE GENERAL MAINTENANCE WORK	1	001539	K.O. # 06-8183-0	903	B FEERICK x3401	06/16/87	THEN	10/01/87	11/23/87	CLOSED	100	8792	CLOSED
08A	SHOP WORK TO SUPPORT MAINTENANCE OF SLC POSITRON SOURCE	1	001973	K.O. # 06-2301-B	903	B FEERICK x3401	11/11/87	THEN UMEN	10/01/88		10/01/88	0	0	
09	BUNCH MONITORS	3	001775	K.O. # 06-8630-0	210	B FEERICK x3401	07/14/87	EREN UMEN	10/10/87	12/03/87	11/16/87	85	4367	IN MACHINE SHOP
10	PEREGRINATION PARTS, SLC-POSITRON SOURCE	1	002184	K.O. # 06-8005-B	218	B FEERICK x3401	10/26/87	THEN	10/30/87	11/16/87	11/13/87	92	2601	ON HOLD FOR FURTHER INSTRUCTIONS
11	FLUX CONCENTRATOR, +1 SOURCE	4	002262	K.O. # 06-1403-7	221	E REUTER x2072	11/05/87	EREN UMEN UMEN	11/16/87	02/25/88	11/16/87	0	0	

**APPENDIX B**

**Quality Assurance Policies and Standards in Klystron &  
Microwave Department**

**Appendix B.1: Quality Assurance Procedures for Incoming  
Materials**

a.) This section refers to general Q.C. procedures for raw materials (e.g. copper bar, stainless forgings, stainless tube and pipe, cupro nickel sheet, etc.) used for Klystron component manufacturing

b.) TRACEABILITY:

All incoming materials are assigned a lot number, used for internal traceability. This number has the form KXXXX.YY, where XXXX is an assigned number unique to the manufacturer's heat lot number, and .YY is a number used to distinguish between separate bars, sheets, tubes, etc, of the same heat.

All pieces are stamped or labeled with the lot number upon receiving. Traceability is maintained throughout manufacturing processes and vendors return finished parts identified with appropriate lot number. Components are serialized during mechanical inspection, and at that time the lot number is recorded as serial number along with other data on the mechanical inspection report. The lot number is also recorded on the shipping order, shop order log, receiving inspection cover sheet, and daily shipping report, which allows various cross checks in the event of error or omission.

c.) TESTING

All incoming materials are subjected to acceptance

tests. These tests vary depending upon material type and application, but usually consist of independent chemical analysis and metallographic examination. Samples for testing are cut when material is received and are identified with the assigned lot number. Test results are accumulated in a file established for each lot number along with copies of the manufacturers' test reports and certifications and copies of the purchase requisition. This file is then consulted prior to issuing material to verify acceptance.

Tests are performed on some specific materials of importance are as follows:

1.) COPPER

Copper currently being used in SLAC klystrons is purchased from Hitachi (through Copper & Brass Sales). The material is oxygen-free electronic grade certified to ASTM F68-82, Metallographic Class I.

Chemical composition must conform to ASTM F68, Table 1 (copy attached). However independent chemical analysis is not currently part of our acceptance procedure. The contaminant of most concern is oxygen. At the start of 5045 production, quantitative analysis for oxygen was performed on many copper samples by different labs with inconsistent results..

We feel that metallographic examination is a reliable method for determining the presence harmful levels of oxygen. Metallographic examinations are performed on eight (8) samples taken from each copper bar. Samples are cleaned, fired at 950 degrees centigrade for twenty (20) minutes in Hydrogen, polished, etched, and examined at 100x. Samples must conform to ASTM F68, Metallographic Class I. The most common cause for rejection is porosity (usually resulting from oxygen contamination).

2.) STAINLESS STEEL: (Sheet, plate, tube, bar and forgings) is purchased from a variety of domestic and foreign mills depending on price and availability. The acceptance criteria as indicated below vary somewhat depending upon the application within the tube. Forgings or vacuum melted material is used instead of wrought forms whenever the major work direction of the wrought form could result in elongated defects which coincide with the direction of a possible leak path. In addition, vacuum melted (specifically, consumable electrode vacuum arc remelted) material is used for all stainless components near the cathode heater



which are in a more critical position relative to potential outgassing. Type 304L is used in all locations except for the focus electrode and focus electrode support cup, which are made from 317L vacuum melted.

Samples of each piece of stainless purchased for use in klystrons (excluding some external parts, water fittings, etc.) are sent to an independent test lab for chemical analysis. Carbon and sulfur are analyzed by quantitative techniques, other elements by spectrographic analysis. Chemical composition must meet chemical requirements listed in the applicable ASTM specification and compare with chemical test reports supplied by the material manufacturer.

The material used for the focus electrode and focus electrode cup is type 317L modified.

It is a non-standard grade and has the following composition.

Aluminum	(Al)	0.02%
Carbon	(C)	0.014
Chromium	(Cr)	20.43%
Cobalt	(Co)	0.14%
Columbium	(Cb)	0.11%
Copper	(Cu)	0.30%
Manganese	(Mn)	1.55%
Molybdenum	(Mo)	4.09%
Nickel	(Ni)	19.83%
Phosphorus	(P)	0.022%
Silicon	(Si)	0.26%
Sulfur	(S)	0.005%
Titanium	(Ti)	0.01%

Vanadium	(V)	0.09%
Zirconium	(Zr)	0.005%
Alloy Type		317L Modified

Also metallographic examinations are performed at SLAC of two (2) or more samples from each piece of stainless steel used in the klystron (excluding external parts). The inclusion content of the steel is rated in accordance with ASTM E45-84 method D. For the more critical klystron components such as anode housing, anode plate, cathode parts and window flanges, the maximum allowable inclusion content is as follows:

Type	A	B	C	D
Heavy	1 1/2	1	1 1/2	1
Thin	1	1 1/2	1	1 1/2

These requirements are usually met only by vacuum melted material.

For less critical parts, those exposed to vacuum but not in high temperature or high field areas, the maximum allowable inclusion content is as follows:

	A	B	C	D
Heavy	1 1/2	2	1 1/2	2
Thin	2	2 1/2	2	2 1/2

### 3.) CUPRO-NICKEL

A good grade of 70-30 cupro-nickel has been purchased from Amax Special Metals Division and also from a European source through Copper & Brass Sales. Cupro-nickel is used for all the

welding eyelets.

Samples from each shipment are sent to an independent test lab for chemical analysis. The following is the chemical composition of recent samples from copper & brass sales and Amax:

	C&B		AMAX
AL	.005	%	.001
C	.076		.025
Cb	.020		NA
CO	.005		.001
Cm	70.9		69.5
Fe	.005		NA
Pb	.005		.001
Mn	.37		NA
Ni	28.9		30.3
P	.002		.003
Si	.02		.005
S	.006		.002
Ti	.02		.001
Zn	.08		.001

Both of these chemistries are acceptable for klystron use.

Test welds and test brazes are performed on cupro-nickel samples to verify weldability and brazeability. These samples are then mounted, polished, etched and examined at 100x. Possible causes for rejection are excessive porosity or inclusions, poor braze wettability (high contact angle), porosity or cracking in weld.

**Appendix B.2: Summary of QA Activities During Different Stages  
of Tube Manufacturing**

I. MATERIALS

- A. Certification required.
- B. Chemistry tests performed as required.
- C. Metallographic tests performed as required.
- D. Materials numbered for traceability.

II. MANUFACTURING

- A. Engineering drawings required.
- B. Process documentation.
- C. Mechanical inspection of parts with traceability numbers.
- D. Travelers used.

III. TUBE ASSEMBLY

- A. Detailed assembly drawings required.
- B. All parts traced and logged.
- C. Manufacturing parts required for assembly.
- D. Travelers used.
- E. Strong supervision required.

IV. BAKE PROCESSING

- A. Detailed manufacturing rates required.
- B. Computer controlled bake processing.
- C. Equipment maintenance schedule.
- D. Travelers used.

V. MECHANICAL ASSEMBLY

- A. Manufacturing notes required.
- B. Extensive final inspection.
- C. Travelers used.
- D. Strong supervision required.

## **Appendix B.3: Quality Assurance in Klystron Manufacturing**

MANUFACTURING COMPONENTS:

- a.) This section refers to general QC procedures used for all manufactured klystron components, excluding windows, HV seals, cathodes, and electromagnets.
- b.) MECHANICAL INSPECTION: All incoming fabricated components must pass mechanical inspection prior to being placed in inventory. An inspection report is written for each lot of parts received and this report is retained in a permanent manufacturing and inspection history file.

Parts which have an electrical function are inspected 100%. Mechanical parts, fittings, water jackets, etc. are sampled. If discrepancies are found in a sample the lot is inspected 100%. All discrepancies are noted on the inspection report and the affected parts are rejected. In some cases parts may be held pending possible MRB action.

c.) MATERIAL REVIEW BOARD (MRB)

If a part has a discrepancy which is judged to be minor or not affecting tube performance or life, it may be presented to the MRB committee for disposition. The committee consists of the production manager, tube engineer, manufacturing manager, and QC supervisor. The committee decides whether the parts in question will be used as is, reworked, or scrapped. Discrepant parts not

brought before MRB are either reworked or scrapped.

Reworked parts are reinspected.

d.) TRACEABILITY:

All parts are given a serial number or lot number when inspected. This number is recorded on the inspection report along with material lot number and inspection data. The part serial numbers are also recorded tube number during assembly. Thus, given the tube number, complete data including component inspection reports, discrepancies, material test reports, etc., can be obtained.



**Appendix B.4: Quality Assurance Procedures in Klystron Testing**

Klystron Testing operations are governed by a set of Testing Notes that cover all procedures associated with klystron processing and data accumulation. All operators are familiar with these notes, and use them in processing tubes. Each tube is delivered with a travel folder from manufacturing which contains the history of the tube as it proceeded through the manufacturing process. The pulse transformer tank to which the tube is mated has undergone a set of quality assurance checks and pulse modulator testing before being delivered for use with a tube. The tube is mated to a focus magnet which has a separate quality assurance check program, is dressed with plumbing according to a written procedure, and the tank is filled with oil from a carefully monitored oil processing station. A final inspection of the completed tank-tube assembly is conducted by the mechanical group supervisor. Tank, magnet, and assembly information is added to the tube folder.

The tube assembly is installed in the 1  $\mu$ sec test stand, the installation is inspected by the assigned test stand operator, and the tube processing commences according to the processing notes. On completion of initial 1  $\mu$ sec processing, the tube is moved to a 3.5  $\mu$ sec test stand for final processing, and a full power, 180 PPS heat run. Various data logging sheets are used to record each test, and the results. Performance of the tube as recorded by the operator is reviewed by the shift supervisor. All data sheets are kept in the tube travel folder. Any unusual or non-spec performance of a tube is brought to the attention of the shift supervisor, and then to a tube engineer. A program of additional testing is agreed on, and the new procedures are carried out. Most of these additional procedures are documented in the Testing Notes manual.

When a tube has completed all prescribed tests satisfactorily, the data is presented to a tube engineer for acceptance. The tube engineer may request additional testing, or sign off on the tube for Gallery use, sometimes with some limitations which are noted on the data card that goes with the tube. Tubes that are rejected are sent back to manufacturing for autopsy, and possible rebuilding.

The standardized data taken for each tube is entered into the SPIRES manufacturing data base, a tube card containing operating settings is attached to the tube, and the travel folder containing all manufacturing and testing data is filed in the master klystron file. The tube is moved to a storage area and is available for Gallery use.

The overall operation of the Test Lab testing facility is summarized in the morning report which is distributed and discussed at the daily 8:30 AM management meeting. These discussions sometimes generate additional engineering and operational meetings to solve problems as they come up. On a weekly basis, a report of completed testing operations is generated, and used to update Klystron Task Force master data files.

**Appendix B.5: Documentation Process for a Single Part (Anode Housing) in Klystron & Microwave Department**

- B.5a: Material Specifications**
- B.5b: Material Certification and Testing**
- B.5c: Part Purchase Requisition to an Outside Vendor and Machining Specifications**
- B.5d: Part Inspection and QC Reports**
- B.5e: Tube Manufacturing Reports**
- B.5f: Tube Assembly Reports**
- B.5g: Tube Bake Processing Reports**
- B.5h: Klystron Test Reports**
- B.5i: Failure Reports**
- B.5j: Part Non-Conformance Report**
- B.5k: Engineering Change Order**

**Appendix B.5a: Material Specifications**

Specifications for Stainless Steel (2)

Other Specifications for Materials: (not included here)

Standard Specification for Forged or Rolled Alloy-Steel Pipe Flanges, Forged Fittings, and Valves and Parts for High-Temperature Service, ASTM A 182 (p. 93-106)

Standard Practice for Determining the Inclusion Content of Steel, ASTM E 45 (p. 61-73)

## II. Stainless Steel

### a.) General:

Stainless steel (sheet, plate, tube, bar & forgings) is purchased from a variety of domestic & foreign mills depending on price and availability. The acceptance criteria as indicated below vary somewhat depending upon the application within the tube. Forgings or vacuum melted material is used instead of wrought forms whenever the major work direction of the wrought form could result in elongated defects which would coincide with the direction of a possible leak path. In addition, vacuum melted (specifically, consumable electrode vacuum arc remelted) material is used for all stainless components near the cathode heater which are in a more critical position relative to potential outgassing. Type 304L is used in all locations except for the focus electrode and focus electrode support cup, which are made from 317L vacuum melted.

### b.) Chemistry

Samples of each piece of stainless purchased for use in klystrons (excluding some external parts, water fittings, etc.) are sent to an independent test lab for chemical analysis. Carbon & sulfur are analyzed by quantitative techniques, other elements by spectrographic analysis. Chemical composition must meet chemical requirements listed in the applicable ASTM specification (attached) and compare with chemical test reports supplied by the material manufacturer.

The material used for the focus electrode and focus electrode cup is type 317L modified. It is a non-standard grade and has the following composition.

Aluminum	(Al)	0.02%
Carbon	(C)	0.014%
Chromium	(Cr)	20.43%
Cobalt	(Co)	0.14%
Columbium	(Cb)	0.11%
Copper	(Cu)	0.30%
Manganese	(Mn)	1.55%
Molybdenum	(Mo)	4.09%
Nickel	(Ni)	19.83%
Phosphorus	(P)	0.022%
Silicon	(Si)	0.28%
Sulfur	(S)	0.005%
Titanium	(Ti)	0.01%
Vanadium	(V)	0.09%
Zirconium	(Zr)	0.005%

Alloy Type

317L Modified

### c.) Metallographic Testing

SLAC performs metallographic examinations of 2 or more samples from each piece of stainless steel used in the klystron (excluding external

parts). The inclusion content of the steel is rated in accordance with ASTM E45-84 method D (attached). For the more critical klystron components such as anode housing, anode plate, cathode parts and window flanges, the maximum allowable inclusion content is as follows:

	Type A	=	B	C	D
Heavy	1½		1	1½	1
Thin	1		1½	1	1½

These requirements are usually met only by vacuum melted material.

For less critical parts, those exposed to vacuum but not in high temperature or high field areas, the maximum allowable inclusion content is as follows:

	A	B	C	D
Heavy	1½	2	1½	2
Thin	2	2½	2	2½

Photo-micrographs are attached illustrating some of these conditions.

**Appendix B.5b: Material Certification and Testing**

Material Purchase Requisition (1)

Request for Order Shipping (1)

Laboratory Certificate - Anamet Laboratories, Inc. (1)

Materials Characterization (1)

Test Photographs (1)

Material Certification - Western Forge & Flange Co. (1)

**PURCHASE REQUISITION**  
**STANFORD UNIVERSITY**  
**STANFORD LINEAR ACCELERATOR CENTER**

Order Date \_\_\_\_\_ Requisition No. **74094-C**

Originator <b>earson/LEvy</b>	Bin No. <b>30</b>	Phone Ext. <b>2433</b>	Group <b>KLY</b>	Code <b>08A</b>
Authorization	Req'n. Date <b>05-08-85</b>	Date Required <b>10-01-85</b>		
Account Title	Account No.	Work Order No. <b>08-7030-6</b>		
Specific Delivery Point <b>(Clys./Mfg. Levy)</b>	Object	Budget Approval	Approved By <b>(Business Services Only)</b>	

*40945-A*  
*PA*

Expedite <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Inspection Required <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Attach Terms Cond. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Reporting Code		
Refer Inquires To Buyer	<input type="checkbox"/> 2575 Sand Hill Rd <input type="checkbox"/> Other - Specify Below <input type="checkbox"/> Below	
Telephone Authorization Purchasing		

Must Be Checked  
 Equipment is a Replacement  Special Handling or Packaging Requirement

Vendor Name	Delivery Date	Ship Via	F.O.B. Dest. Ship Pt.	Confirming To	Terms	P.O. Number

Item No.	Quantity	Unit	Item(s) Not Available in SLAC Stores <input type="checkbox"/>	Complete Description of Materials	Estimated Cost	DO NOT USE															
				Cross Forged 304L Vacuum Arc Remelted Cylinders, Rough Machined as follows:																	
1	100	ea		8 7/8" OD x 6 3/8" ID x 6 5/8" Long @ \$363.00	36,300.00																
	NOTE:			1) Certification of conformance to ASTM A182-F, and actual chemical test reports traceable to the mill heat lot number, must accompany each shipment.		Do not write in this section															
				2) Send additional copies of certifications and test reports via US Mail; Attn: Irwin Levy, Bin 30.																	
				3) All pieces to be from the same material heat lot.																	
				4) Heat lot and billet number to be stamped on each piece.																	
				5) Final inspection and acceptance will be at the SLAC, Menlo Park, CA. Non-conforming materials will be rejected.																	
				6) All tolerances + 1/16" - 0" (OD); + 0" - 1/16" (ID).																	
				7) Maximum allowable inclusion content rating shall be:																	
				<table border="1"> <thead> <tr> <th>TYPE</th> <th>MEDIUM</th> <th>HEAVY</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>1</td> <td>1/2</td> </tr> <tr> <td>B</td> <td>1 1/2</td> <td>1</td> </tr> <tr> <td>C</td> <td>1</td> <td>1/2</td> </tr> <tr> <td>D</td> <td>1 1/2</td> <td>1</td> </tr> </tbody> </table>	TYPE		MEDIUM	HEAVY	A	1	1/2	B	1 1/2	1	C	1	1/2	D	1 1/2	1	
TYPE	MEDIUM	HEAVY																			
A	1	1/2																			
B	1 1/2	1																			
C	1	1/2																			
D	1 1/2	1																			
				as defined in ASTM E-45, Method "D".																	
				8) No welding or other repair permitted.																	
				9) Recommended Vendors:																	
				a) Coulter Steel, Wayne, 4-653-2512																	
				b) Viking Metallurgical, Steve, 9-800-648-3768																	
				c) Western Forge & Flange, Bill, 6-727-7000																	
					36,300.00																

Contract No. If Other Than "515" \_\_\_\_\_  
 Suggested Vendors Below \_\_\_\_\_

Remarks: REF: Housing, Anode PF-700-867-42  
 1: 402-502  
 298-373 / Chris Book 6/84

PURCHASING CHOICE

Previous REQ: 9460

Requisition No. **74094-C**



ACCT. NO. FOR CHGS.  
12-0871

DEPARTMENT  
Klystron

REQUISITION#  
Bob Hoshida

Ext. 2433

PLU NO.  
84501:D

# REQUEST FOR SHIPPING ORDER

RETURN THIS

TO EXPEDITING - Bin 1

SHIP TO (COMPLETE ADDRESS)

Anamet Laboratories Inc.  
2827 Seventh St.  
Berkeley, CA 94710

VENDOR

SAME AS SHIP TO

### SPECIAL INSTRUCTIONS FOR ORIGINATOR:

- A. CONTAINS NO HAZARDOUS MAT'L ( STATEMENT ON REQ'N ( ) VERIFIED BY \_\_\_\_\_ UNLESS CHECKED BELOW.  
 ( ) EXPLOSIVE ( ) LASER ( ) RADIOACTIVE ( ) FLAMMABLE ( ) POISONOUS ( ) CORROSIVE ( ) X-RAY EQUIP.  
 ( ) OTHER RESTRICTED MATERIAL NOT LISTED/SPECIFY:
- B. ( ) DELICATE/FRAGILE MAT'L - SPECIFY.
- C. ( ) FOR NON-GOVERNMENT USERS ONLY - AMOUNT OF INSURANCE REQUESTED.

SUBCONTRACT NO. US 511370-MB	SHIP VIA Best Way	SHIPMENT		VENDOR RETURN AUTHORIZATION	DATE WRITTEN 2-6-86
		PREPAID XX	COLLECT		

QTY	QUANTITY	UNIT	DESCRIPTION / SERIAL NO. / DOE NO.	APPROX. WT & SZ.	REASON FOR SHIPMENT
1	1	lot	K911:1, 304L V.M. Forged Cyl.		Quantitative analysis for carbon and sulfur (leco) emission spectographic analysis.
2	1	lot	K911:2, " " " "		
3	1	lot	K922, 304L X-Forged Sample		
4	1	lot	K923, 1/4" DIA. 304L Stamped Disc		

Item 3. (K922) is Rush!

CT LOCATION OF MATERIAL:

FREIGHT CHGS.

SHIPMENT AUTHORIZED BY

OR:

Material Chemical Analysis CREDIT

REPLACEMENT

REWORK

FABRICATION

LOAN

VENDOR PROPERTY

WARRANTY

Remarks to Expediting:

70

LABORATORY CERTIFICATE

Anamet Laboratories, Inc.

2827 SEVENTH STREET

BERKELEY, CALIFORNIA 94710

(415) 841-5771

ANALYTICAL  
CHEMICAL  
METALLURGICAL

HIGH TEMPERATURE  
APPLIED RESEARCH  
PHYSICAL TESTING

February 14, 1986

LABORATORY NUMBER: 286.88 P.O. No. U.S. 511370-MB  
Req. No. 84501D  
Acct. No. 12-0871  
S.C. No. 04126

SUBJECT: Four Metal Coupons for Chemical Analysis

MARK: K911.1 & K911.2; 304L V.M. Forged Cyl., K922; 304L X-Forged Sample, K923; 1 1/4" Dia. 304L Stamping Disc.

DATE SUBMITTED: February 7, 1986

REPORT TO: Stanford Linear Accelerator Center  
2575 Sand Hill Road  
Menlo Park, California 94025  
Attn: Bob Hoshida, Bin 30

CHEMICAL ANALYSIS

Mark:	K911.1	K911.2	K922	K923
Aluminum (Al)	0.006%	0.006%	0.009%	0.005%
Carbon (C)	0.009%	0.013%	0.014%	0.025%
Chromium (Cr)	18.96%	18.90%	18.01%	18.81%
Cobalt (Co)	0.27%	0.28%	0.05%	0.10%
Columbium (Cb)	0.02%	0.02%	<0.005%	<0.005%
Copper (Cu)	0.34%	0.35%	0.47%	0.16%
Manganese (Mg)	1.21%	1.22%	1.60%	1.57%
Molybdenum (Mb)	0.49%	0.52%	0.22%	0.24%
Nickel (Ni)	10.65%	10.72%	10.56%	9.02%
Phosphorus (P)	0.022%	0.024%	0.022%	0.025%
Silicon (Si)	0.41%	0.40%	0.50%	0.29%
Sulfur (S)	<0.002%	<0.002%	<0.002%	0.016%
Titanium (Ti)	<0.005%	0.005%	0.007%	<0.005%
Vanadium (V)	0.12%	0.12%	0.05%	0.05%
Zirconium (Zr)	<0.005%	<0.005%	<0.005%	<0.005%
Alloy Type	304L	304L	304L	304L

These tests were performed in accordance with the purchase order.

Respectfully submitted,  
ANAMEI LABGRATORIES, INCCRPORATED

71

By E. A. Foreman  
E. A. Foreman  
Manager, Quality Control

5

304L VM Forging

MATERIALS CHARACTERIZATION

2-7-86

Sample \_\_\_\_\_

Date 6

Submitted by Bob Hoshida

Account No. 08-208-6 U.14.2

Phone Ext. 2433

Sample No. \_\_\_\_\_

Analysis to be performed:

IR

XRD

Emiss. Spec.

Mass. Spec.

SEM

Metallograph

EDAX

Auger

Inclusion

Microporosity

$\mu$ -Probe

RBS

ESCA

Other \_\_\_\_\_

Results:

Analyst: \_\_\_\_\_

Mount No: \_\_\_\_\_

Reported: \_\_\_\_\_


By \_\_\_\_\_

Channel: \_\_\_\_\_

Phone \_\_\_\_\_

Memo \_\_\_\_\_


Other \_\_\_\_\_



$D = \frac{1}{2}$

AH01

911.2



$D = \frac{1}{2}$

AA00

911.1

# WESTERN FORGE & FLANGE CO.

780 REED STREET 95050  
P.O. BOX 327 95052-0327  
SANTA CLARA, CALIFORNIA  
T.I.N. #94-1022981

PHONE (408) 727-7000  
TWX 910-338-0111  
TELEX 34-6448  
ELN #62819212

C  
U  
S  
T  
O  
M  
E  
R

Stanford Linear Accelerator Center  
P.O. Box 4349  
Stanford, CA 94305  
Attn: Accts Payable

S  
H  
I  
P  
T  
O

same  
2575 Sand Hill Road  
Menlo Park, CA 94025

INVOICE DATE

INVOICE NO.

PACKING LIST

WORK ORDER NO.

D 91268

DATE SHIPPED 1/6/86	DATE WANTED
CARRIER WFP Trk	FOB Dest
CARTONS & WT.	SHIP VIA
CHEM. & PHYSICAL W/FLANGES	MARK NO.
1	1
RESALE TAXABLE <input checked="" type="checkbox"/>	NON-TAXABLE <input type="checkbox"/>
1	RFQ 3713

CUST. P.O. NO. PO US 489950H	DATE REC'D 7/30/85	REC'D BY mail	SALESMAN BF	PARTIAL COMPLETE <input checked="" type="checkbox"/>	RESALE TAXABLE <input checked="" type="checkbox"/>	NON-TAXABLE <input type="checkbox"/>	1	1	RFQ 3713
---------------------------------	-----------------------	------------------	----------------	---	---	---	---	---	----------

74

ITEM NO.	QUANTITY	DESCRIPTION	HEAT NO.	PRICE	AMOUNT
3.	68	RINGS, CROSS FORGED & RMAO TO FIN: 8-7/8" O.D. + .060 - .000 6-3/8" I.D. + .000 - .060 6-5/8" Long + .060 - .000 A182 F-304L VAR. WITH INCLUSION RATING PER ASTM E45 METHOD D.	64278		

TERMS: NET 30 FROM DATE OF SHIPMENT

After 30 days SERVICE CHARGE is computed by a PERIODIC RATE 1 1/2% per month which is ANNUAL PERCENTAGE RATE of 18%.

CLAIMS FOR SHORTAGE WITHIN 5 DAYS AFTER R BE MADE OF GOODS.

**Appendix B.5c: Part Purchase Requisition to an Outside Vendor  
and Machining Specifications**

Part Purchase Requisition (1)

Specification - Machining Lubricants (1)

Specification - Machining, Polishing, Deburring (1)

Part Drawing, Anode Housing (1)

STANFORD UNIVERSITY  
STANFORD LINEAR ACCELERATOR CENTER

Originator <b>PEARSON/BEEBE</b>	Bin No. <b>30</b>	Phone Ext. <b>3602</b>	Group <b>KLY</b>	Code <b>08A</b>
Group Authorization	Req'n. Date <b>12-02-86</b>	Date Required <b>03-01-87</b>		
Account No. <b>SEE NOTES</b>	Work Order No. <b>SEE NOTES</b>			
Specific Delivery Point <b>TESTLAB KLY/MFG.</b>	Object	Budget Approval <i>[Signature]</i>	Approved By <i>[Signature]</i>	

Reporting Code  
**22-19-08**

Buyer  
**52-606-1000**

Refer Inquire To  
Buyer

Telephone Authorization Purchasing  
*[Signature]*

2575 Sand Hill Rd.  
Palo Alto, CA 94304  
S:  Above  
P:  Below

Dec 3 1 20 PM '86

Does Requisition Involve Hazardous Material?  Yes  No

Special Handling or Packaging Requirements

Inspection Required  Yes  No

Attach Terms Cond.  Yes  No

Item No.	Vendor Name	Delivery Date	Ship Via	F.O.B.	Confirming to	Terms	P.O. Number
A	Holz Products	2-16	Freight	X	Holz	1-10	
B		2-16			Ardytne		
C							
D							

Item No.	Quantity	Unit	Item(s) Not Available in SLAC Stores <input type="checkbox"/>	Complete Description of Materials	Estimated Cost	DO NOT USE
1	50	ea		PF-700-367-42-RO ANODE HOUSING (1682)	\$13,500.00	<i>2588/10/2</i>
NOTES:						
1) SLAC will provide all materials. SLAC will also provide all stress relieving, chemical cleaning and plating if applicable. Vendor will provide material heat lot traceability for each part. Parts will be bagged and tagged with part number and applicable material heat lot number. Vendor will return residual stock with piece parts. <del>XXXX</del>						
2) Material must be rough machined then stress relieved. Material returned for stress relieve must be free from burrs, chips and sharp edges.						
3) Quantities of plus or minus five percent (+5%) will be accepted.						
4) Vendor will use only SLAC approved machinists lubricants and abrasives per SC-700-866-47-R4 and SC-700-866-49-R1 for machining and polishing.						
5) Parts will be manufactured in strict accordance with drawing specifications. Vendor will provide a 100% general workmanship certificate of compliance. In addition vendor will provide a 100% dimensional inspection of at least 10% of the delivered parts. Parts inspected will be identified by tag traceable to individual inspection reports.						
6) Material supplied by SLAC will be identified with a material heat lot number. Finished parts must be traceable to this number, i.e. if more than one heat lot number is supplied, each part must be labeled with the heat lot number of the material from which it is made.						
				98% wof 08-7030-7 acct# 12-0873		
				2% wof 08-7030-8 acct# 12-0877		
					TOTAL	\$13,500.00

Gov't Contract No. If Other Than "SIS" \_\_\_\_\_

List Suggested Vendors Below

Remarks: T:429-479

CHAMP (6) 379-6550

M E (6) 227-7040

HOLZ (6) 943-9204

Requestion No. **24284 - E**

SC-700-866-47-R4 B

REV.	DESCRIPTION	DRN.	APR.	DATE
R4	REVISED & REDRAWN	H.G.	10/17/86	10/17/86

The following list of lubricants is approved for use in machining and fabricating components which will become part of a high vacuum system.

- |                                       |  |
|---------------------------------------|--|
| Relton A-9                            | Cimperial #1011                        |
| Tap Magic                             | Haloform CH-40                         |
| Tapmatic #1                           | Aqua Syn 55 (G-C Lubricants Co.)       |
| Tapmatic #2                           | Dip Kool 862                           |
| Rapid Tap                             | Trim Sol                               |
| Trim Tap                              | Trim 9106 CS                           |
| "Pearl" Kerosene by Chevron Chem. Co. | CINDOL 3102                            |
| "Tool Saver" by Do All Corp.          | Penwalt #DP 1131                       |
| Cutzol EDM 220-30                     | Cold Stream Coolant by Johnson Wax Co. |
| Sunnen Man-852 Honing Oil             |  |
| Vytron Concentrate                    |  |
| Rust-Lick G-25-J                      |  |
| Wheelmate #203                        |  |
| RD2-195                               |  |
| Dip Kool 868                          |  |
| Dip Kut 819H                          |  |
| Ho Sul #6871                          |  |
| Kool Mist #88                         |  |
| Cimcool 5 Star 40                     |  |

77

PROPRIETARY DATA OF STANFORD UNIVERSITY AND/OR U.S. DEPARTMENT OF ENERGY.  
 RECIPIENT SHALL NOT PUBLISH THE WITHIN INFORMATION WITHOUT SPECIFIC  
 PERMISSION OF STANFORD UNIVERSITY.

SCALE:	ITEM NO.	PREFIX	BASE	SUFFIX	TITLE OR DESCRIPTION	QTY.
UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES TOLERANCES: BREAK EDGES .003-.015 INTERNAL CORNERS .015 R MAX FRACTIONS 1/2 DEC. .XX .XXX ANGLES 1/2					DO NOT SCALE DRAWING	NEXT ASSEMBLY:
					STANFORD LINEAR ACCELERATOR CENTER U.S. DEPARTMENT OF ENERGY STANFORD UNIVERSITY STANFORD, CALIFORNIA	SPECIFICATION MACHINING LUBRICANTS 5045 KLYSTRON
					ENGR. <u>T. LEE</u> D/TS <u>H. GREENHILL</u> CHK <u>FJA 10-6-86</u>	APPROVALS <u>J.H.L. 10/17/86</u>
						SC-700-866-47-R4 B
					SH OF	M/F R4



B SC-700-866-49-R1

REV.	DESCRIPTION	DRN.	CHK	APP.	DATE
RI	REVISED & REDRAWN	BB	6/20/84	RTH	6/20/84

Acceptable techniques and materials for use in the machining, deburring, and polishing of klystron components.

I. Scope

This specification is required for the finishing of all klystron components which have surfaces communicating with the inside vacuum areas. The specification is invoked by referring to the specification number in the drawing notes, purchase order requirements, manufacturing notes, or work instructions.

II. Techniques

a. Machining

The preferred technique for finishing is by machining only, i.e. no abrasive or polishing compounds are to be used unless approved. All commonly available cutting tools are permitted. Metal removal other than by machining, such as grinding, honing, EDM, chem milling, etc. are expressly forbidden.

b. Deburring

Deburring shall be with file, deburring knife or permitted abrasive. Deburring by abrasive vibrating or tumbling is permitted only if medium is silicon carbide in conjunction with fluids expressly permitted per SLAC Spec. SC-700-866-47-R0. Deburring by any other unspecified technique is prohibited.

c. Polishing

If the surface finish requirements cannot be met by machining alone, then polishing with approved abrasives may be permitted. Care must be taken to avoid using excessive pressure during polishing so as to preclude contamination of surfaces by imbedded abrasives. Avoid any burnishing or excessive heating. Any evidence of imbedded contamination will be cause for rejection.

III. Materials

a. Fluids - Lubricants

Cutting fluids, lubricants, wetting agents, etc. for use in machining or polishing are limited to those expressly permitted per SLAC Spec. SC-700-866-47-R0.

b. Abrasives

Abrasives for use in polishing klystron components are limited to the following:


3M Scotch Brite	Type S, Silicon Carbide (Gray Color) Type A, Aluminum Oxide (Maroon Color) Note: Type S is available in ultra fine (500 grit equiv.) while Type A is available in very fine (240 grit equiv.).
3M Wetordry Fabricut Cloth	Aluminum oxide or silicon carbide (available in 600 grit equiv.).

PROPRIETARY DATA OF STANFORD UNIVERSITY AND/OR U.S. DEPARTMENT OF ENERGY. RECIPIENT SHALL NOT PUBLISH THE WITHIN INFORMATION WITHOUT SPECIFIC PERMISSION OF STANFORD UNIVERSITY.

78

SCALE:	ITEM NO.	PREFIX	BASE	SUFFIX	TITLE OR DESCRIPTION	QTY.
UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES TOLERANCES: BREAK EDGES .005-.015 INTERNAL CORNERS .015R MAX FRACTIONS ± DEC. .X .XX .XXX ANGLES ± ALL SURFS. ✓	DO NOT SCALE DRAWING				NEXT ASSEMBLY:	
	STANFORD LINEAR ACCELERATOR CENTER U.S. DEPARTMENT OF ENERGY STANFORD UNIVERSITY STANFORD, CALIFORNIA				SPECIFICATION MACHINING, POLISHING, DEBURRING KLYSTRONS	
	ENGR C. DEARSON	APPROVALS		SC-700-866-49-R1		B
	DRS B. BOHL					
	CHK R. T. H.					
					SH OF	M/F/R1

REV.	DESCRIPTION	DRN.	CHK.	APP.	DATE
1	ADDED FINISH CHAIN LINE	JGS	FJA	REV	4/10



- NOTES:
- STRESS RELIEVE AT 950°-1000°C FOR 10-20 MIN. WITH FAST COOL BEFORE FINAL MACHINING
  - ALL RADII MUST BE FULLY BLEND - NO FLATS, STEPS OR TOOL MARKS PERMITTED
  - USE ONLY SLAC APPROVED MACH'G FLUIDS PER SC-700-566-47
  - SURFACES SHOWN WITH 16/ FINISH TO BE POLISHED PER SC-700-566-49

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES.  
 TOLERANCES:  
 BREAK EDGES .005-.015  
 INTERNAL CORNERS .015 R MAX  
 FRACTIONS ±  
 DEC. .X  
 .XX .010  
 .XXX .005  
 ANGLES ± 5° ALL SURFS. 32/

SCALE: 1/1  
 DO NOT SCALE DRAWING  
 STANFORD LINEAR ACCELERATOR CENTER  
 U. S. DEPARTMENT OF ENERGY  
 STANFORD UNIVERSITY STANFORD, CALIFORNIA  
 PROPRIETARY DATA OF STANFORD UNIVERSITY AND U.S. DEPARTMENT OF ENERGY. RECIPIENT SHALL NOT PUBLISH THE INFORMATION WITHIN UNLESS GRANTED SPECIFIC PERMISSION OF STANFORD UNIVERSITY  
 DATE: 12/16/81  
 AUTH: [Signature]  
 TITLE: [Signature]  
 CHKD: RTH 12-15-83

ITEM NO.	PREFIX	BASE	SUFFIX	TITLE OR DESCRIPTION	QTY.
-				TUBE, 304L FORGED SS	
				STOCK OR PART NO.	
				NEXT ASSEMBLY: SA-700-567-41	
				HOUSING, ANODE 5045 KLYSTRON	
				PF 700-567-42-R1	C

PF-700-567-42-R1 C

**Appendix B.5d: Part Inspection and QC Reports**

Inspection Report, Anode Housing (2)

Cover Sheet, Lot Inspection Report (1)

Master Inspection Report in Master File (1)

PART NAME HOUSING, ANODE				ASSY. 5045				PF/SA # PF-700-867-42-RO				REPORT # 0024							
REQ # 1682				BATCH/SN #				Insp'd By:		Ht. Lot		Date		Page					
Qty. 28		Rej. $\emptyset$		Accept 28		VENDOR HOLZ PRECISION				SEL BELOW		5-26-87		1 OF 2					
SN # +	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419
Dimensions +																			
30° ± 1/2°																			
8.00 ± .010																			
7.250 ± .005																			
6.500 ± .005																			
HAND MEASURE																			
15° ± 1/2°																			
3.12 ± .010																			
.75 ± .010																			
3.00 ± .010																			
1.22 ± .010																			
.163 ± .004(2X)																			
.060 ± .005																			
8.560 ± .002																			
1.002   A   B																			
.50 ± .010 R (3X)																			
1.875 FULL RADIUS 756																			

18

PART NAME HOUSING, ANODE				ASSY. 5045				PF/SA # PF-700-867-42-R0				REPORT # 0024			
REQ #		Rej.		Accept		BATCH/SN #				Insp'd By:		HE. Lot		Date	Page
Qty.						VENDOR									= 03 2

SN # +	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419
Dimensions +																			
.500 ± .005																			
// .002   A																			
.140 ± .005																			
// .002   A																			
6.510 ± .005																			
□ .001   -A -																			
8.750 ± .005																			
↑↑ .001   A   B																			
-B-																			
15° ± 1/2°																			
8.25 ± .010																			
7.998 ± .003																			
↑↑ .002   A   B																			
7.500 ± .003																			
↑ .001   A   B																			
7.22 ± .010																			
1.394 ± .005																			
// .002   A																			
8.750 ± .005																			
↑↑ .001   A   B																			

.0012

SHOP # 1682  
 EQ. # 24284-E  
 P.O. # 619285

PART # PF-700-867-42RO  
 DESCRIPT. ANODE HOUSING  
 HT LT # PARTS MARICED K911, K756

VENDOR HOLZ PRECISION P.L. # 5-13/5-14

	RECEIVING			Q.C.		QTY			DATE
	DATE	QTY	LOC	DATE	BY	ACC	REJ	RTU	RTU
1	5-14-87	28	FLOOR	5-26-87	<i>[Signature]</i>	28	<del>0</del>		
2									
3									
4									

(1) REMARKS

(2) REMARKS

(3) REMARKS

(4) REMARKS

I.R. # 0024

**SPECIAL INSTRUCTIONS:**  
 See Enclosed Q.C. Blueprint.  
 RED: Level "A", 100% Inspection.  
 YELLOW: Level "B", 10% Inspection plus 100% when any discrepancies are found.  
 GREEN: Level "C", Visual plus 1% Inspection.  
 \* Asterisk indicates discrepancies must be dispositioned by full MRB. i.e. Project Engineer, Production Manager, and Q.C. Manager. Other items may be dispositioned by Production Manager or Q.C. Manager, alone.  
**MASTER INSP. REPORTS IN MASTER FILE**

**SPECIAL GAUGING METHODS:**  
 1) Check all <sup>100</sup> finish surfaces 100% visual. Per note #2.  
 2) Check finish visually on all grooves.  
 FACSIMILE GAGE FOR 15° .50R, 15° 4.100R AND 2.290 IN BOX ON TOOL SHELF  
 CHECK 16 USING TYPE QC ANPLIMETER & PROFILOMETER IF QUESTIONABLE  
 Validate Program G5

L O T	R E V	DATE	VENDOR	R E M A R K S	SERIAL NO.	QTY	REQ. NO.	HEAT LOT NO.	CLASS OF DEFECT			INSP. DISP.		INSP. REPORT NO.	INSP. INIT.	REMARKS
									A	B	C	A	B			
1	Ø	5-16-84	Remett Hopkins		17-16	16	46	15-097				16	Ø	0001	J/D	OK
2			CHAMP		17-26	10	56436	K-235	✓			10	Ø	0002	J/LW	RTU 16
3	Ø	7-27-84	Champion		27-30	10	56436	K-235				10	Ø	0003	J/R	No-changes
4		10-8-84	Champ		37-45	9	56436	11-231				9	Ø	0004	J/R	RTU Recheck - heat etc
5	Ø	12-12-84	EDWARDS													
5	Ø	10-30-84	CHAMP		46-64	19	56436	234				19	Ø	0005	LW	
6	Ø	12-12-84	EDWARDS		66-75	10	59496	349				10	Ø	0006	J/LW	
7	Ø	1-7-85	EDWARDS		76-95	20	"	"				20	Ø	0007	J/LW	
8	Ø	1-7-85	EDWARDS		96-115	20	51911	349				20	Ø	0008	J/LW	
9	Ø	4-15-85	CHAMP		116-128	77	70158	497				77	Ø	0009	J/LW	WAT/ARB 4-8-85
10	Ø	8-21-85	CHAMP		127-128	16	8963	K-646				16	Ø	0010	J/LW	
11	Ø	8-24-85	CHAMP		191-208	16	8963	K-646				16	Ø	0011	J/LW	
12	Ø	8-24-85	CHAMP		209-218	16	8963	K-646				16	Ø	0012	J/LW	
13	Ø	10-3-85	CHAMP		249-250	11	8963	K-645				11	Ø	0013	J/LW	
14	Ø	10-10-85	CHAMP		229-238	10	8963	K-645				10	Ø	0014	J/LW	WAT 4-10-85 RTU LW
15	Ø	10-10-85	CHAMP		239-248	10	8963	K-645				10	Ø	0015	J/LW	WAT 4-10-85 RTU LW
16	Ø	10-11-85	CHAMP	✓	201-207 208	3	"	"				3	Ø	0011	J/LW	
16	Ø	10-16-85	CHAMP		249-263	15	8963	K-645				15	Ø	0016	J/LW	NO PROBLEMS
12	Ø	10-23-85	CHAMP	✓	211, 212 214, 215	4	8963	K-646				4	Ø	0012A	J/LW	
17	Ø	10-31-85	CHAMP	✓	232	1	8963	K-645				1	Ø	0014	J/LW	SCRAP
15	Ø	10-31-85	"	✓	244-248	2	"	K-645				2	Ø	0015	J/LW	
16	Ø	12-7-85	EDWARDS		264-343	80	78211	K-356				80	Ø	0016	J/LW	RTU 10
16	Ø	2-11-86	"	✓	6-12	77	"	"				77	Ø	0016A	J/LW	2-RTU
16	Ø	2-15-86	EDWARDS		265, 271 243	3	1342	K-356				3	Ø	0016B	J/LW	1-RTU
17	Ø	8-13-86	CHAMP		344-396	53	1572	K-911				53	Ø	0017	J/LW	JOE
18	RED	12-3-86	KLYSTRON	✓	C.R.	5	M-1776	N/R				5	Ø	0018	J/LW	SPECIALS 1/CHR
19	RED	1-6-87	KLY		108, 109, 110 400	3	5A591	N/R				3	Ø	0019	J/LW	2.0 SEE 10.0053
20	Ø	1-20-87	KLY	✓	C.I.R.	7	1823	-				7	Ø	0019	J/LW	
21	Ø		KLY	✓	C.I.R.	3						3	Ø	0020	J/LW	
21	Ø	2-17-87	KLY	✓	C.I.R.	9	1734	N/R				9	Ø	0020	J/LW	2.5
22	Ø	2-18-87	"	✓	C.I.R.	9	Ø	-				9	Ø	0021	J/LW	
23	Ø	2-24-87	KLYSTRON	✓	C.I.R.	9	1752	N/R				9	Ø	0022	J/LW	2HC
23	Ø	4-6-87	KLYSTRON	✓	SN 14	1	1752	N/R				1	Ø	0022A	J/LW	
24	Ø	5-26-87	Holz		401-428	28	1682	C.R.				28	Ø	0024	J/LW	20
25	Ø	7-1-87	Holz Precision		429-452	24	1682					24	Ø	0025	J/LW	
25	Ø	7-21-87	Holz Precision	✓	436	1	"	"				1	Ø	0025	J/LW	

**Appendix B.5e: Tube Manufacturing Reports**

Bake Section Report (1)

Collector Section Report (1)

Klystron Autopsy Inspection (1)

Window Bake and Inspection Sheets (4)

Gun Section Report (1)

Cavity Section Report (1)



**BAKE SECTION**  
TUBE-NO 5045-349a

TUBE-TYPE: 5045 CATHODE-NO: SP-329-5C  
 BAKE-STN-NO: 3 DATE-ON: 11 15 186  
 AUTO-SCHL: 5045 MANUAL-SCHL: \_\_\_\_\_  
 AUTO-REY: Q3 MANUAL-DATE: 1 1  
 SPECIAL COMMENTS: \_\_\_\_\_

	DATE	TIME	PRESS	I <sub>f</sub>	TEMP	
01. YENT-STN	11 15 186	11:00				
02. VESSEL-RGH	11 15 1	12:30				
03. ACH-BAKE-1	11 16 1	04:00	1.6 E-5	15.6	550	
04. FIN-BAKE-1	11 11 1	08:10	2.4 E-8	30.0	550	
05. START-COOL	11 12 1	(18:00)	(1.0 E-8)	(34.0)	430	
06. LEAK-CHK	11 13 1	07:12	1.4 E-9			LEAK? YES / (NO)
			1.4 E-9			CMTS:
07. HOT-SHOT	11 13 1	:	E-			MIN: 15
			E-			AMPS: 41
08. STRT-EMM	11 13 1	09:45	1.0 E-8	34.8		EXT-PROC 22 hrs @ 37 A
09. FIN-EMM	11 14 1	08:25	7.0 E-9	35.0		76 mA @ 114 Volts
10. FIN-APP	11 14 1	08:15	7.2 E-9	35.0		APP-PUMP-CURRENT: 3 μA
11. PINCH-OFF	11 14 1		1.9 E-9			
			1.9 E-9			
12. REMOVE	11 14 1					DELIVERY TO: <u>Test</u>
13. DELIVER	11 14 1					CERAMIC RES: <u>9.5 E+8 Ω</u>

HRS-INSTALL => 1.5 DAYS-BAKED => 8  
 (02-01) (06-02)  
 HRS-BAKE-1 => 128 DAYS-ON-STN => 9  
 (04-03) (12-01)  
 HRS-BAKE-2 => 34 BAKE-DISP => pass  
 (05-04)  
 PROCESS-COMM-1 => gassy during initial age.

PROCESS-COMM-2 => \_\_\_\_\_

EXPER-NO => \_\_\_\_\_  
 (Please separate numbers with commas)

**COLLECTOR SECTION**  
**TUBE-NO 5045- 349a**

**Note :** For each item, don't write the value if it is the same as the value given here.

SEGMENT	BASE DIAMETER	ALPHA	LENGTH
1	1.500	45	1.381
2	3.030	∞	3.200
3	3.030	∞	3.200
4	3.030	∞	3.600
5	3.030	04	3.125
6	2.633	06	3.125
7	1.996	15	1.875
8	1.010	15	1.527

COLL-COMMENTS : \_\_\_\_\_  
 \_\_\_\_\_

**ASSEMBLY**

READY-DATE 10/28/86 WELD-DATE 10/28/86 by [Signature]  
 (initials)

SPECIAL-CHAR : \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

EXPER-NO : \_\_\_\_\_  
 (Please separate numbers with commas)

Klystron Autopsy Inspection

Inspected by: .....

Tube No. 349a .....

Date: .....

Cathode:

Focus Electrode & Gun Stem:

Alignment: Parallel: + ..... - ..... Concent:

Anode & Housing:

Drift Tubes:

Window(s):

Cavities:

Collector:

Other:

5045 WINDOW

FINAL INSPECTION SHEET

\*\*\*\*\*  
\* Window # 2114 \*  
\*\*\*\*\*

Date Ring Tested 10-17-86

OK (X) Fail ( )

ceramic mat'l: AL-995  
sleeve mat'l: CU  
sleeve #: ~~887~~ 887

\*\*\*\*\*  
\* approved use rejected date initial \*  
\* (X) ( ) 10-22-86 SH \*  
\*\*\*\*\*



Microscopic examination of bevel area

Top side:

edge arcing (yes) (no)  
arc spots (yes) (no)

SMALL PIT W/DARK SPOT ON TOP SIDE.  
REMOVED ~~THE~~ SURFACE PARTICLES  
SOME DARK SPOTS IN CERAMIC  
LOOKS OK

Bottom side:

edge arcing (yes) (no)  
arc spots (yes) (no)

REMOVED SURFACE PARTICLES  
SOME DARK SPOTS IN CERAMIC  
LOOKS OK


Visual examination of both surfaces

List:

TOP: ONE SMALL PIT MARK TOP SIDE. IS OK  
defect(s): BOT- NO DEFECTS

discoloration(s): DISCOLORATION OF CERAMIC DUE  
TO COATING

Backlight examination of both surfaces



Ring date examination

WINDOW SECTION  
TUBE-NO 5045-349A

please circle: LEFT RIGHT WINDOW

ISSUE-DATE: 10/28/86

WINDOW-NO	=> <u>2114</u>	CERAMIC-MAT	=> _____
SLEEVE-MAT	=> <u>Cu</u>	METALLIZING	=> <u>NiO<sub>2</sub></u>
CERAMIC-EDGE	=> <u>Beveled</u> / <u>STRAIGHT</u>		
COAT-DATE	=> <u>9-24-86</u>	COAT-TYPE	=> <u>TiN</u>
COAT-METHOD	=> <u>D.C. sputt</u>	TIME/SIDE	=> <u>65</u> (min)(sec)
COAT-PRESS	=> <u>50.0 MTORR</u>	COAT-VOLTAGE	=> <u>2.8 KV</u>
F-TOP-FRONT	=> <u>64</u> Hz	F-TOP-REAR	=> <u>129</u> Hz
F-BOTTOM-FRONT	=> <u>71</u> Hz	F-BOTTOM-REAR	=> <u>150</u> Hz
GAS-MIX	=> <u>40% OF N<sub>2</sub></u> / <u>60 % OF AR</u>		
RING-TEST-DATE	=> <u>10 / 17 / 86</u>		

CENTER TEMP, UNCOOLED, 6μS, 40MW, 43.2KW	=> <u>54</u>	°C
CENTER TEMP, UNCOOLED, 6μS, 60MW, 44.8KW	=> <u>62</u>	°C
SLEEVE TEMP, UNCOOLED 43.2KW	=> <u>55.8</u>	°C
SLEEVE TEMP, UNCOOLED 64.8KW	=> <u>62.4</u>	°C

RING OBSERVATIONS => BRIGHT GREEN GLOW THRU (SHORT TEST)

POST TEST OBSERVATIONS => \_\_\_\_\_

RECOAT-DATE	=> _____	RECOAT-TIME	=> _____ (min sec)
RECOAT-CURRENT	=> _____	RECOAT-RESULTS	=> _____
WINDOW-COMMENTS	=> <u>PRE BAKED 600°C For 24 hrs</u>		

EXPER-NO => \_\_\_\_\_

(Please separate numbers with commas)

FINAL INSPECTION SHEET

\*\*\*\*\*  
\* Window # 2124 \*  
\*\*\*\*\*

Date Ring Tested 10-18-86

OK (X) Fail ( )

ceramic mat'l: AL-995  
sleeve mat'l : CU  
sleeve # : 1061

\*\*\*\*\*  
\* approved use rejected date initial \*  
\* (X) ( ) 10-20-86 GH \*  
\*\*\*\*\*

*[Handwritten signature]*

Microscope examination of brace area

Top side:

edge arcing (yes) (no)  
arc spots (yes) (no)

REMOVED SURFACE PARTICLES.  
SOME DARK SPOTS IN CERAMIC  
LOOKS GOOD

Bottom side:

edge arcing (yes) (no)  
arc spots (yes) (no)

REMOVED SURFACE PARTICLES  
COUPLE OF BURN SPOTS REMOV  
SOME DARK SPOTS IN  
CERAMIC  
LOOKS GOOD


Visual examination of both surfaces

List:

defect(s): TOP - COUPLE OF DARK SHADED AREAS, LOOKS OK UNDER MICROSCOPE  
BOT - ONE DARK SHADED AREA, LOOKS OK UNDER MICROSCOPE.

discoloration(s): DISCOLORATION OF CERAMIC DUE TO COATING

Back-light examination of both surfaces



Ring data examination

**WINDOW SECTION**  
TUBE-NO 5045-349A

please circle: LEFT / RIGHT WINDOW

ISSUE-DATE: 10/28/86

WINDOW-NO	=> 2124	CERAMIC-MAT	=> AL-995
SLEEVE-MAT	=> Cu	METALLIZING	=> NiO <sub>2</sub>
CERAMIC-EDGE	=> Beveled / <u>Stratoh</u>		
COAT-DATE	=> 10-2-86	COAT-TYPE	=> TiN
COAT-METHOD	=> D.C. Sputt	TIME/SIDE	=> 6.5 (min) <u>sec</u>
COAT-PRESS	=> 50.0 mTorr	COAT-VOLTAGE	=> 2.8 kV
F-TOP-FRONT	=> 82 Hz	F-TOP-REAR	=> 154 Hz
F-BOTTOM-FRONT	=> 67 Hz	F-BOTTOM-REAR	=> 119 Hz
GAS-MIX	=> 40% OF N <sub>2</sub> / 60% OF Ar		
RING-TEST-DATE	=> 10 / 18 / 86		
LOSSES, COOLED, 6 μS, 100MW, 108KW	=> 70.0		Watts
CENTER TEMP, COOLED, 6 μS, 100MW, 108KW	=> 54		°C
CENTER TEMP, UNCOOLED, 6 μS, 50MW, 54KW	=> 54		°C
CENTER TEMP, UNCOOLED, 6 μS, 25MW, 27KW	=> 40		°C
SLEEVE TEMP, UNCOOLED, 54KW	=> 58.2		°C
SLEEVE TEMP, UNCOOLED, 27KW	=> 46.0		°C
RING OBSERVATIONS	=> MED BLUE EDGES THRU (LONG TEST)		
POST TEST OBSERVATIONS	=>		
RECOAT-DATE	=>	RECOAT-TIME	=> (min sec)
RECOAT-CURRENT	=>	RECOAT-RESULTS	=>
WINDOW-COMMENTS	=> PRE BAKED 600°C For 24 hrs		

EXPER-NO =>

(Please separate numbers with commas)

### GUN SECTION

TUBE-NO 5045- 349a

NOTE : Example of a value for Pressure:  $3.2 \text{ E-}8$  ( where  $3.2 \text{ E-}8 = 3.2 \times 10^{-8}$  )

GUN-NO	=> <u>SA-316</u>	CATHODE-NO	=> <u>SP-329-5c</u>
GUN-USED-IN	=> <u>New</u>	CATH-USED-IN	=> <u>New</u>
FE-NO	=> <u>SA-370</u>	CATHODE-TYPE	=> <u>Scandate</u>
FE-USED-IN	=> <u>New</u>	CATH-AN-SPAC	=> <u>1.691</u>
FE-SPAC	=> <u>(0.216)</u>	MOUNT-DATE	=> <u>101 281 86</u>
FIN-PRESS-HOT	=> <u>9.7 E-8</u>	HEATER-RES	=> <u>.0624 <math>\Omega</math></u>
FIN-PRESS-COLD	=> <u>0.3 E-8</u>	HV-SEAL	=> <u>LI-139</u>
VAC-FIRE-STN	=> <u>4</u>	A	=> <u>.496</u>
CONCENTR	=> <u>.001</u>	B	=> <u>.467</u>
PARALLEL	=> <u>.00075</u>	C	=> <u>.463</u>
GUN-COMMENTS	=> _____		

PHASE-NO	TEMP	AMPS	VOLTS	PRESS.	HOURS	RF
1	<u>1015°C</u>	<u>31.7</u>	<u>14.0</u>	<u>1.5 E-6</u>	<u>20.5</u>	<u>(ON) / OFF</u>
2	<u>1017°C</u>	<u>32.0</u>	<u>14.1</u>	<u>6.1 E-7</u>	<u>18.0</u>	<u>(ON) / OFF</u>
3	<u>1119°C</u>	<u>36.6</u>	<u>17.7</u>	<u>3.0 E-7</u>	<u>18.0</u>	<u>(ON) / OFF</u>
4	<u>1010°C</u>	<u>31.5</u>	<u>14.1</u>	<u>6.7 E-8</u>	<u>6.5</u>	<u>(ON) / OFF</u>
5	<u>1038°C</u>	<u>33.4</u>	<u>15.4</u>	<u>6.0 E-8</u>	<u>6</u>	<u>ON / (OFF)</u>
6	<u>1073°C</u>	<u>35.1</u>	<u>16.7</u>	<u>9.7 E-8</u>	<u>1</u>	<u>ON / (OFF)</u>

EXPER-NO => \_\_\_\_\_  
 (Please separate numbers with commas)

GUN AUTOPSY

GUN-AUT-COMM=> \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

FE-COMMENTS=> \_\_\_\_\_

CATH-COMMENTS=> \_\_\_\_\_

AUTO-CONCENTR=> \_\_\_\_\_

AUTO-PARALLEL=> \_\_\_\_\_



**CAVITY SECTION**  
**TUBE-NO 5045-349a**

Cavity #	1	2	3	4	5	6	Date	Initials
SPEC'S MHz	2860±3	2855±2	2877±2	2887±2	2935±7	2853±3,-8		
Q <sub>e</sub>	175±25					16.5±1,-3		
CLAMPED MHz	2856.1	2858.2	2874.3	2883.4	2932.5	2857.1		
Q <sub>e</sub>	173					18.0		

FINAL MHz	2857.6	2862.0	2874.9	2883.7	2932.2	2848.2	10/24/86	AN
ADJUST MHz		2855.1	2876.4	2888.0				
FINAL Q <sub>e</sub>	206					16.2		
A-IN:	I-201		A-GAIN:		G-196		A-OUT:	
					0-197			

RECHECK MHz					/		/ /	
READJUST MHz					/			
RECHECK Q <sub>e</sub>								

CAVITY COMMENTS :

EXPER-NO :

(Please separate numbers by commas)

**Appendix B.5f: Tube Assembly Reports**

Klystron Final Assembly Procedure (4)

Anode Housing Assembly Sheets (2)

KLYSTRON FINAL ASSEMBLY PROCEDURE.

Uyeda/Sirois Jan.85

Tube Serial No. 349-a

Date Assembled 10-28-86

1. Check sub-assemblies for serial numbers:

- |             |              |               |                   |
|-------------|--------------|---------------|-------------------|
| a. Input    | <u>201</u>   | e. Recombiner | <u>RV-49</u>      |
| b. Gain     | <u>196</u>   | f. Collector  | <u>C-175</u>      |
| c. Output   | <u>197</u>   | g. Anode      | <u>AH-211</u>     |
| d. Splitter | <u>SV-49</u> | h. Gun        | <u>SP-329 S.C</u> |

2. Dimensions (indicate name of person doing the work)

	<u>Reading</u>	<u>Engraving</u>	<u>SWIM THICKNESS</u>
a. Gap btwn. 2a & 2b drift tubes	<u>.029</u>	_____	_____
b. Gap btwn. 5a & 5b drift tubes	<u>.021</u>	_____	_____
c. Dim. 2.125" on 2a drift tube	<u>2.130</u>	_____	_____
d. Dim. 2.122" on 2b drift tube	<u>2.126</u>	_____	_____
e. Dim. 2.125" on 5a drift tube	<u>2.130</u>	_____	_____
f. Dim. 2.122" on 5b drift tube	<u>2.120</u>	_____	_____

3. Install H<sub>2</sub>O jackets on Gain Sub-Assembly

4. Clean stacking mandrel with acetone and ether

5. Clean ceramic ring and place on mandrel

6. Stack Sub-Assemblies on mandrel. Check for foreign objects, scratches, etc:



Note: 1. 2 people needed, to guide pieces.

Ar

2. All heliarc eyelets to be cleaned  
with ether before assembling.

Ar

a. Input section .

Ar

b. Gain Section (Orient correctly to Input)

Ar

c. Output Section (Orient correctly to Gain)

Ar

d. Bolt the 3 sections together

Ar

7. Lift Assembly with nylon sling and place on  
"cold test" cart (2 people required)

Ar

8. Bolt on 2 dummy windows and the recombiner section  
(3 bolts/flange snug fit - not torqued)

Ar

9. Transport to Cold Test Area

Ar

10. Have Tube Engineer indicate disposition of tube  
with his signature

Accept \_\_\_\_\_ Reject \_\_\_\_\_

11. Lift Assembly from cold test cart with nylon  
sling and place on a tube stand (2 people required)

Ar

12. Blow off flanges with filtered N<sub>2</sub> and remove  
dummy windows

Ar

13. Install permanent windows:

- a. Record serial no. or nos. 2114 2129
- b. Blow off faces of window(s) with N<sub>2</sub> Juan
- c. Blow off Recombiner flanges with N<sub>2</sub> Juan
- d. Bolt window(s) in place:
  - 1. Install 1 stud/window Juan
  - 2. Torque nuts to 17 ft/lbs using a 180° criss-cross pattern Juan
  - 3. Use WG alignment tool for single windows Juan

- b. Blank off WG flange Juan

14. Install Collector and weld Welder: Juan

- 15. Install Collector H<sub>2</sub>O Jacket
  - a. Add the Lifting Fixture Juan

16. Lift Assembly from tube cart with nylon sling Juan

- 17. Weld heliarc eyelets
  - a. Gain to Output Welder: Juan
  - b. Gain to Input Welder: Juan

18. Weld icon pump flange Welder: Juan

19. Weld blank-off disc on input Welder: Juan

20. Install Gun Assembly:

- a. Visual check of drift tube for foreign objects, etc.
- b. Clean anode nose with ether
- c. Blow off Focus Electrode with filtered N<sub>2</sub>
- d. Orient Gun Assembly with Input
- e. Attach with 4 studs
- f. Weld eyelets

Jim L. U  
Jim L. U  
Jim L. U  
Jim L. U  
Jim L. U  
Jim

Welder

21. Attach 8 liter ion pump. Orient properly to leave room for its magnet

Jim

22. Leak check with H<sub>2</sub> Leak Detector

a. Output side of window(s)

Name:

Jim

b. Tube side of window(s)

Name:

Jim

23. Weld H<sub>2</sub>O Jackets on Gain Section

Welder:

Jim

24. Place tube back on a tube stand

Jim

25. Complete "Blue Sheet" with Travel Folder

Jim

26. Turn Tube and Travel Folder over to Bake Shop personnel

Jim

Received

ANODE HOUSING

SERIAL NO. AH-211  
*Used Anode Housing.*

ITEM	NO.	SERIAL NO.
PUMPOUT RING	PF-700-860-60	A/A
HELIARC RING (short)	PF-700-861-12	H
HELIARC RING (long)	PF-700-861-13	G
ANODE HOUSING	PF-700-861-42	#42 b
ANODE HOUSING RING	PF-700-867-43	SA-116-A

SERIAL NO. AH-178b in #350

ITEM	NO.	SERIAL NO.
PUMPOUT RING	PF-700-860-60	B3/A
HELIARC RING (short)	PF-700-861-12	A
HELIARC RING (long)	PF-700-861-13	H
ANODE HOUSING	PF-700-861-42	SN-310
ANODE HOUSING RING	PF-700-867-43	SA-350A/SN-176

SERIAL NO. <sup>In #351</sup> AH-113b Reworked. From #254

ITEM	NO.	SERIAL NO.
PUMPOUT RING	PF-700-860-60	A/A
HELIARC RING (short)	PF-700-861-12	G
HELIARC RING (long)	PF-700-861-13	G
ANODE HOUSING	PF-700-861-42	SN-215
ANODE HOUSING RING	PF-700-867-43	SA-288a-SN-244

SERIAL NO. AH-212 #352a

ITEM	NO.	SERIAL NO.
PUMPOUT RING	PF-700-860-60	A/B3
HELIARC RING (short)	PF-700-861-12	<del>SA</del> G
HELIARC RING (long)	PF-700-861-13	SN-I
ANODE HOUSING	PF-700-861-42	SN-311
ANODE HOUSING RING	PF-700-867-43	SA-381

EXPERIMENT # 0269 "024

ASSEMBLY	SERIAL NO.
BASE	B-101
CATHODE ASSY.	SA-395 7.7x10 <sup>5</sup> after Wake
PELLET	SP-418-5C/ E.C.
H.V. SEAL	LI-186 No Nucleations.
ANODE HOUSING	85 B rework.
INPUT	199
GAIN	187
OUTPUT CAVITY WAVEGUIDE	202
OUTPUT SPLITTER	SV-48
WINDOW (LEFT)	2093 <sup>2</sup> Suspect leak Replaced with 2104
WINDOW (RIGHT)	2126
OUTPUT RECOMBINER	RV-77
ION PUMP	HIA 6099
COLLECTOR	G-172

TUBE NO. 349a

10-28-86

ASSEMBLY	SERIAL NO.
BASE	A-44b
CATHODE ASSY.	SA-316
PELLET	SP-329-5C
H.V. SEAL	LI-139 has Nucleations
ANODE HOUSING	AH-211
INPUT	201
GAIN	196
OUTPUT CAVITY WAVEGUIDE	197
OUTPUT SPLITTER	SV-49
WINDOW (LEFT)	<del>2114</del>
WINDOW (RIGHT)	2124
OUTPUT RECOMBINER	RV-49
ION PUMP	HIA 6088
COLLECTOR	C-175



**Appendix B.5g: Tube Bake Processing Reports**

Klystron Processing Check List (4)

Processing Schedule Authorization (1)

Klystron Bake Processing Log (4)

Process Graphs (5)

Tube Process Report - Station Log (1)

KLYSTRON PROCESSING CHECK LIST  
Revision 5/8/86 -- "BAKE LIST"

S/N & REWORK LEVEL 349a STATION# 3  
TUBE TYPE 5045 DATE 11-5-86

-----  
INITIAL EACH STEP WHEN COMPLETED

Station Preparation

RB Check station status and maintenance list  
RB Ion gauge spare filament available for tube & vessel  
RB Cooling air and heat tape switches properly set  
RB Station vented and logged

Tube Preparation

RB Borescope Inspected  
RB Input connector removed.  
RB All tape and foreign matter removed  
RB O'rings removed  
RB Appendage pump orientation and bolt clearance okay  
RB Appendage pump heat shield installed and ground spring removed  
RB Folder received from tube shop  
RB Proper collector water jacket  
RB Visual inspection

Tube Installation

RB Let-up fixture purged with nitrogen  
RB Tube vented. Handle CAREFULLY  
RB Pinch-off flange and station flange visually inspected  
RB Tube valved-in and logged  
RB Filament continuity normal 11.8 .8  
RB All thermocouples working  
RB Waveguide blown out using high pressure N2  
RB Tube body not visually shorted to ground  
RB Bellows restraint adjusted and plate installed  
RB All thermocouples not shorted by visual inspection  
RB Heat shields on gun, input, and appendage pump  
RB Earthquake restraints installed  
RB Window pump started or leak rate  $\leq$  1mT per second  
RB All foreign matter cleared and base plate blown off  
RB Wipe down O'ring  
RB Window manifold number 14  
AN Second person visually check

Vessel Installation

~~BB~~ Vessel oven power cord connected (fan on Sta #5)  
~~BB~~ Groundstrap on vessel  
~~BB~~ Water lines connected  
~~BB~~ Bake status switch correct  
~~BB~~ Interlocks complete; except 28  
~~BB~~ Vessel roughing and logged  
~~BB~~ Schedule authorization obtained  
~~BB~~ Paperwork initiated, folder obtained, schedule  
authorization posted, summary sheet and graph  
labeled  
~~BB~~ Log tube on calendar  
~~BB~~ Set-up fan on ion pump  
~~BB~~ Enter tube on computer and in logbook  
~~BB~~ Vessel valved-in, interlocks complete and computer  
normal

Before Leak Check

~~BB~~ Computer prompt "LEAK", or all TC's  $\leq 150C$   
~~BB~~ Vessel gate valve and bypass valve shut  
~~BB~~ RGA tuned to helium  
~~BB~~ Helium purged  
~~BB~~ Readings logged

Leak Check

~~BB~~ Vent vessel  
~~BB~~ Log tube leak check status  
~~BB~~ Log O/P waveguide leak status. Subsequent leak check  
needed? Yes X No       
~~BB~~ Wait until TC#3  $\leq 100$  degree C  
~~BB~~ Remove vessel  
~~BB~~ Vent window manifold  
~~BB~~ Log through window leak status  
~~BB~~ Appendage pumps started  
~~BB~~ Heat shields removed  
~~BB~~ Start filament pre-stabilization  
~~BB~~ Waveguide cover installed  
~~BB~~ Retorqued bolts and log

Before Emission

~~BB~~ Hot shot complete, and fil back to operating condition  
~~BB~~ Record appendage pump current, then disconnect  
~~BB~~ Hook up high voltage equipment, and check visually for  
shorted tube body

BM

Set up safety equipment. Clear ladder and bystanders.

End Emission

BB  
BB  
BB  
BB  
BB

Pressure & emission current OK or notify supervisor  
High voltage off (Fil. on)  
Appendage ion pump on (Fil. on)  
Log final readings with filament on  
Filament off. Tube cooling for pinch

Before Pinch-off

BB  
BB  
BB  
BB  
JH  
BT

Bellows support properly adjusted  
Rubber grommet in place  
Pinch-off tool properly centered and leveled  
Pump-out tubing oiled  
Second person checks set-up  
Log pressure before pinch-off. Must be normal

After Pinch-off

BB  
BB  
BT  
BB  
BB  
BB  
BB  
BB

Log after pinch-off pressure  
Conclude computer processing and sign out logbook  
Leak check pinch-off  
Epoxy  
Pinch-off cup installed  
Input installed and covered  
Evaluate need for sandblasting. Sandblasted?  
Yes X No \_\_\_\_\_  
Gun ceramic resistance check

$$\frac{9.5}{\text{meter reading}} \times 10^6 \text{ megohms} \times \frac{10}{\text{switch multiplier}} \times \frac{10}{\text{volt meter multiplier}} = 9.5 \times 10^8 \text{ Ohms}$$

BB  
BB  
BB  
BB  
BB

Notify supervisor if resistance <  $1 \times 10^6$  ohm.  
Water jacket leak checked  
O/P waveguide leak checked if required. Checked?  
Yes X No \_\_\_\_\_  
O/P blown out using high pressure N2 and properly sealed.  
Plastic bag over gun  
Log tube off calendar  
Final visual inspection by Mike or Chuck

Delivery

BB

Tube delivered to Test cage, noted on blackboard;  
Person notified: X Lu

BL

BB

Tube delivered to Mechanical; Person notified \_\_\_\_\_  
Appendage pump started and logged  
Paperwork complete; tube folder, processing folder  
etc.

-----  
RETURN COMPLETED CHECKLIST TO CHUCK

PROCESSING SCHEDULE AUTHORIZATION BAKE DETAIL DATA

STATION NO: 3	DATE ON: 11 / 5 / 86
TUBE TYPE: 5045	S/N: 349a

SPECIAL FEATURES :

CATHODE S/N: SP-329-SC

SCHEDULE :	REV. NO: 03
AUTOMATED <input checked="" type="checkbox"/> MANUAL <input type="checkbox"/>	

HIGH BAKE TEMPERATURE: 550°C FILAMENT: 30.A

LOW BAKE TEMPERATURE: 430°C FILAMENT: 31.A

APPROVED BY Rebecca Bussard DATE 11-5-86

[Signature] 11/5/86

BAK

# S.L.A.C. KLYSTRON BAKE PROCESSING LOG

STATION# 3  
TUBE# 349g

DATE 11-5-86

TIME	FILAMENT		STATION ION PUMP CURRENT	WINDOW ION CURRENT APPENDAGE ION CURRENT	TEMPERATURE °C				EMISSION		'T' TAPES 'A' AIR	TUBE PRESSURE	VESSEL PRESSURE	INITS	COMMENTS	
	AMPS	VOLTS			TC1	TC2	TC3	AVG.	H.V. TRIAC SET	CURRENT TRIAC CURRENT						
11:00					Station Valve							1.8-9				BD
11:50			.75 mA		Tube Valve					1W		6.8-7				BB
12:03			.6 mA									1.8-7				BB
12:30			.42 mA		Vessel Pumping							1.0-7				BB
13:00			.3 mA		DP Valve				1W			5.9-8	10-5			BB
13:25	11.6	.7	.25 mA	2 mA								4.8-8	2.0-5			BB
15:00	11.3	1.5	.6 mA	4.7 mA								1.0-6	4.5-6			BD
17:15	11.9	2.1	1.35 mA	1.0 mA	60	75	75		8	3.2	-	2.0-7	8.0-6			cy Set TSP
			pump for 100 mA auto calibration. (K12 continuous scan)													
21:45	11.9	2.4	2.8 mA	3.8 mA	290	290	330		30	8.7	T	3.0-6	3.2-5			VN
046	15.6	4.7	12.1 mA	10.5 mA	555	565	575		34	8.7	T	1.6-5	2.8-5			STB
972	22.9	8.5	57 mA	4.2 mA	515	555	545		41	9.9	T	6.2-6	1.4-5			RM
17:05	50.0	13.0	2.3 mA	1.7 mA	550	555	540		29	7.8	T	2.5-6	4.3-6			BB
14:30	29.9	13.0	1.4 mA	1.4 mA	550	555	540		29	7.8	T	1.7-6	3.2-6			BB
21:00	24.5	12.8	8.0 mA	.9 mA	560	555	550		30	8.0	T	1.0-6	2.1-5			VN
0355	29.7	13	4.9 mA	.6 mA	565	575	560		30	8.6	T	5.0-7	1.5-6			TS
0411	29.5	12.9	3.7 mA	.46 mA	565	570	560		30	7.7	T	4.7-7	1.3-6			RM
11:55	29.9	13.1	2.2 mA	.27 mA	545	550	535		27	7.8	T	2.1-7	4.6-7			BB
16:39	29.9	13.0	1.56 mA	.25 mA	550	555	535		19	5.3	T	1.7-7	3.9-7			cy
21:45	30.0	13.2	1.16 mA	170 mA	550	555	535		28	7.0	T	1.3-7	3.3-7			VN
04:00	29.9	13.1	.91 mA	120 mA	550	560	540		27	7.0	T	1.0-7	2.4-7			STB
15:00	30.0	13.1	.7 mA	85 mA	560	565	550		27	7.4	T	7.8-8	2.7-7			BT
16:00	29.9	13.1	.7 mA	80 mA	560	565	550		27	7.5	T	7.8-8	2.8-7			BT
17:00	29.9	13.1	.68 mA	78 mA	560	565	550		27	7.5	T	7.5-8	2.8-7			BT
18:00	29.7	13.0	.65 mA	70 mA	560	565	550		27	7.4	T	7.1-8	2.7-7			BT
19:00	29.9	13.1	.63 mA	69 mA	560	565	550		27	7.3	T	7-8	2.7-7			BT
20:00	29.9	13.1	.6 mA	64 mA	560	565	550		27	7.3	T	6.7-8	2.6-7			BT

108

S.L.A.C. KLYSTRON BAKE  
PROCESSING LOG

STATION# 3  
TUBE# 349a

DATE 11-8-86

TIME	FILAMENT		STATION ION PUMP CURRENT	WINDOW ION CURRENT APPENDAGE ION CURRENT	TEMPERATURE °C				EMISSION		'T' TAPES 'A' AIR	TUBE PRESSURE	VESSEL PRESSURE	INITS	COMMENTS
	AMPS	VOLTS			TC1	TC2	TC3	AVG.	H.V. TRIAC SET	CURRENT TRIAC CURRENT					
2100	29.9	13.1	.58mA	60µA	580	565	550		27	7.1	T	6.3-8	2.5-7	BT	
2200	29.9	13.1	.55mA	58µA	560	565	550		27	7.2	T	6.1-8	2.5-7	BT	
2300	29.1	13.1	.53MA	55µA	560	565	550		27	7.1	T	6.0-8	2.5-7	LC	
0000	29.9	13.1	.50MA	53µA	560	565	550		27	7.4	T	5.8-8	2.5-7	LC	
0100	29.9	13.1	.50MA	50µA	560	565	550		27	7.2	T	5.7-8	2.4-7	LC	
0200	29.9	13.1	.47MA	50µA	560	565	550		27	7.1	T	5.5-8	2.3-7	LC	
0300	29.9	13.1	.45MA	47µA	560	565	550		27	7.3	T	5.4-8	2.2-7	LC	
0400	29.9	13.1	.43MA	45µA	560	565	550		27	7.4	T	5.3-8	2.2-7	LC	
0500	29.9	13.1	.43MA	43µA	560	565	550		27	7.1	T	5.2-8	2.1-7	LC	
0600	29.9	13.1	.45MA	40µA	560	565	550		27	7.0	T	5.0-8	2.1-7	LC	
0700	29.9	13.1	.43MA	40µA	560	565	560		27	7.1	T	4.8-8	2.1-7	LC	
1500	29.9	13.0	.4mA	36µA	560	565	550		27	7.6	T	4.4-8	2.1-7	BT	
1600	29.9	13.1	.4mA	36µA	560	565	550		27	7.6	T	4.4-8	2.1-7	BT	
1700	29.9	13.0	.38mA	34µA	560	565	550		27	7.6	T	4.3-8	2.1-7	BT	
1800	29.8	13.0	.32mA	30µA	550	560	540		24	6.9	T	3.8-8	1.8-7	BT	
1900	29.9	13.1	.32mA	30µA	560	560	540		20	8.2	T	3.8-8	1.8-7	BT	
2000	29.9	13.1	.32MA	30µA	550	560	540		22	6.3	T	3.8-8	1.8-7	BT	
2100	30.0	13.1	.3mA	30µA	550	560	540		29	7.9	T	3.7-8	1.8-7	BT	
2200	29.9	13.1	.3mA	30µA	550	560	540		25	7.0	T	3.7-8	1.9-7	BT	
2300	30.0	13.1	.3MA	27µA	550	560	540		20	6.7	T	3.5-8	1.8-7	LC	
0000	29.8	13.0	.28MA	27µA	550	560	540		27	7.3	T	3.4-8	1.7-7	LC	
0100	30.0	13.1	.28MA	27µA	550	560	540		27	7.6	T	3.4-8	1.7-7	LC	
0200	29.9	13.0	.28MA	27µA	550	560	540		25	7.0	T	3.3-8	1.7-7	LC	
0300	30.0	13.1	.28MA	25µA	550	560	540		25	6.7	T	3.3-8	1.7-7	LC	
0400	30.0	13.1	.28MA	25µA	550	560	540		25	6.8	T	3.2-8	1.6-7	LC	
0500	29.9	13.1	.25MA	25µA	550	560	540		25	6.7	T	3.1-8	1.6-7	LC	
0600	30.0	13.1	.25MA	25µA	550	565	540		27	7.2	T	3.0-8	1.6-7	LC	





S.L.A.C. KLYSTRON BAKE  
PROCESSING LOG


STATION# 3  
TUBE# 349a

DATE 11-13-86


TIME	FILAMENT		STATION ION PUMP CURRENT	WINDOW ION CURRENT APPENDAGE ION CURRENT	TEMPERATURE °C				EMISSION		'T' TAPES 'A' AIR	TUBE PRESSURE	VESSEL PRESSURE	INITS	COMMENTS	
	AMPS	VOLTS			TC1	TC2	TC3	AVG.	H.V.	CURRENT						
									TRIAC SET	TRIAC CURRENT						
1115	35.0	16.3	45 mA						1KV	76 MA		9.4-9			AB	
1130	36.0	16.3	47 mA						1KV	75 MA		1.0-8			AB	
1145	35.0	16.2	46 mA						1KV	74 MA		1.0-8			AB	→ 37 A
	Not in M		not a	Round	Process	w	1.20 V	1.0				Gassy	tube			procedure
1200	36.9	17.7	80 mA						1KV	75 MA		1.8-8			BB	
1300	36.9	17.8	91 mA						1KV	77 MA		2.0-8			BB	
1355	36.9	17.7	87 mA						1KV	77 MA		1.9-8			BB	
1500	36.9	17.7	86 mA						1KV	79 MA		1.9-8			BB	
1702	36.9	17.7	82 mA						1KV	70 MA		1.8-8			BB	
1900	36.9	17.7	79 mA						1KV	72 MA		1.6-8			BB	
035	36.9	17.6	70 mA						--	--		1.5-8	4.0-7		JS	
0701	36.9	17.7	68 mA						1KV	81 MA		1.5-8			BB	→ 35 A
0701	35.3	16.6	56 mA						1KV	79 MA		1.1-8			BB	
0800	35.0	16.1	35 mA						1KV	76 MA		7.0-9			BB	1KV off
0808	34.9	16.1	36 mA	.7 mA					—	—		7.3-9			BB	
0815	35.0	16.2	36 mA	.6 mA								7.2-9			BB	fil off
0818	—	—	18 mA	.3 mA								2.7-9			BB	
1040	—	—	11 mA	.3 mA								1.9-9			BB	Bobo Pinch
1042	—	—	11.4 A	.34 A								1.9-9			JH	AFTER PINCH

111


Tube 5045 Serial 0349A on Station 3 05-NOV-86




Tube 5045 Serial 0349A on Station 3 05-NOV-86




Tube 5045 Serial 0349A on Station 3 05-NOV-86



Tube 5045 Serial 0349A on Station 3 05-NOV-86



Tube 5045 Serial 0349A on Station 3 05-NOV-86



Tube Process Report

1 STATION LOG OD:[300,303]50450349A.KDL CREATED AT 13:16:29 05-NOV-86 BY PROCE

Step	Step Start Time	Step Finish Time	Temperature		Tube Pressure		Filament	
			Min	Max	Min	Max	Min	Max
4	17:48 05-NOV-1986	09:49 07-NOV-1986	566.2	566.2	3.1E-07	3.1E-07	29.7	29.7
7	09:49 07-NOV-1986	10:25 11-NOV-1986	474.6	555.3	8.6E-09	2.5E-07	29.9	30.0
8	10:25 11-NOV-1986	09:40 12-NOV-1986	430.2	430.2	1.4E-08	1.4E-08	34.0	34.0
11	09:40 12-NOV-1986	17:42 12-NOV-1986	428.7	432.9	1.3E-08	1.4E-08	33.9	34.1
12	17:42 12-NOV-1986	22:34 12-NOV-1986	306.0	431.2	1.8E-09	1.3E-08	4.0	33.9
13	22:34 12-NOV-1986	03:22 13-NOV-1986	155.8	293.6	1.5E-09	1.8E-09	3.4	4.1
14	03:22 13-NOV-1986	09:00 13-NOV-1986	24.6	155.8	1.3E-09	1.5E-09	0.0	30.0
15	09:00 13-NOV-1986	09:26 13-NOV-1986	22.9	24.6	1.4E-09	4.3E-09	29.8	34.9
16	09:26 13-NOV-1986	09:58 13-NOV-1986	23.0	23.8	6.0E-09	8.9E-09	35.0	35.0
17	09:58 13-NOV-1986	10:18 13-NOV-1986	24.2	24.4	5.0E-08	6.0E-08	40.7	40.9
18	10:18 13-NOV-1986	10:34 13-NOV-1986	24.2	24.6	7.6E-09	9.3E-09	35.2	35.3
19	10:34 13-NOV-1986	10:36 13-NOV-1986	24.2	24.2	6.5E-09	6.5E-09	35.0	35.0
20	10:36 13-NOV-1986	10:54 13-NOV-1986	24.2	24.3	4.7E-09	6.5E-09	34.9	35.1
21	10:54 13-NOV-1986	08:32 14-NOV-1986	23.3	29.1	1.5E-09	1.8E-08	0.0	37.3
0	08:32 14-NOV-1986	08:32 14-NOV-1986	23.5	23.5	4.8E-09	4.8E-09	0.0	0.0
22	08:32 14-NOV-1986	10:54 14-NOV-1986	21.2	23.5	1.9E-09	4.8E-09	0.0	0.0
23	10:54 14-NOV-1986	10:54 14-NOV-1986	21.8	21.8	1.9E-09	1.9E-09	0.0	0.0



## Appendix B.5h: Klystron Test Reports

Index of Klystron Test Notes (2)  
Test Stand Summary Sheet (1)  
Tube Data Summary Sheet (1)  
Processing Data Summary (1)  
Interlock and Safety Check (1)  
Emission Check (1)  
Process Performance Data Work Sheet (5)  
Test Sheet (2)  
Heat Run Sheet (1)  
Acceptance Test Report (1)  
Final Test Data Summary (1)  
Specification Conformance Summary (1)  
Klystron Checkoff Sheet (1)  
Acceptance Performance Data Work Sheet (5)  
Stability Check Form (2)  
Acceptance test Report (1)

KLYSTRON TESTING NOTE	DATE	01/26/87	KTN-01 (Revision 40)
TITLE	INDEX OF TEST NOTES	AUTHOR	E. LaClair

The following is a list of material on klystron testing as of the above date. In addition, all operators are expected to be familiar with the material listed under "TRAINING MATERIALS."

KLYSTRON TESTING NOTES

	TITLE	DATE REVISED
01 Rev.40	Index of Klystron Test Notes	01/26/87
02 Rev.4	Load Installation Guidelines	08/21/86
03 Rev.3	General Test Stand Information	08/22/86
04 Rev.5	Engineering Data Graphs	08/22/86
05	Cathode Cooling/Load Vac. Let-up	08/22/86
06	Test Operator Skills	08/22/86
07	5045 Installation/Removal	08/22/86
08 Rev.14	5045 Pre-Processing (1 $\mu$ s)	10/23/86
09 Rev.19	5045 Processing (3.5 $\mu$ s)	01/26/87
10 Rev.5	T/L Check on 5045 Klystron	11/20/86
11	Magnet Supply Run-down	04/29/84
12 Rev.8	Round Tank Processing	01/26/87
13	Thyratron Ranging	09/11/84
14 Rev.2	5045 Stability Check	12/05/86
15	Magnet Mating Test	11/14/85
16 Rev.2	T/S Start-up & Shut-down	12/10/85
17 Rev.15	5045 Final Test	01/26/87
18 Rev.2	5045 CDR/ Check/Set Procedures	01/27/86
19	Epx/Mismatch Check	03/04/85
20	Operating Data on 5045 Klystron	04/19/84
21	Operating the CALF	11/14/84
22	Klystron Aging Room	02/04/85
23	Window Testing Procedure	02/04/85
24 Rev.4	5045 Break Up Check	11/11/85
25	Data Acquisition Procedure	05/05/85
26 Rev.3	Power Balance Calculation	08/14/86
27	Tube Interception Calculation	04/02/85
28	XK5 Gallery Return Test	04/09/85
29 Rev.1	XK5 Final Test	07/08/85
30 Rev.4	5045 Gallery Return Test	04/11/86
31	E/M Focusing Interlock Protection	04/24/85
32 Rev.3	5045 Frequency Response Check	11/13/85
33	Window Thermocouple Installation	04/17/86
34	Sub-Booster Testing	05/12/86
35	Sub-Booster Power Out/Drive Curve	05/12/86
36 Rev.1	Barton Turbine Flow Measurements	08/27/86

MAINTENANCE NOTES

	<u>TITLE</u>	<u>DATE REVISED</u>
MN 29	Removal and Installation of Windows for Ring Testing	05/23/85

TRAINING MATERIALS

TECHNICAL SPECIFICATION SC-700-866-45-R3 SLAC 5045 KLYSTRON  
Performance Data Work Sheet  
Klystron Test Sheet  
Heat Run Sheet  
Radiation Check  
Power Data Form  
Installing a Klystron Tube  
Slippery Perveance Test  
Input VSWR Check  
Stability Check (XK-5)  
Acceptance Test Report  
Thyratron Ranging  
Klystron Emission Check  
The Brazing Furnaces  
Checking Breakdown Resistance of Pulse Transformer Oil  
T/L Check  
Breakup Check  
Scope Sweep Linearity Check  
Safety Memos

KLYSTRON TEST LAB FORM

KTF-008A

T SECTION

TUBE-NO 5045 2494 TEST-START-DATE 11-21-86

TOTAL-HV-HOURS 77.0 TOTAL-FIL-HOURS 81.6

TEST STAND	LOAD NO.	TYPE TEST	START DATE	MAGNET NO.	ELMA	FOCUS BUCK	CURRENT TOP	BOTTOM	EF START	IF END	EPY KV	PRF Hz	TRF us	P-O MW	FAULT NO./HRS	AM Y-N
08	110-46	Pre-Press	11-21-86	5005	15.0				12.6/30.0	12.6/30.0	350	180~	1.0	64.6	1/2	N
FM Y-N	HUM Y-N	IND Y-N	GLITCH Y-N	RUBBER Y-N	BODY delta t	BREAKUP NO./MIN	STABILITY +	-	TUBE PRESSURE START	END	COLOR	WINDOW FLASH	LEFT T	RIGHT T	TEST HV	HOURS FIL
N	N	N	N	N/A	.16	N/A	+2	-3	0.1	0.1	MARK	N	25.6	35.5	18.9	26.4

COMMENTS:

TEST STAND	LOAD NO.	TYPE TEST	START DATE	MAGNET NO.	ELMA	FOCUS BUCK	CURRENT TOP	BOTTOM	EF START	IF END	EPY KV	PRF Hz	TRF us	P-O MW	FAULT NO./HRS	AM Y-N
7	110-46	P	11-24-86	5005	14.8				12.6/30.0	12.3/29.0	350	180	3.5	64	1/4	-
FM Y-N	HUM Y-N	IND Y-N	GLITCH Y-N	RUBBER Y-N	BODY delta t	BREAKUP NO./MIN	STABILITY +	-	TUBE PRESSURE START	END	COLOR	WINDOW FLASH	LEFT T	RIGHT T	TEST HV	HOURS FIL
-	N	N	N	N	0.25	-	2	3	0.1	0.2	Y	N	31.1	32.2	35.3	31.5

COMMENTS:

TEST STAND	LOAD NO.	TYPE TEST	START DATE	MAGNET NO.	ELMA	FOCUS BUCK	CURRENT TOP	BOTTOM	EF START	IF END	EPY KV	PRF Hz	TRF us	P-O MW	FAULT NO./HRS	AM Y-N
7	110-46	P	11-25-86	5005	14.7				12.6/30.0	12.3/29.0	350	180	3.5	65	1/30	N
FM Y-N	HUM Y-N	IND Y-N	GLITCH Y-N	RUBBER Y-N	BODY delta t	BREAKUP NO./MIN	STABILITY +	-	TUBE PRESSURE START	END	COLOR	WINDOW FLASH	LEFT T	RIGHT T	TEST HV	HOURS FIL
N	N	N	N	N	.38	0/15	2	3	0.2	0.2	Y	N	41.3	43.5	37.8	36.1

COMMENTS:

TEST STAND	LOAD NO.	TYPE TEST	START DATE	MAGNET NO.	ELMA	FOCUS BUCK	CURRENT TOP	BOTTOM	EF START	IF END	EPY KV	PRF Hz	TRF us	P-O MW	FAULT NO./HRS	AM Y-N
FM Y-N	HUM Y-N	IND Y-N	GLITCH Y-N	RUBBER Y-N	BODY delta t	BREAKUP NO./MIN	STABILITY +	-	TUBE PRESSURE START	END	COLOR	WINDOW FLASH	LEFT T	RIGHT T	TEST HV	HOURS FIL

COMMENTS:

TEST STAND	LOAD NO.	TYPE TEST	START DATE	MAGNET NO.	ELMA	FOCUS BUCK	CURRENT TOP	BOTTOM	EF START	IF END	EPY KV	PRF Hz	TRF us	P-O MW	FAULT NO./HRS	AM Y-N
FM Y-N	HUM Y-N	IND Y-N	GLITCH Y-N	RUBBER Y-N	BODY delta t	BREAKUP NO./MIN	STABILITY +	-	TUBE PRESSURE START	END	COLOR	WINDOW FLASH	LEFT T	RIGHT T	TEST HV	HOURS FIL

COMMENTS:

K L Y S T O N T E S T L A B F O R M KTF-008B DATA SUMMARY  
 TUBE-NO 5045 3/9 OPERATING EF 12.1 OPERATING IF 12.0  
 PULSE LENGTH 3.5 PPS 180 END-TUBE PRESSURE 0.3 ua

FOCUS CURRENTS		BUCK	TOP	BOTTOM	ELMA				
EPY KV	Ik A	Pave KW	Pout MW	uk	Pdr W	GAIN sat	EFF %	HUM @ dB	
315									
AM @ dB		FAULT NO./HRS	MISSED PULSES	IF @ TL	CHANGE IN Ik %	CHANGE IN IF	WINDOW LEFT	TEMPS RIGHT	SUMMARY BY
									JE
EPY KV	Ik A	Pave KW	Pout MW	uk	Pdr W	GAIN sat	EFF %	HUM @ dB	
320	36.3	27.8	47.3	2.00	497	49.7	40.1	1.2	-3
AM @ dB		FAULT NO./HRS	MISSED PULSES	IF @ TL	CHANGE IN Ik %	CHANGE IN IF	WINDOW LEFT	TEMPS RIGHT	>>>>>>
11	-3		0				40.0	11.7	
EPY KV	Ik A	Pave KW	Pout MW	uk	Pdr W	GAIN sat	EFF %	HUM @ dB	
350	41.3	40.1	65.0	2.00	327	32.7	41.3	1.1	-3.0
AM @ dB		FAULT NO./HRS	MISSED PULSES	IF @ TL	CHANGE IN Ik %	CHANGE IN IF	WINDOW LEFT	TEMPS RIGHT	>>>>>>
12	+2.0	2/20	0	28	1.93	20	41.3	45.3	

COMMENTS:

DISPOSITION	DATE	COMMENTS:
HOLD		help - for focussing
ACCEPT		
RETURN		

122

PROCESSING DATA SUMMARY

TUBE # 349a  
MAGNET # 5005  
LOAD # A1a-4b  
DATE IN 11-24-86

TEST STAND # 7  
HVRT 30.3  
HFRT 31.5  
DATE OUT 11-25-86

*Rec'd  
1. Lee  
12/1/86*

epy, KV	ik Amps	Pdr Watts	Pout MW
315	—	—	—
320	362	553	45.0
350	413	362	64.5

Focus Current	
BUCK	—
MAIN/ELMA	14.8
TOP	—

WINDOW: COLOR Yes ARCING N FLASHING N

MAXIMUM WINDOW TEMPERATURES: LEFT 31.1 RIGHT 32.2 PRR 180

F.F.E. FAULTS:

350 KV 15/MIN 320KV 15/MIN 315KV 15/MIN

PULSE STABILITY:

350KV SAT	320KV SAT	315KV SAT
+2 dB	+2 dB	+2 dB
-3 dB	-3 dB	-3 dB

FAULT RATE: 1 fault in last 4 hrs

RADIATION: Normal around tube, above normal around tank

ABNORMALITIES: —

COMMENTS: —

DISPOSITION: Released to Acceptance

DATA SUMMARIZED BY: [Signature]

APPROVED BY: \_\_\_\_\_

INTERLOCK AND SAFETY CHECK

DATE 11-24-86

TUBE 3499

TEST STAND # 07

FIL. CONTINUITY Before test ok STB After test \_\_\_\_\_  
(minimum) UNITS (set)

WATER FLOW (Low Limit) Tube 15 GPM 15.0 GPM 15.0 ✓  
Load 15 GPM 15.0 GPM 15.0 ✓  
XFMR ✓ Flow ok

VAC ION SUPPLIES (High Limit) (maximum) Tube 1 X 10<sup>-7</sup> 1 X 10<sup>-7</sup> 2.30 TRIP  
Load 1 X 10<sup>-6</sup> (0-270KV) 1 X 10<sup>-6</sup> TRIP  
Load 4 X 10<sup>-7</sup> (270-320KV) 5 X 10<sup>-7</sup> 3.70 TRIP

FOCUS SUPPLIES Klixon Connected ✓ Body Connected ✓  
Under Current Amps ✓ Polarity ✓  
Enter Focus Settings — 15.0 —  
(Bucking) (Middle) (Upper)

FILAMENT Zero Reset ✓ Time Delay 60 min  
Under Current 4.6 Proper Value (V/I) 30.0

TUBE TANK Oil Level ✓ Tank Flow N/A

LEAD SHIELDING Kwacshoc  
Collector ✓ Collector Cap ✓  
Magnet: Sides ✓ Top \_\_\_\_\_ Bucking Coil \_\_\_\_\_  
Check Vac Ion Cables = Tied Down ✓  
Ground Clip Connected ✓  
Interlock Lamps = Replace if Needed No

Comments: All meters zeroed Operator STB

STATION 07

TUBE 349a

DATE 1/24/86

HVRTM 2748.9

FRTM 8692.1

PRR 60v


INITIAL  $I_r$  30.0

FINAL  $I_r$  30.0

FOCUS — 15.0 —

P <sub>r</sub> SATURATION DATA								
E <sub>r</sub>	14.1	12.7	11.5	10.2				
I <sub>r</sub>	32.0	30.0	28.0	26.0				
Fil. W	451	381	322	265				
e <sub>py</sub> KV	350							
i <sub>k</sub> A	417	415	407	390				
μK	2.01	2.00	1.97	1.88				
P <sub>t</sub> μa	0.5	0.1	0.1	0.1				
Stbl Rng	0/-3	+2/-3	+2/-3	+2/-3				
Time	0900	0600	0700	0800				

Comments: \_\_\_\_\_





INITIAL (1μs)
✓ PROC. (3.5μs)
ACCEPTANCE
FINAL
(OTHER)

ROUND TANK ONLY	
PTT	119
PT	57-733
CDR	5312:1
NEW CDR	

TUBE #	3499
MAGNET	5005
LOAD	A10-4b
T/S #	07
OPERATOR	STB

INSTALLED HVRTM: 2741.5 FRM: 8686.5 TOTAL FRM: TOTAL HVRTM: (6.1)

START OF SHIFT	HVRTM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR			
2:00	—	12.5	12.5	30.0	30.0	60~			
TIME	TUBE VAC	LOAD VAC	FOCUS	EOLC	R/E	HVOC	WINDOW C°	H <sub>2</sub> O	
	0.1 μa	3.5 μa	— 5.0 —	FLTS		FLTS	LEFT RIGHT	IN °C	
0045	Interlock check complete - HV on @ 150KV, 119A, 2.05μk								
0100	P175KV, 150A, 2.05μk - Sat. FRC=1.0μs ⊕ ⊕ ⊕ 22.0 22.2 21.6								
0115	P200KV, 184A, 2.06μk - Sat. FRT=.02 ⊕ ⊕ ⊕								
0130	P225KV, 217A, 2.03μk - Sat. FRT=.02 ⊕ ⊕ ⊕ 22.2 22.3 21.8								
0145	P250KV, 255A, 2.04μk - Sat. FRT=.02 ⊕ ⊕ ⊕								
0200	P260KV, 271A, 2.04μk - Sat. FRT=.02 ⊕ ⊕ ⊕ 22.4 22.6 21.9								
0215	P270KV, 286A, 2.01μk - Sat. FRT=.02 ⊕ ⊕ ⊕ 22.7 22.6 21.9								
0230	P280KV, 302A, 2.04μk - Sat. FRT=.03 ⊕ ⊕ ⊕ 22.7 22.8 21.6								
0245	P290KV, 319A, 2.04μk - Sat. FRT=.03 ⊕ ⊕ ⊕ 22.9 23.0 21.9								
0300	P300KV, 333A, 2.03μk - Sat. FRT=.05 ⊕ ⊕ ⊕ 23.2 23.4 22.0								
0315	P310KV, 350A, 2.02μk - Sat. FRT=.06 ⊕ ⊕ ⊕ 23.2 23.5 21.9								
0330	P320KV, 366A, 2.02μk - Sat. FRT=.06 ⊕ ⊕ ⊕ 23.2 23.4 21.8								
0345	P330KV, 382A, 2.02μk - Sat. FRT=.06 ⊕ ⊕ ⊕ 23.3 23.5 21.8								
0400	P340KV, 398A, 2.01μk - Sat. FRT=.06 ⊕ ⊕ ⊕ 23.6 23.7 21.9								
0415	350KV, Sat. LFD expanding trf=3.5μs ⊕ ⊕ ⊕								
0500	350KV - Begin T/L check ⊕ ⊕ ⊕ 26.2 26.4 21.7								
0655	350KV - Sat								
	Total Fawilts (2) (1)								
	2750.6								
	2741.5								

HVRT (6.1)

STANFORD LINEAR ACCELERATOR CENTER  
 WORK SHEET  
 PERFORMANCE DATA  
 (KTF003)

Page No. 2

Date 11/24/86

INITIAL (1μs)
PROC. (3.5μs)
ACCEPTANCE
FINAL
(OTHER)

ROUND TANK ONLY	
PTT	119
PT	ST-733
CDR	5312:1
NEW CDR	

TUBE #	349a
MAGNET	5005
LOAD	AL0-46
T/S #	7
OPERATOR	TM

INSTALLED HVRM:                      FRTM:                      TOTAL FRTM:                      TOTAL HVRM:

START OF SHIFT	HVRM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR	H <sub>2</sub> O	
0700	2750.9	11.5	11.5	28.0	* 28.0	* 60	IN	°C
TIME	TUBE VAC	LOAD VAC	FOCUS	EOLC	R/E	HVOC	WINDOW	°C
	μa	μa		FLTS		FLTS	LEFT RIGHT	
0700	<0.1	10.4	15.0					
* * * 0910 To 26A - Pmi CDR efficiency factor 98% per TF.								
* * * 0910 End TL ck - to 300k per PC - to 300k/120v - unit								
0905	300k - To 310k							
	310k							
1010	310kV ↑ 320kV	362A	μK 2.00	⊖	⊖	⊖	28.1 28.5	21.9
1025	↑ 330kV	379A	μK 1.999	⊖	⊖	⊖	29.0 29.3	22.1
1040	↑ 340kV	375A	μK 1.992	⊖	⊖	⊖	30.6 30.2	22.2
1105	↑ 350kV	413A	μK 1.995	⊖	⊖	⊖	30.5 31.2	22.4
1140	↓ 300kV	PRR → 180v		Ⓣ	⊖	⊖	31.1 32.2	22.7
	300 327A μK 2.002							
1215	300kV ↑ 310kV	344A	μK 1.993	⊖	⊖	⊖	31.2 31.7	23.1
1230	310kV ↑ 320kV	361A	μK 1.999	⊖	⊖	⊖	32.1 32.8	22.8
1300	320kV ↑ 330kV	377A	μK 1.989	⊖	⊖	⊖	32.8 33.7	22.8
1325	330kV ↑ 340kV	393A	μK 1.992	⊖	⊖	⊖	33.5 34.5	22.7
1355	340kV ↑ 350	410A	μK 1.980	Ⓣ	⊖	⊖	34.0 35.3	22.7
1425	Place on fire heat sensor							
	CDR check needed @ 1500							

STANFORD LINEAR ACCELERATOR CENTER  
 WORK SHEET  
 PERFORMANCE DATA  
 (KTF003)

Page No. 3

Date 11/24/66

	INITIAL (1μs)
✓	PROC. (3.5μs)
	ACCEPTANCE
	FINAL
	(OTHER)

	ROUND TANK ONLY
PTT	119
PT	ST-733
CDR	5312:1
NEW CDR	

TUBE #	349a
MAGNET	S225
LOAD	FLD-4b
T/S #	7
OPERATOR	FF

INSTALLED HVRTM: 2714.5 FRM: TOTAL FRM: TOTAL HVRTM: 14.2

START OF SHIFT	HVRTM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR	WINDOW C°		H2O IN °C
<u>1500</u>	<u>2758.7</u>	<u>12.9</u>	<u>12.9</u>	<u>28.2</u>	<u>30.2</u>	<u>182</u>	LEFT	RIGHT	
TIME	TUBE VAC 8.1 μa	LOAD VAC 18 μa	FOCUS 15A	EOLC FLTS	R/E	HVOC FLTS			
<u>1500</u>	<u>350KV</u>	<u>Continue Heat Run</u>		<u>(2)</u>	<u>2</u>	<u>2</u>	<u>34.2</u>	<u>36.2</u>	<u>22.5</u>
<u>2220</u>	<u>350KV</u>	<u>Heat Run Completed</u>							
		<u>Radiation is recorded.</u>							
		<u>Tank radiation = 3.5 MR/hr @ 3'</u>							
<u>2240</u>	<u>350KV</u>	<u>Change H.D. to Heat. (1)</u>		<u>2</u>	<u>2</u>		<u>42.2</u>	<u>45.2</u>	<u>30.2</u>

STANFORD LINEAR ACCELERATOR CENTER  
 WORK SHEET  
 PERFORMANCE DATA  
 (KTF003)

Page No. 4

Date 11-25-86

INITIAL (1 $\mu$ s)
✓ PROC. (3.5 $\mu$ s)
ACCEPTANCE
FINAL
(OTHER)

ROUND TANK ONLY	
PTT	119
PT	57-733
CDR	5312:1
NEW CDR	5140:1

TUBE #	349a
MAGNET	S-005
LOAD	ALO-4b
T/S #	07
OPERATOR	RLG

INSTALLED HVRTM:                      FRM:                      TOTAL FRM:                      TOTAL HVRTM:

START OF SHIFT	HVRTM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR		
2300	2766.9	12.9		30.0	30.0	150		
TIME	TUBE VAC μa	LOAD VAC μa	FOCUS	EOLC FLTS	R/E	HVOC FLTS	WINDOW C° LEFT RIGHT	H <sub>2</sub> O IN °C
	.4		15.0					
CDR check does not seem to have been done (see note Page 2, Time 1425)								
found well under voltage New CDR 5140:1 (used ASDen's 95%)								
2320	unstable +.5db at 350KV Lower IA T 29A							
0030	350KV	424.4K	2.05	③	⊖	⊖	33.1 34.7	22
0130	"			⊖	⊖	⊖	33.8 35.5	22.2
0230	"			①	⊖	⊖	33.9 35.5	22.3
0330	"			⊖	⊖	⊖	33.4 35.0	22.0
0430	"			②	⊖	⊖	33.7 35.2	22.3
0530	switch TO HOT H <sub>2</sub> O							
	Power balance OFF, +6.9%, Suspect hold For Further investigation.							
0630	350KV			①	⊖	⊖	43.8 46.6	35.3

STANFORD LINEAR ACCELERATOR CENTER  
 WORK SHEET  
 PERFORMANCE DATA  
 (KTF003)

Page No. 5

Date \_\_\_\_\_

	INITIAL (1 $\mu$ s)
<input checked="" type="checkbox"/>	PROC. (3.5 $\mu$ s)
	ACCEPTANCE
	FINAL
	(OTHER)

	ROUND TANK ONLY	
PTT	119	
PT	S-733	
CDR	5812	
NEW CDR	5190	

TUBE #	349a
MAGNET	S-005
LOAD	L10-11/2
T/S #	07
OPERATOR	JE

INSTALLED HVRTM:                      FRTM:                      TOTAL FRTM:                      TOTAL HVRTM:

START OF SHIFT	HVRTM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR	WINDOW C°		H <sub>2</sub> O
0700	2774.8	12.2	12.2	27.0	29.0		LEFT	RIGHT	IN °C
TIME	TUBE VAC	LOAD VAC	FOCUS	EOLC	R/E	HVOC	WINDOW C°		H <sub>2</sub> O
	0.2 $\mu$ a	18.5 $\mu$ a	15.0	FLTS		FLTS	LEFT	RIGHT	IN °C
	350KV Loading into 11/2								
	HV RTM 2794.8 FRTM 8718.0								
	HVRT 30.3 FRT 31.5								

TUBE# 349a

LOAD# A10-46

MAGNET# 5005

TANK# 119

T/S# 07

5110.1

1. V <sub>f</sub>	Volts	12.7	12.9			
2. I <sub>f</sub>	Amps	30.0	30.0			
3. V <sub>beam</sub>	KV	320	350	320	350	350
4. I <sub>beam</sub>	Amps	366	415	330	362	413
5. P <sub>beam</sub> (Peak)	MW	117.1	145.3	99.0	115.8	144.5
6. P <sub>beam</sub> (Avg)	KW	38.3	47.5	45.2	75.7	94.5
7. μk		2.02		2.01	2.000	1.995
8. V <sub>focus</sub>	Volts	211		212	212	212
9. I <sub>focus</sub>	Amps	15.0		15.0	15.0	15.0
10. Bucking I <sub>1</sub>	Amps					
11. Main I <sub>2</sub>	Amps					
12. Upper I <sub>3</sub>	Amps					
13. Frequency	MHz	2856	SAME		2856	2856
14. PRR	Hz			120	120	120
15. τ <sub>beam</sub> (current)	μs	5.45		5.5	5.45	5.45
16. τ <sub>rf</sub>	μs	1.0		3.5	3.5	3.5
17. P <sub>d</sub> (fwd)	mw	.071	.058	0.56	.52	1.34
18. P <sub>out</sub> (fwd)	mw	.126	.180	0.58	.80	1.15
19. P <sub>out</sub> (refl)	mw	0	0	-	1.078	1.01

20. Tube Flow	GPM	18.5	18.6	18.61	18.65	18.30
21. Tube deltaT	°C	8.4	10.1	11.7	12.9	15.3
22. Body deltaT	°C	.05	.07	0.04	.09	.25
23. Load Flow	GPM	19.23	19.25	19.36	19.35	19.00
24. Load deltaT	°C	.7	1.0	2.7	2.7	5.4
25. Total H <sub>2</sub> O pwr	KW	44.6	44.7	71.3	82.4	101.0
26. Focus Pwr(-)	KW	3.2	3.2	3.2	3.180	3.180
27. Real H <sub>2</sub> O pwr	KW	41.4	51.5	68.1	79.2	97.8
28. P <sub>out</sub> (Avg)	KW	2.6	5.1	13.8	18.9	27.1
29. P <sub>out</sub> (Peak)	MW	59.2	81.7	32.8	45.0	64.5
30. P <sub>d</sub> (Peak) <small>26.5clb</small>	Watts	529	432	522	553	362
31. Efficiency	%	30.6	58.3	50.2	38.9	44.6
32. Gain	db	50.5	529	47.4	49.1	52.5

33. Stable Range	+	+2	+2	2A	2.0	2.0
34. Stable Range	-	-3	-3	2A	3.0	3.0
35. Glitches		N	N	N	N0	N0
36. RF Breakup		N	N	N	N0	N0
37. Tube Pressure	μA	0.1	0.1	0.1	0.2	0.2
38. Load Pressure	μA	8.0	9.3	12.4	13.5	15.5
39. Interception	%	0.390	0.670	0.3	1.56	1.23
40. L. Wind. Temp.	°C	23.2	23.7	27.4	28.8	31.1
41. R. Wind. Temp.	°C	23.5	23.9	27.6	29.3	32.2
42. Window Color		DARK	DARK	ART GLASS	ALLOW	ALLOW
43. H <sub>2</sub> O in Temp.	°C	22.0	21.7	21.9	22.0	22.7
44. Power Balance	%	6.79m	7.390	-4.1	+4.42	+3.37
45. Date		11-24-86	11-24-86		11-24-86	11-24-86
46. Time		0340	0430	0955	1020	1140
47. Operator		JTB	JTB	TM	JE	JE

Comments: \_\_\_\_\_

TUBE# 349A

LOAD# A10-116

MAGNET# S-005

TANK# 119

T/S# 07

5140:1

1. V <sub>f</sub>	Volts	12.9	12.9	12.2		
2. I <sub>f</sub>	Amps	30.0	30.0	29.0		
3. V <sub>beam</sub>	KV	320	350	350		
4. I <sub>beam</sub>	Amps	361	410	424		
5. P <sub>beam</sub> (Peak)	MW	115.5	143.5	148		
6. P <sub>beam</sub> (Avg)	KW	113.3	140.8	146		
7. μk		1.994	1.780	2.05		
8. V <sub>focus</sub>	Volts	212	212	213		
9. I <sub>focus</sub>	Amps	15.0	15.0	14.8		
10. Bucking I <sub>1</sub>	Amps	/	/			
11. Main I <sub>2</sub>	Amps	/	/			
12. Upper I <sub>3</sub>	Amps	/	/			
13. Frequency	MHz	2856	2856	2856		
14. PRR	Hz	180	180	180		
15. τ <sub>beam</sub> (current)	μs	5.45	5.45	5.45		
16. τ <sub>rf</sub>	μs	3.5	3.5	3.5		
17. P <sub>d</sub> (fwd)	mw	164	161	139		
18. P <sub>out</sub> (fwd)	mw	112	1170	1185		
19. P <sub>out</sub> (refl)	mw	10087	10214			
20. Tube Flow	GPM	18.42	18.50	18.44		
21. Tube deltaT	°C	19.3	22.3	24.0		
22. Body deltaT	°C	.12	.38	.78		
23. Load Flow	GPM	19.07	19.17	19.07		
24. Load deltaT	°C	5.7	7.8	8.5		
25. Total H <sub>2</sub> O pwr	KW	122.5	148.4	160		
26. Focus Pwr(-)	KW	3.180	3.180	3.15		
27. Real H <sub>2</sub> O pwr	KW	119.4	145.2	156		
28. P <sub>out</sub> (Avg)	KW	29.7	37.5	42.7		
29. P <sub>out</sub> (Peak)	MW	45.5	117.6	67.7		
30. P <sub>d</sub> (Peak)	Watts	454	433	277		
31. Efficiency	%	39.4	43.6	45.7		
32. Gain	db	50.0	51.6	53.9		
33. Stable Range	+	2.0	2.0	2		
34. Stable Range	-	3.0	3.0	3		
35. Glitches		NO	NO	N		
36. RF Breakup		NO	NO	N		
37. Tube Pressure	μA	0.2	0.2	.3		
38. Load Pressure	μA	17.0	19.0	17		
39. Interception	%	.49	1.28	2.43		
40. L. Wind. Temp.	°C	32.8	34.5	43.7		
41. R. Wind. Temp.	°C	33.6	36.3	46.0		
42. Window Color		g10w	g10w	Y		
43. H <sub>2</sub> O in Temp.	°C	22.8	23.1	35.0		
44. Power Balance	%	6.1	3.03	6.9		
45. Date		11-24-86	11-24-86	11-25-86		
46. Time		1300	1425	0545		
47. Operator		JE	JE	JE		

Comments: \_\_\_\_\_

STANFORD LINEAR ACCELERATOR CENTER  
HEAT RUN SHEET  
SLAC 5045 KLYSTRON

TUBE SERIAL # 319a  
TEST STAND # 37  
EM # S-205

SHEET # 0  
DATE 11-24-86  
LOAD # A1011b

TIME HOURS ELAPSED	TIME HOURS ACTUAL	BEAM VOLTAGE KV	BEAM CURRENT AMPS	PRR HZ	RF IN		FAULTS			WINDOW		TEMP.		INPUT WATER TEMP.	BODY DELTA T	FOCUS			17
					HW	MW	EOLC	HVOC	RE	LEFT	RIGHT	BUCK	MIDDLE			TOP			
1	1530	350	428	180	.56	1.70	(2)	0	0	34.0	35.9	22.8	.35	/	15.0	/	0.1		
2	1630	350	428	180	.53	1.65	(2)	0	0	34.0	35.9	22.7	.34	/	15.0	/	0.1		
3	1730	350	429	180	.57	1.71	(1)	0	0	33.9	35.8	22.7	.37	/	15.0	/	0.1		
4	1830	350	429	180	.58	1.70	(1)	0	0	33.4	35.0	22.2	.36	/	15.0	/	0.1		
5	1930	350	429	180	.59	1.72	(1)	0	0	33.1	34.8	22.2	.37	/	15.0	/	0.1		
6	2030	350	429	180	.59	1.72	(1)	0	0	32.9	34.4	21.8	.38	/	15.0	/	0.1		
7	2130	350	429	180	.56	1.71	(1)	0	0	33.0	34.6	22.3	.37	/	15.0	/	0.1		
8	2230	350	429	180	.55	1.71	(1)	0	0	33.3	34.7	22.2	.38	/	15.0	/	0.1		
9																			
10																			
11																			
12																			
13																			
14																			
15																			
16																			
17																			
18																			
19																			
20																			

Completed Heat Run

COMMENTS:




STANFORD LINEAR ACCELERATOR CENTER  
 ACCEPTANCE TEST REPORT  
 SLAC 5045 KLYSTRON  
 RADIATION SURVEY

*PKR 180-L*


OPERATING CONDITIONS:

TUBE NO. 349a TEST 3.5 uSec Process  
 EPY 350KV OPER. HF  
 DATE 11/24/86 TEST STAND D7  
 SQUARE TANK  ROUND TANK   
 MAGNET NO. EL-5005



RADIATION LEVELS IN mR/hr:

POSITION	BEFORE PB	AFTER PB
<u>1</u>	<u>1</u>	<u>&lt;1</u>
<u>2</u>	<u>2</u>	<u>2</u>
<u>3</u>	<u>42</u>	<u>42</u>
<u>4</u>	<u>3.5</u>	



COMMENTS:

Pos #1-2-3 42 MR/hr @ 3'  
Pos #4 3.5 MR/hr @ 3'  
Tank should have lead  
shielding added.

STANFORD LINEAR ACCELERATOR CENTER  
5045 KLYSTRON FINAL TEST DATA SUMMARY

DATE 11-26-86

TUBE # 349a  
LOAD # A10-4b  
MAGNET# S-005  
TEST STAND # 07  
HVRT 29.8 hrs  
FRT 30.9 hrs  
FILAMENT VOLTAGE 12.1  
FILAMENT CURRENT 29.0

*accept.*  
*1.2 sec*  
*12/1/86*

TANK # 119  
TRANSFORMER # S+733  
DIVIDER RATIO 5240!!  
FOCUS(350kv) 14.7  
FOCUS(320kv) 14.7  
SHUNT (Y) (N)  $\Omega$   
SHUNT BOX LABEL YES  
SUMMARIZED BY JE

epy KV	ik Amps	Pdr Watts	Pout MW	Stbl +	Stbl -
<del>350</del> <sup>320</sup>	363	497	47.3	2.0	3.0
<del>320</del> <sup>350</sup>	413	327	65.0	2.0	3.0

COMMENTS:

Faulting: (2) EOLC in 20 hrs / (1) EOLC last shot

Po Pulse Quality: 1.2 sec - 2.0dB → -3.0dB @ both 350KV & 320KV  
W < 15% AM & H.H. @ Both 350KV & 320KV at all levels.

Emission Check: If set @ 29.0A / 12.1V if @ TL 28.0A  
change in IC 1.93% change in IS 2.0A

SLAC 5045 KLYSTRON

Accept.  
T. Lee  
12/1/86

SPECIFICATION CONFORMANCE SUMMARY

TUBE 349a

COMPLIED WITH SPECS: YES NO

ITEM	AREA	COMMENTS	LOG PG.																				
1	Pout  Pdr & ik	<table border="1"> <thead> <tr> <th>epy, KV</th> <th>ik, Amps</th> <th>Pdr, W</th> <th>Pout, MW</th> <th>Focus, I</th> </tr> </thead> <tbody> <tr> <td>315</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>320</td> <td>363</td> <td>497</td> <td>47.3</td> <td>14.7</td> </tr> <tr> <td>350</td> <td>413</td> <td>327</td> <td>65.0</td> <td>14.7</td> </tr> </tbody> </table>	epy, KV	ik, Amps	Pdr, W	Pout, MW	Focus, I	315					320	363	497	47.3	14.7	350	413	327	65.0	14.7	10
		epy, KV	ik, Amps	Pdr, W	Pout, MW	Focus, I																	
		315																					
		320	363	497	47.3	14.7																	
350	413	327	65.0	14.7																			
2	PULSE STABILITY	STABLE RANGE + $\frac{2.0 \text{ dB}}{2.0 \text{ dB}}$ - $\frac{3.0 \text{ dB}}{3.0 \text{ dB}}$	8-9																				
3		TESTS NOT PERFORMED PHASE AMPLITUDE DRIFT NOISE																					
4	SHUNT	NO YES _____ $\Omega$ SHUNT BOX LABEL ATTACHED? <u>YES</u>																					
5	SPURIOUS SIGNALS	FAST FORWARD ENERGY FAULTS (BREAK UP) $\phi$ B/V @ 350KV $\phi$ B/V @ 320KV	7																				
6	HEAT RUN	② EOLC LAST 20hr / ① EOLC LAST 8hr	17																				
7	WINDOW CONDITION	MAX TEMPS L $44.7^\circ \text{C}$ ; R $45.6^\circ \text{C}$ COLOR: <u>YES</u>	17																				
8	IONIZING RADIATION	Pos # 4 (TANK AREA) 3.5 mR/hr @ 3' tank SHOULD HAVE LEAD SKIRT BEFORE going to gallery.	3.5 mR/hr																				

INSTALLED IN MAGNET # S-005 DATE: 11-26-86 DATA BY: VF

INSTALLED ON PULSE TANK # 119 REVIEWED BY: [Signature]

COMMENTS: See ionizing Radiation

KLYSTRON CHECKOFF SHEET

Tube # 3499

1 μsec Pre-processing

Initials	Check	Initials	Check
_____	<input type="checkbox"/>	_____	<input type="checkbox"/>
_____	<input type="checkbox"/>	_____	<input type="checkbox"/>
_____	<input type="checkbox"/>	_____	<input type="checkbox"/>
_____	<input type="checkbox"/>	_____	<input type="checkbox"/>

3.5 μsec Processing

<u>STB</u>	Interlock check	<input checked="" type="checkbox"/>	<u>PF</u>	Radiation Survey	<input checked="" type="checkbox"/>
<u>STB</u>	Process to 350Kv/60~	<input checked="" type="checkbox"/>	<u>AF</u>	Heat Run (4 hr. minimum)	<input checked="" type="checkbox"/>
<u>STB/TM</u> <u>FM</u>	T/L check (• 3.5 μsec)	<input type="checkbox"/>		Yellow Sheet	<input checked="" type="checkbox"/>
<u>YMI</u>	Process to 350Kv/120~	<input type="checkbox"/>		Process Summary	<input checked="" type="checkbox"/>
	Process to 350Kv/180~	<input type="checkbox"/>			

Acceptance (Input water @ 35.0°C, T<sub>rf</sub> @ 3.5μsec)

<del>_____</del>	Breakup check	<input type="checkbox"/>	_____	Heat Run	<input type="checkbox"/>
<del>_____</del>	Stability	<input type="checkbox"/>	_____	Yellow Sheet	<input type="checkbox"/>
<del>_____</del>	Acceptance Test Report	<input type="checkbox"/>	_____	Acceptance Summary	<input type="checkbox"/>
<del>_____</del>	Eng. Rundown Graphs	<input type="checkbox"/>	_____	Acceptance Data Card	<input type="checkbox"/>
<del>_____</del>	Freq. Response Check	<input type="checkbox"/>	_____	Hold For Acpt. Card	<input type="checkbox"/>

Final

_____	Interlock Check	<input type="checkbox"/>	_____	Heat Run @ 350Kv /120~	<input type="checkbox"/>
_____	T/L Check	<input type="checkbox"/>	_____	Breakup @ 350Kv /120~	<input type="checkbox"/>
<u>_____</u>	CDR Check	<input checked="" type="checkbox"/>	_____	Summary Sheet	<input type="checkbox"/>
_____	Radiation Survey	<input type="checkbox"/>	_____	Final Data Card	<input type="checkbox"/>
_____	Power Data 320Kv	<input type="checkbox"/>	_____	Shunt Box Label	<input type="checkbox"/>
_____	Power Data 350Kv	<input type="checkbox"/>	_____	Tank Data Card	<input type="checkbox"/>

STANFORD LINEAR ACCELERATOR CENTER  
 WORK SHEET  
 PERFORMANCE DATA  
 (KTF003)

Page No. 1  
 Date 11-25-86

INITIAL (1μs)
PROC. (3.5μs)
✓ ACCEPTANCE
FINAL
(OTHER)

ROUND TANK ONLY	
PTT	119
PT	5733
CDR	5312
NEW CDR	5190

TUBE #	349a
MAGNET	S-005
LOAD	A10-416
T/S #	07
OPERATOR	JE

INSTALLED HVRTM: 271.8 FRM: 8718.6 TOTAL FRM: TOTAL HVRTM:

START OF SHIFT	HVRTM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR	WATER	
0700		12.2	12.2	27.0	27.0	18.6	LEFT	RIGHT
TIME	TUBE VAC	LOAD VAC	FOCUS	EOLC FLTS	R/E	HVOC FLTS	WINDOW C°	H <sub>2</sub> O IN °C
	0.2 μa	18.5 μa	14.8				LEFT RIGHT	
0715	350KV check P1 11R							
	$25.03 \times 1038 \times 15 \times 1.5 = 355KV$							
	Secondary Cuv V - In 370KV =							
	66.79 New CDR 5240:1							
0750	HV off to check valve P1 11R							
0805	check P1 CDR VALUE is correct							
	1038:1 * ↓ 125% to check P1 11R							
0950	HV off to install H <sub>2</sub> O standard in tube flow							
1045	HV on to know HOT Flow							
	Tube flow of 60-40 gpm							
	HV off to disconnect standard							
	Hook up to load flow							
	load flow within 1 gpm of minimum							
	connect standard							
	w/ tube flow standard							
	K Factor not what it says it is							

STANFORD LINEAR ACCELERATOR CENTER  
 WORK SHEET  
 PERFORMANCE DATA  
 (KTF003)

Page No. 7

Date 11-25-81

	INITIAL (1 $\mu$ s)
	PROC. (3.5 $\mu$ s)
✓	ACCEPTANCE
	FINAL
	(OTHER)

	ROUND TANK ONLY	
PTT	119	
PT	5+733	
CDR	5190.1	
NEW CDR	5240.1	

TUBE #	349a
MAGNET	S-CC5
LOAD	A10-46
T/S #	07
OPERATOR	JE

INSTALLED HVRTM:

FRTM:

TOTAL FRTM:

TOTAL HVRTM:

START OF SHIFT	HVRTM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR	WINDOW C°		H <sub>2</sub> O
0700	2778.7	12.2	12.2	29.0	29.0	120	LEFT	RIGHT	IN °C
TIME	TUBE VAC	LOAD VAC	FOCUS	EOLC	R/E	HVOC	WINDOW C°		H <sub>2</sub> O
	.2 $\mu$ a	12.0 $\mu$ a	14.7	FLTS		FLTS	LEFT	RIGHT	IN °C
1210	350KV -				2	2	37.4	38.5	32.3
1330	HV off Machine w/ H <sub>2</sub> O standard for coll flow since flow is off by .4gpm DATA TO BE TAKEN USING H <sub>2</sub> O STANDARD NOT STATION METERING OF COLL. flow BECAUSE of Pur Ex. JRE 11/25/80 OK'd. BMC								
1340	HV on 350KV change back to 180v increased coll flow to 19.13gpm Allow 1hr for tank temp to stabilize								

STANFORD LINEAR ACCELERATOR CENTER  
 WORK SHEET  
 PERFORMANCE DATA  
 (KTF003)

Page No. Σ 3  
 Date 11/25/86

	INITIAL (1μs)
	PROC. (3.5μs)
✓	ACCEPTANCE
	FINAL
	(OTHER)

ROUND TANK ONLY	
PTT	119
PT	ST-733
CDR	5198:1
NEW CDR	5248:1

TUBE #	349a
MAGNET	S-885
LOAD	ALD-4b
T/S #	87
OPERATOR	EL

INSTALLED HVRTM: 2774.8 FRMT: 8718.0 TOTAL FRMT: TOTAL HVRTM:

START OF SHIFT	HVRTM	EF-MTR	EF-TRUE	IF-MTR	IF-TRUE	PRR, %			
1500	2781.7	12.2		29.0		80			
TIME	TUBE VAC μA	LOAD VAC μA	FOCUS — 14.7 —	EOLC FLTS	R/E	HVOC FLTS	WINDOW C° LEFT RIGHT		H <sub>2</sub> O IN °C
1500	350KV			⊖	⊖	⊖			
1600	Begin B/V check			⊖	⊖	⊖			
1630	Complete B/V check & Stability Check			⊖	⊖	⊖			
1700	Completed Acceptance Test Report			⊖	⊖	⊖			
1730	Complete Eng. Rundown			⊖	⊖	⊖			
1740	Begin Freq Response			⊖	⊖	⊖			
	Unable to Sat @ 2850 Mhz								
	Unable to Sat @ 2866 Mhz								
	Unable to Sat @ 2868 Mhz								
	Unable to Sat @ 2870 Mhz								
1810	Completed Freq Response Test			①	⊖	⊖			
1815	Placed on Acceptance Heat Run								







8

KTF014

STABILITY CHECK FORM  
5045 KLYSTRON

DATE 11-25-86

TECH. EC

TUBE# 349-

Beam voltage (circle one)    270    315    320    350

Optimum focus    I1 -    I2 14-7    I3 -    PRR 180

Saturation drive (Peak) 497 W    Set input H2O temp at 35.0° C. (±.5°)

Pulse width 3.5 μs    Peak Power Out 47.3 MW

Body Interception 0.8 %

DESCRIPTION OF PULSE: (Instabilities, type, percentage of pulse, etc.)

Stable from:    + 2 to - 3 db.

Saturation:    % AM 20.1

% Hum 20.1

At Max Stable overdriven condition (+ 2 db)    % AM 20.1

% Hum 20.1

At Max Stable underdriven condition (- 3 db)    % AM 20.1

% Hum 0.2

Comments: Pulse is clear at all observed levels.

9

KTF014

STABILITY CHECK FORM  
5045 KLYSTRON

DATE 11-25-80

TECH. EV

TUBE# 349

Beam voltage (circle one) 270 315 320 350

Optimum focus I1 — I2 14.7 I3 — PRR 180

Saturation drive (Peak) 327 W Set input H2O temp at 35.0° C. (±.5°)

Pulse width 3.5  $\mu$ s Peak Power Out 65.0 MW

Body Interception 1.4

DESCRIPTION OF PULSE: (Instabilities, type, percentage of pulse, etc.)

Stable from: + 2 to - 3 db.

Saturation: % AM 0.1

% Hum 0.1

At Max Stable overdriven condition (+ 2 db) % AM 0.2

% Hum 0.1

At Max Stable underdriven condition (- 3 db) % AM 0.1

% Hum 0.1

Comments: Pulse is clean at all observed levels

10

TUBE 349a MAGNET S005 LOAD A10-46 TEST STAND 7

TECH. EL REVIEWED BY \_\_\_\_\_ DATE 11-25-86

DRIVE ATTN. 26.5 db FIL E. 12-1 FIL I. 29-0

PRR 180 FOCUS V 210 FOCUS I 14.7

BEAM PULSE LENGTH 5.5  $\mu$ s RF PULSE LENGTH 5.5  $\mu$ s INPUT H2O TEMP 3-1  $^{\circ}$ C

		315	320	350
1. BEAM VOLTAGE	KV			
2. BEAM CURRENT	AMPS		363	413
3. PERVEANCE	$\mu$ K		2.00	2.00
4. TUBE PRESSURE	$\mu$ A		0.2	0.2
5. AVE. DRIVE PWR.	mW		.70	.46
6. LOAD FLOW	GPM		19.14	19.15
7. LOAD $\Delta$ T	$^{\circ}$ C		5.9	8.1
8. TUBE FLOW	GPM		19.9	20.0
9. TUBE $\Delta$ T	$^{\circ}$ C		17-1	19.9
10. BODY $\Delta$ T	$^{\circ}$ C		0-18	0-38
11. WINDOW TEMP. L/R	$^{\circ}$ C		40-0 / 41.7	41-3 / 43-3
12. FK. BEAM POWER	MW		116.2	144.6
13. AVE. BEAM POWER	KW		114.9	143.1
14. PEAK DRIVE	WATTS		497	327
15. AVE. RF OUT	KW		29.8	40.9
16. PEAK RF OUT	MW		47.3	65.0
17. TUBE WATER PWR	KW			
18. TOTAL WATER PWR	KW		119.6	146.0
19. FOCUS POWER	KW		3.07	3.09
20. EFFICIENCY	%		40.7	44.9
21. GAIN	db		43.8	52.9
22. BODY INTERCEPTION	%		0.8	1.4
23. POWER BALANCE	%		1.42	-0.1

## Appendix B.5i: Failure Reports

Trouble-Failure/Modification Report (1)

Window Inspection Data Sheet (1)

Klystron Failure Report (1)

Reject Klystron Tube Inspection (1)

Autopsy Report (1)

SYSTEM NO.  
5

STANFORD LINEAR ACCELERATOR CENTER  
TROUBLE-FAILURE/MODIFICATION REPORT

CONTROL NO. 84  
No. 3781

TROUBLE OBSERVED - DATE: 1 14 1987  
TIME OBSERVED: 1100  
LOCATION - STATION: 16-3  
REFERENCE NO.

PRIORITY CODE:  EMERGENCY  ROUTINE  MODIFICATION/ENGINEERING CHANGE

TROUBLE DESCRIPTION:  
1) REMOVE KLY # 349A (POSSIBLE BROKEN WINDOW)  
2) INSTALL NEW KLY

ACTION:  
O.K. to remove.  
M. Allen

SUB-SYSTEM  
-

COMPONENT	REMOVED		INSTALLED		SYMBOL
	Serial No.	Mfg.	Serial No.	Mfg.	
KLYSTRON	349A	SEARC	354A	SLAR	
				1-1587	

DATE COMPLETED: \_\_\_\_\_ TIME COMPLETED: \_\_\_\_\_  
MONTH DAY YEAR 1987 24 HOUR SYSTEM

NAME(S)  
R. FOWKES Person Notified Collins  
Trouble Reported By Person Notified Trouble Repaired By AOG Acceptance

Please see reverse side for instructions

5045 KLYSTRON  
WINDOW INSPECTION DATA SHEET


Tube Number: 349A  
 Right Window Number: \_\_\_\_\_  
 Left Window Number: \_\_\_\_\_  
 Inspected By: (4)

Inspection Number: 1283  
 Time Inspected: \_\_\_\_\_  
 Location: D- Tube Shop LITHON  
 Date: 1-26-87 Initials: (D)


	<u>Right Window</u>	<u>Left Window</u>
Blow off Req'd.	yes/no	yes/ <u>no</u>
Number of Times	_____	_____
Metallic Particles Found	yes/no/uncertain	yes/ <u>no</u> /uncertain
Spots Found	Yes/No	Yes/ <u>No</u>
Hold Window	Yes/No	Yes/ <u>No</u>
Return to Tube Shop (Yes/No)		Return Approved By: _____
Particulates Recovered (Yes/No)		Date: _____

General Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Left Window



Right Window



# KLYSTRON FAILURE REPORT

TUBE 349a TANK 119 MAGNET 9-005 DATE 1-20-87  
FROM STATION 16-3 ELAPSED FRM 446.9 ELAPSED HVRTM 281.6

REASON FOR RETURN (FROM TROUBLE REPORT):

Arcing in w/g valve

INITIAL INSPECTION: TUBE VACUUM 121<sup>u</sup> OIL BKDN 37KV

BORESKOPED

~~CHANGE TANK~~

BY [Signature] 1-20-87

PRIMARY RESPONSIBILITY: KLYSTRON , MAGNET , TANK

ACTION TO FOLLOW:  
BORESKOPE &  
TEST AS US.

Check, please

BY [Signature] 1/20/87

ANALYSIS: Check for leaks in window area and leakage current in pump.

Leak checked through window NIL  $\frac{1}{3}$  OR output, used I.P. leak detector, also confirmed NO current leakage on 81/5 pump R Barrow, very large leak up rate. Detected to have a leak  $\frac{1}{3}$  inside. Pump off  $\frac{1}{3}$  magne off for approx 4 min leaked up from 1.5  $\mu$ a to 20-30  $\mu$ a. BB

There is a small leak through one of the windows.  $P_i$  is 1.5  $\mu$ a when windows open to atm.  $P_i$  drops to < 1  $\mu$ a when load pumped down.  $P_i$  goes back up when load let up to  $N_2$ . Leak size  $\approx 2 \times 10^{-8} \frac{T \cdot L}{sec}$

PREVENTIVE ACTION:

1/23/87 Found leak using I.P. detector. tube press goes to > 25  $\mu$ a when w/g pressurized w/ Helium 1-27-87  
1/23 - same indication as R.C. Except when blown out with  $N_2$  tube press 2  $\mu$ a R Barrow

ASSEMBLIES OK FOR REUSE IN GALLERY, KLYSTRON  MAGNET  TANK

SEND TO TUBE SHOP [Signature] - H.V. Seal Resistance Before Autopsy - 121  
2/3/87 csl

FAILURE CODE 051 SIGNATURE [Signature] DATE 3-13-87

COPIES: TUBE-WHITE; TANK-BLUE; DEP. REP.-PINK; DEPT. FILE-YELLOW; CLOSEOUT-BUFF



Reject Klystron Tube Inspection

Tentative date tube is to be opened 2-5-87 09:00

Confirmed by Garwin, Hoyt, etc. Hoyt, Callin

Tube No. 349a Type 5Q4S

Gun Date

Serial No. 51-316  
SP-329-SC Type SCANDATE

Vacuum Firing 8Hrs/750°C T&M  Varian \_\_\_\_\_

RF Firing Duration 62 Hrs.

Final Pressure (HOT) 9.7E-8 Torr

Window Data

Serial No. 2114  
2124 Type AL-995

Brazed in \_\_\_\_\_ Horizontal  Bell Furnace

Sleeve Mat'l CX Ceramic-Sleeve braze alloy 35-65

Sleeve-Housing braze mat'l. 50-50

Type of coating Ti. Nitride Method used D.C. Spt'g

Cleaning method  Wet blast  Chemical

Water Pik

Other (specify) \_\_\_\_\_

Window temps. during operation at various power levels.

Bake Data

Date on bake 11/5/86 Date Pinched-off 11/14/86

Max temp. 550° °C For 128 hrs.

Pressure 7.0E-9 Torr and Emission Current 76 ma @ 1 kv

Pinch-off pressure 1.9E-9

Plans

\_\_\_\_\_ Rework \_\_\_\_\_ Scrap \_\_\_\_\_ Authorized by \_\_\_\_\_

Change \_\_\_\_\_ Window \_\_\_\_\_ Ion Pump \_\_\_\_\_ Collector \_\_\_\_\_

Other (specify) \_\_\_\_\_

Test Data

A SUMMARY

Operating  $E_f$   $I_f$


Ik Amp	P <sub>out</sub> Mw	μk	P <sub>dr</sub> W	Input w/o w DST	VSWR Sat. SS	Gain %	Eff %	Humid @ db	AM % @ db	Fault/ 8 hrs.	Missed Pulses	E <sub>f</sub> @TL	$\frac{\Delta I_{k_{avg}}}{\Delta E_f}$	Wind Temp

POSITION: \_\_\_\_\_ Date: \_\_\_\_\_ Comments/Reasons: \_\_\_\_\_

~~1068~~ RETURN 1/20/87 WINDOW FAILURE

**AUTOPSY REPORT**

Tube No 349A Date Failed 1-20-87  
 Failure mode WINDOW FAILURE Inspected by RC CG J.P. + E.H.  
 Date 2-5-87



Measurements: a) .036  
 b) .036  
 c) .036

**INSPECTION**

Smell of C2H2: Strong (S)  Weak (W)  Absent (A)

Comments: \_\_\_\_\_

Cathode No: SA-316 Clean: Y  Mottled: Y   
SP-329-52 N  N

Comments: SLIGHT MOTTLING IN TWO AREAS  
NEAR EDGE

Focus Electrode: Many: (M)  Few: (F)   
 Arcs Tiny: (T)  Heavy: (H)   
 Arcs on Radius (Yes)  (No)   
 Arcs on Outside (Yes)  (no)

Comments: A FEW TINY AND FEW HEAVY ARCS

Gun Alignment: \*TIR Concentric  
.012 TOTAL  
.006 T.I.R  
+.0012 Parall  
.0012 TOTAL PARALLEL  
 \* Total Indicator Runout

Comments: \_\_\_\_\_

S.S. Housing: Arcs: FI/FH  or MI/MH

Comments: SOME HEAVY ARCS  
A FEW HEAVY ARCS  
ON OUTSIDE RADIUS OF CORONA SHIELD.

Recommendations for gun assembly a  
 Signature: \_\_\_\_\_

Ceramic Standoff Condition H.V.S. # 42-139

Clean (C)  Puncture (P)  Breakdown (B)   
 Comments: HV seal taped, leak checked - no leak  
(twice)  
(small suspicious chip in seal)

Please check one of the following  
 A Reprocess and reuse on n tube and or use on tube  
 B Use as is on next availab on tube No. \_\_\_\_\_  
 C Scrap

Anode Nose Arcs Many Tiny (MT)  Many Heavy (MH)   
 Few Tiny (FT)  Few Heavy (FH)   
 Coating Heavy (H)  Light (L)

Comments: slightly oxidized  
few big arc spots to pit-top (SS)

Other Notes:  
H.V. Seal Res. AFTER Bake: 9.5E-8  
H.V. Seal Res. BEFORE Autopsy: 1.0

Beam Interception 0 360 \_\_\_\_\_

Comments: none  
some grain growth on anode tape Id.

**Appendix B.5j: Part Non-Conformance Report**

NON-COMFORMANCE REPORT  
KLYSTRON TUBE SHOP

Explain nature of non-conformance in detail and illustrate if necessary.

THE SPRING BETWEEN THE FOCUS ELECTRODE  
KATE EDGE AND THE CATHODE EDGE IS CLOSER THAN  
TOLERANCES ALLOW (.044 ± .006)

THE GUN ASSEMBLY SA-969 SP-65-5C SPACINGS ARE: .036,  
.037,  
.039

Name of person who first detected the problem. CHRIS GRAY

Non-conformance part  accepted  rejected by A. E. Vicks (Cognizant engineer)

Steps taken to keep this problem from re-occurring \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Part used in tube # #458a

**Appendix B.5k: Engineering Change Order**



**APPENDIX C**

**Quality Assurance Policies and Standards in Electronics  
Department**

**Appendix C.1: List of Procedures and Standards In Electronics  
Production**



## S L A C M E M O R A N D U M

March 1, 1988

To: J. Oijala - 07

From: F. Generali

Subject: ELD/EPC QC WORKMANSHIP STANDARDS AND PROCEDURES USED

---

The following list of documents are the present practices and procedures which our EPC groups use.

SPECIFICATION	TITLE
1. QC-119-100-00-R6	Production of Printed Circuit Boards (F. Generali 02/24/81)
2. QC-140-561-00-R3	Component Installation of Printed Circuit Boards (F. Generali 11/09/73)
3. QC-140-697-00-RO	Electronics Fabrication Workmanship Standards (F. Generali 04/05/74)
4. Shop Handbook	Printed Circuit Board Processing Procedure (F. Generali 04/01/74)
5. Shop Handbook	Printed Circuit Board Design and Drafting Procedure (F. Generali 01/27/88)
6. Evaluation Procedure	Outside Vendor's Qualifications to Perform SLAC PC Design Work (F. Generali 02/22/88)
7. Evaluation Procedure	Outside Vendor's Qualifications to Perform SLAC P/C Fabrication Work (F. Generali 02/22/88)
8. Evaluation Procedure	Outside Vendor's Qualifications to Perform SLAC P/C Assembly Work (F. Generali 02/22/88)
9. Evaluation Procedure	Outside Vendor's Qualifications to Perform SLAC Chassis Work (F. Generali 02/22/88)

## 10. EPC Work Processing Forms

- a. EPC Job Completed - Customer Review Sheet
- b. Printed Circuit Job-Flow Sheet
- c. EPC Labor Cost Estimate Sheet
- d. ELD/EPC Job Order Sheet
- e. Suggested Documentation & Prototype Unit Revision Job-Flow Sheet
- f. P/C Board Estimation Sheet
- g. Job Order Additional Charges (Customer Approval) Sheet
- h. CNC EPC Standard Drill Tool Number Sheet
- i. Engineering Change Request Sheet

11. QC-034-100-01-R3            SLAC/Quality Control Workmanship Standards
12. FP-027-100-01-R1            SLAC/Plating Standard for Corrosion  
Protection
13. DS-016-110-01-R6            SLAC General Drafting Instructions  
(Presently under review by the SLAC  
Standards Committee)
14. DS-016-310-01-R12           Engineering Document Numbering System  
(Presently under review by the SLAC  
Standards Committee)

FG/jbn

Copies:    M. Allen

**Appendix C.2: Examples of Documentation in Electronics  
Department**

Customer Feedback Report (1)

Engineering Change Request (1)

Electronics Department Job Order (1)

Additional Work Request (1)

P/C Job-Flow Sheet (1)

Revision Summary Sheet (1)

DATE: \_\_\_\_\_

To : \_\_\_\_\_

FROM : F. Generali - Elect. Fab. Shop

SUBJECT: Job Order # \_\_\_\_\_

After you have carefully analyzed the above subject job order which our shop has just completed for you, I would greatly appreciate your comments of the findings.

The information given, will aid our shop in personal job satisfaction; to better understand our customers' needs and to perform a better job in the future.

EXCELLENT

GOOD

POOR

SPECIFIC COMMENTS:

ENGINEERING CHANGE REQUEST STANFORD UNIVERSITY STANFORD LINEAR ACCELERATOR CENTER		EC	Page 1 of
ORIGINATOR	EXT. DATE	ORIG(GROUP):	W/O.No ACC.No
REQUEST DATE	PRIORITY 1. ___ 2. ___ 3. ___	TO(GROUP):	JOB ORDER No
NOW IN PROTOTYPE: ___Y ___N		NOW IN PRODUCTION: ___Y ___N	
Recommended CHANGE ___Y ___N		By Resp. Engineer:	
AUTHORIZED BY: _____			
SYSTEM TITLE: _____			
APPLICABLE DRAWING NUMBER: _____			
REASON ENGINEERING CHANGE REQUIRED:			
DESCRIPTION OF CHANGE:			
INTERNAL USE ONLY: AFFECTED AREAS (DISTRIBUTION)		ASSOC. DRAWINGS	
COORDINATION _____	(SUPV)	DL _____	BD _____
DESIGN/DRAFTING _____	(SUPV)	SD _____	FL _____
P/C DESIGN _____	(SUPV)	PF _____	SI _____
PRODUCTION/ MANUFACTURING _____	(SUPV)	ML _____	OTHER _____
		SA _____	
		WD _____	
DATE COMPL:	COMPL BY:	ENG ACCEPT:	

ELECTRONICS DEPARTMENT JOB ORDER

Job title			WO number	JO number
Engineer/originator	Extension	Coord code	Acct number	Dwg number
Initial status code P:   A:   R:	Rcvd date	Rqst date	Shop code	Priority
Approved	Inspected	Quantity	Hours est	CD   EA   FI   FE   LD   MS   OP   PF
Job description:			S/D	Preferred wiring:
			P/C	Kynar   Rad.   Teflon
			MECH.	

Date: \_\_\_\_\_

TO: \_\_\_\_\_  
EPC Customer's Name Bin #

FROM: \_\_\_\_\_  
EPC Group Supervisor Bin # Phone #

SUBJECT: \_\_\_\_\_  
EPC Job # Job Title Drawing #

This is to inform you that additional charges have been imposed on your work order # \_\_\_\_\_ for the following reasons:

	Original	Additional Charges		
	Hrs.	Hrs.	\$/Hr.	Cost
1. Additional work requested by originator.				
2. Additional work which was not foreseen during initial estimate.				
3. Systems or process problems.				
_____ (Specific Problem)				
TOTAL				

Please review this form, return to the above group supervisor with your comments, and sign so that we may take the appropriate action. Thank you.

Continue the work.

Stop all work.

Originator's Comments:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
Customer's Signature

\_\_\_\_\_  
(Date)

cc: F. Generali  
B. Barrera

2/88

# P/C JOB-FLOW SHEET

JOB TITLE: _____					
<u>JOB NUMBER</u>	<u>W/O, ACC. NUMBER</u>	<u>PHOTOFAB. REC. DATE</u>	<u>DUE DATE</u>		
<u>PROCESS</u>	<u>STATUS</u>	<u>NAME</u>	<u>DATE</u>	<u>INSP.</u>	<u>DATE</u>
FILMS ENCLOSED					
MYLARS ENCLOSED					
OPTICAL PROGR.					
N/C DRILL TAPE AVAILABLE					
INNER LAYERS					
LAMINATE					
<input type="checkbox"/> DRILL N/C <input type="checkbox"/> DRILL <input type="checkbox"/> MANUAL					
FIRST ARTICLE					
SAND/CLEAN					
STEP I					
PHOTORESIST					
STEP II					
TIN/LEAD					
ETCH					
GOLD PLATE					
SOLDER-REFLOW					
TRIM					
SOLDER MASK					
SILKSCREEN					

SPECIAL INSTRUCTIONS

FINAL  
INSP.

BOARDS QTY _____
SINGLE <input type="checkbox"/> SIDED BD. THICK _____
DOUBLE <input type="checkbox"/> SIDED BD. THICK _____
MULTI-LAYER <input type="checkbox"/> BD. THICK _____
SPECIAL MATERIAL <input type="checkbox"/> BD. THICK _____





**APPENDIX D**

**Quality Assurance Policies and Standards in Plant Engineering**

**Appendix D.1: Quality Assurance Plans and Policies of  
Different Groups in Plant Engineering**

**Quality Assurance Plans: Electrical Engineering Group (2)**

**Plant Maintenance Shops (1)**

**Design Drafting Group (2)**

**Architectural/Civil/Structural  
Group (2)**

**Mechanical Group (1)**

.....

QUALITY ASSURANCE PLAN IN ELECTRICAL ENGINEERING GROUP

PLANT ENGINEERING DEPARTMENT

---

The work performed by this group can be broadly divided into three categories:

1. New installations by outside subcontractors.
2. New installations or modifications by in-house personnel.
3. Maintenance, trouble shooting, etc.

Each category is described below.

1. New installation by the Subcontractor:
  - a. The drawings and specifications are prepared by an engineer/designer assigned to the project. Whenever possible or whenever it is very critical, the design is checked by another engineer. They are reviewed and approved by the group leader.
  - b. During construction engineers make frequent field inspections to check for compliance with drawings and specifications.
  - c. Subcontractors are required to perform testing, e.g. hipot and megger witnessed by the engineer.
  - d. After the job is completed, a functional test is performed to ensure proper operation.
  - e. "As built" mark-ups are returned to drafting.
2. New Installation by In-house:
  - a. A work order is prepared by the engineer with an engineering sketch that describes the work to be done. This is sent to PMS. The work order and sketch are reviewed and approved by the group leader.
  - b. The engineer makes site visits to explain the details to the electricians assigned to the project.
  - c. Hipot and/or megger tests are performed by the electricians and witnessed by the engineer.
  - d. After the job is completed a functional test is performed to ensure operation.

.....

- e. "As built" markups are returned to the Drafting Department.

3. Maintenance:

- a. Trouble calls are received and attended by the shop (PMS). Engineering support is provided as needed. Electricians are supervised by their supervisors for safety and quality.
- b. Preventive maintenance items are scheduled and performed whenever manpower and shutdown of equipment are available.
- c. A new computerized system is being developed which will help in keeping precise records and better planning.

.....

QUALITY ASSURANCE PLAN -  
PLANT MAINTENANCE SHOPS

---

Carpenter

SLAC has two journeyman level carpenters, one carpenter laborer, and two journeyman level job shoppers.

All the carpenters are familiar with SLAC policies, safety programs, and building codes.

They can handle all carpenter related needs. All work orders are reviewed, estimated, material ordered, and coordinated by the Carpentry Supervisor. Small jobs are checked at least once, while in progress, and checked with the requestor on completion. Larger jobs are checked at least daily.

Paint Shop

The paint shop has three painters. One man works in spray booth painting electronic racks, panels, and stains items that come from the carpenter shop. The other two men do mud, tape, and paint offices, hall ways, rest rooms, or anything that can be painted with rollers or brushes.

Labor Pool

The labor pool has five people plus a supervisor. They cut weeds, clean up around the site, move furniture, dig trenches, drive the bus, and deliver materials.

Mechanics

The Mechanic Shop has seven journeymen. Two work full time on heavy equipment, diesel powered equipment, two pettibones, two diesel powered forktrucks, tractors, a backhoe, a flatbed trailer, the Letourneau, and generators. One man is on long term loan to IR-2 doing steel fabrication work. The other four men do metal fabrication jobs, crane repair, installation of HVAC units and duct work, earthquaking of equipment, removal and installation of pumps, overhaul of pumps, installation and repair of fans, and test runs, and preventive maintenance of M.G. sets.

All jobs are estimated and priorities are set. Most of the mechanic jobs are short term. The supervisor checks the jobs at least daily.

.....

Quality Assurance Plan, Design Drafting Group,  
Plant Engineering Department

The primary responsibility of this group is to provide design and drafting services for new facilities and for modifications to existing facilities which are engineered by the Plant Engineers. This may include estimating, material selection, take-off and ordering, scheduling, calculations, and field inspection, as well as drafting on both new and existing drawings.

A secondary responsibility of this group is to provide design and drafting service to other departments either in our own shop or to provide personnel to work in their areas. This shop also provides reference help to others for buildings and underground utilities for the various facilities type drawings.

A Drafting Standards

1. The SLAC general drafting standards, DS-016-110-01 is the reference for all disciplines. It outlines the general rules to assure that titles, numbers, and formats are similar for ease of understanding.
2. Specific other SLAC standards are used for various design and construction procedures within the different disciplines.
3. Specific industry standards, such as ANSI, AIA, AISC, etc. are also used where applicable. (SLAC standards are currently being revised and will include CADD standards.

B Design and Drafting Accuracy

1. This is accomplished by checking between the designer and the squad leader or another designer of the same discipline.
2. 2. The final check and acceptance is by the cognizant engineer.

C Drafting "As-Built"

After completion of construction, markups are usually returned to drafting when major field changes occur to assure decent reference drawings later. These are stockpiled to be accomplished during slack time and when funds are available.

## QUALITY ASSURANCE

### Document Control and Offset Printing

#### Document Control

- A. Inspect incoming documents to be sure they comply with Document Control Procedures, AP-041-300-01, which calls for standards:
  - 1. Document has all authorized signatures.
  - 2. Correct format for new document and for revision.
  - 3. Titles and numbering.
- B. Inspect keypunched slave card.
  - 1. Adequate information for identification.
  - 2. Process cards in correct sequence.
- C. Microfilming.
  - 1. Check microfilm on densitometer.
  - 2. Process cards in correct sequence.
  - 3. Visual check of duplicate aperture card.
- D. Key punch aperture card.
  - 1. Process cards in correct sequence.
- E. Hardcopy.
  - 1. Visual check for quality copy, too dark, too light, clean copy.
  - 2. Distribute to correct department.
- F. Blueline duplicating.
  - 1. 100% inspection for quality of copy, within acceptable limits.
  - 2. Distribute to correct department.
- G. Processing engineering document requisitions.
  - 1. Withdrawal of original tracing from vault.
    - a. Authorized personnel only, signature required on preprinted card.

#### Offset Printing

- A. Visual - random check for quality product.
  - 1. In proper sequence.
  - 2. Correct reproduction size.
  - 3. Quality image from master material to paper.



## Quality Assurance Plan

Architectural/Civil/Structural Group - Engineering  
Plant Engineering Department

The primary responsibility of the group is the planning and design of new facilities and modifications to existing facilities. As such, the primary output is of a service nature; producing drawings, specifications, design reports, calculations, cost estimates, schedules, and other engineering support. The quality of the services is not easy to determine since the primary product is a service, rather than a specific object like a piece of equipment or other fabricated component. However, the quality of the service can be judged by the end resultant: for example, a well-constructed building accomplished within budget and on schedule.

### A. Construction Inspection

1. Engineers make daily field inspections during construction (not only civil, but mechanical and electrical as well) to check for compliance with drawings and specifications and to insure that construction is in accordance with codes and standards.

Recently implemented policy is use of daily inspection reports that are kept in project and contract file.

2. Test cylinders are made for ready-mixed concrete and sent to lab for testing to insure strength of concrete. Reports are retained in project file.
3. Soil testing laboratory is hired to test compaction and backfill on larger projects where engineered fill is required. Reports are retained in project file.
4. Mill certifications are obtained from supplier for structural steel and steel reinforcing bars to check for composition and strength. Submittals for products are obtained from subcontractors and suppliers. Shop drawings are checked for compliance with design drawings and concept.
5. Structural steel is checked at random for bolt torque and weld quality.
6. Electrical and mechanical engineers make required tests on their equipment and installations also. This is not covered herein.

### B. Drawings, Specifications, & Calculations

1. Checked by responsible engineer and another engineer for compliance with DOE design criteria, other codes, standards, and accepted engineering practice, and for errors, omissions, and clarity.
2. Reviewed and approved by Group Leader.

### C. Feedback/Correction

1. As the job progresses, specifications and drawings are updated and filed to document changes or other corrections, some of which are due to errors or clarifications not found during the design phase. These are used as references on future, similar jobs.
2. Cost data and schedules from previous projects are used as a database for determining costs and schedules for new projects. Improvement is needed in this area.

## Quality Assurance Plan - Mechanical Group

**Purchasing:** Group leader signs all requisitions over \$1000.

**Engineering:** Crafts support: - Agreement with remaining engineer and/or crafts supervisor.

Design: - Review of drawings and specs by other engineers.  
- Periodic review of design as it is being developed.

Formal sign-off of drawings.

Written cost estimates for all work orders over \$2000 required.

**Crafts:** Surveillance: - On site work (sporadic supervision of major shutdowns/problems, none of minor shutdown problems).  
- Purchases all reviewed by supervisor.  
- Written log and operation log sheets reviewed 100% by supervisor.

Plumbing: - All cost estimates reviewed or produced by an estimator.  
- Improvements (sporadic supervision of major work).  
- All purchases reviewed by supervisor.

Instrument Shop: - All cost estimates completed by supervisor or lead man.  
- Written log book reviewed 100% by supervisor.  
- On site work and improvement work similar to plumbing and surveillance above.

**APPENDIX E**

**Quality Assurance Policies and Standards in Accelerator  
Department**

## Appendix E.1: Quality Assurance in Software Engineering

In software engineering quality assurance issues arise in the areas of software design, implementation ("fabrication") and installation. The policies and practices described here are those that are in use routinely in the Accelerator Department Software Engineering Group, but many of these also apply elsewhere in the Laboratory.

Design phase involves reviews and presentations for public review along with written documents. The idea is to get as much conformity as possible with overall system architecture, design philosophy and general coding practice. Design specifications describe what the software is supposed to do, and reviews are to check that this will be accomplished before the final coding is started. Designs will have to go through this formal review process in order to maintain a standard software system in the Laboratory. Some of the documentation involved in a standard design review process is shown in Appendix E.1a.

During implementation the main quality assurance tool is an In-house Programmers Guide planned to help producing robust and maintainable code. Recently, a set of Coding Standard was implemented (see Appendix E.1b) for the SLC VAX Fortran. The purpose is to reduce the maintenance problem by producing code that is straightforward to debug and extend, either by the original author or someone else and to produce code that follows well-recognized software design principles and should, therefore, be less prone to errors and future problems. This system requires that programs be written in a standard format including a Standard Program Header. The header includes important information about the author, review process, any design changes, program description, etc, and thus serves as a logbook, traveler, and change order.

The installation phase involves integration of new software into existing systems. This is normally done using developmental system control programs to detect and fix errors before releasing the code for production use. Programmers are responsible for their work and the way their programs work or do not work. The new problem reporting system points out problems, both software and hardware, immediately, and brings them to the attention of responsible programmers.

**Appendix E.1a: Examples of Documentation in Software Design Review**

## BPM Difference Design Review Action Items

December 11, 1987

Author:	Lou Sanchez-Chopitea	(LSC)
Moderator:	Dave Wisner	(DEW)
Reviewers:	Miguel Flores	(MICK)
	Mark Woodley	(MDW)
	Tony Gromme	(TEG)
Amanuensis:	Robert Sass	(RCS)

Considerable discussion was had at various times on the issue of how to use colors to tell 'good' differences from 'bad' differences which might have bad status, missing difference data etc. Dark blue is used for invalid difference data.

1. (DEW) On the display, show the name of the reference orbit being used. Look at what the ARC people have done. Do they do TMITs differences?

Opened:\_\_\_\_\_ Completed:\_\_\_\_\_ Approved:\_\_\_\_\_

2. (MICK) There should be two sets of limits and the same button should show different scales depending on the mode; difference vs. normal.

Opened:\_\_\_\_\_ Completed:\_\_\_\_\_ Approved:\_\_\_\_\_

3. (LSC) The title of the BPM plot is on the background.

Opened:\_\_\_\_\_ Completed:\_\_\_\_\_ Approved:\_\_\_\_\_

4. (MICK MDW) Need to save all of the button information from the BPMP measurement display in the config file based on where it is in the template. This is a functional enhancement.

Opened:\_\_\_\_\_ Completed:\_\_\_\_\_ Approved:\_\_\_\_\_

5. (MICK) Automated BPM setup to match the config file would be nice. This is a functional enhancement.

Opened:\_\_\_\_\_ Completed:\_\_\_\_\_ Approved:\_\_\_\_\_

6. (LSC) BPMDISP and BPMDISPV need more smarts when operating in both planes. Need to uncouple planes.

Opened:\_\_\_\_\_ Completed:\_\_\_\_\_ Approved:\_\_\_\_\_

It was noted that there is a management problem between the database and the config file but no further discussion ensued.

## COMMENTS ON THE SOFTWARE

### DESIGN REVIEW PROCESS

(Steve Moore, 10/8/87)

#### 1. Audience

- a) technical supervisor, management type or someone responsible for the software under review
- b) people directly affected by, knowledgeable in or otherwise requiring interfaces to the software
- c) someone to act as amenuensis, maintaining a list of attendees and Action Items or Open Items that would be brought to a subsequent review...items to be closed off...in a smaller, less formal review with just the impacted parties; these Items might be one or more of the following:
  - 1) modules that must be modified
  - 2) any design issues that were ill-defined or incorrectly defined
  - 3) problems in format or style
- d) design review moderator/monitor, usually a management type or other person afforded respect who:
  - 1) paces the proceedings
  - 2) decides when it's time to move off trivial details (very important)
  - 3) determines when to table discussions for an external meeting
  - 4) deflects verbal abuse or other barblike comments directed toward the poor, hapless reviewee
  - 5) when it's time to quit
- e) optionally, interested hecklers and others

#### 2. What To Bring

Some or all of the following, to an appropriate level of detail:

##### a) Data Flow Diagrams

These should be high-level depictions of data and information flowing between software that has been partitioned into single logical functions (i.e., MODULES) represented by balloons. These diagrams should be of a hierarchical nature, where peering into balloons reveals lower-level data flow diagrams. Control flow is acceptable where necessary, shown with special arrows between balloons, but should be avoided. Contained inside the balloons are module names or descriptive text, preferably both.

##### b) PDL

This is a language of basically simple English descriptions of what each module is doing, laced with basic logical constructs:



- 1) IF something THEN
  - [ELSEIF something else THEN]
  - [ELSE]
 END IF
- 2) DO FOR all of something
  - END DO
- 3) DO WHILE something's happening
  - END DO
- 4) CALL {subroutine name}

Only a high level of detail should appear here, with no references to variable names or other such trivialities. The object is to communicate the basic design structure of the software, and the intentions of the developer. A more detailed discussion would be saved for the Code Review.

### c) Hierarchical Charts

These are basic structure diagrams that show who-calls-whom, by a simple indentation scheme. (This assumes that you've gotten to the point of naming names in the data flow balloons.)

Module	Description
MAIN	main program
SUBROUTINE_1	initialization routine
SUBSUBROUTINE_1	device initialization
UTILITY_4	set characteristics
SUBROUTINE_2	the workhorse
SUBROUTINE_3	the exit handler
UTILITY_1	the error reporting utility

The listing of UTILITY\* modules is optional, and can be used to enhance the understanding of what the parent module's function is. There is no need to go below the UTILITY\* module, since this should have been done elsewhere...the scope here is limited to just the modules under development.

### d) Relevant Data Structure Definition

This is a free-form pictorial containing the structure of any databases or other global data used in performing the functions under review ("...without which you would not understand what the software was doing...", as Someone Famous once said).

### e) Functional Requirements Specification

If available, this document will serve to insure that all functional requirements are addressed by the software design.

## 3. Acceptance Criteria

This is a basic checklist of issues to be addressed or questions to be answered by each reviewer. Some may or may not be relevant to the software being reviewed. A typical list is as follows:

- a) are all the functional requirements being met...if not, is there a valid reason and should the functional spec be changed?
- b) is there adequate error recovery and/or exception handling capability?
- c) what will be the approach for testing, validation and verification? when will we know it's "done", ready for production?
- d) is the software easily enhanceable, modifiable, maintainable and expandable? (i.e., is it modular?)
- e) what kind of post-release documentation is appropriate?
- f) are all appropriate user devices supported (e.g., COWs, CALFs, WKS)?
- g) what kind of hard limitations are being imposed inherent in the design, and is it justifiable? (i.e., are there arrays that are not sized large enough for future expansion?)

#### 4. Agenda

- a) brief overview of what the purpose of the software is, where it fits, who will use it, etc.
- b) present data flow diagrams, from top to bottom; here, the reviewers should make sure that the functional requirements are being met
- c) hierarchical chart is brought out for future reference, to allow reviewers a road map into the PDL modules
- d) PDL is reviewed for content only...style, header and grammar criticisms are tabled, quashed or postponed for external discussion, otherwise the process gets bogged down; something that's worked well is to have reviewers red-line their trivial comments on the listing and submit to the reviewee, or mail the reviewee a list of comments afterwards; the list of Action or Open Items will simply contain a note to the effect that there are objections to the format of one or more modules.
- e) reviewee is carried out on stretcher

#### 5. Follow-up Review

This should be attended only by people who voiced objections to content or format from the initial review, to see that the Open Items are closed off. Hopefully, this process would go smoothly, as there would have been edicts handed down from above regarding trivial matters, and all that remains would be matters of content. Also, there would have been one-on-one meetings with impacted parties or those knowledgeable in these areas in order to clear up bones of contention or to resolve approaches to certain problems.

**Appendix E.1b: SLC Coding Standards (VAX Fortran)**

## SLC Coding Standards

Computer: VAX  
Language: Fortran

## Intent:

The purpose of programming standards is to (a) reduce the maintenance problem by producing code that is straightforward to debug and extend, either by the original author or someone else and (b) to produce code that follows well-recognized software design principles and should, therefore, be less prone to errors and future problems. Generally the intent is to produce software that "flows" from top-to-bottom, start-to-end, and can be "read" easily by others because the block-structuring is readily apparent. These standards are not intended to be hard and fast (exceptions can be found), but should serve as a guide to achieving the goals stated in the first sentence. Enforcement of these standards may be either through a formal code review process, or a "spot" review of existing code. Any code following the standards will be generally acceptable as written. It is recognized that there are cases where following the standards may produce more awkward code, but these cases are rare and will be dealt with on a case-by-case basis. Code not conforming to the standards may be acceptable, but if it can be demonstrated that the same code can be written in an acceptable manner consistent with the standards, the original code will have to be modified. These standards will evolve as more experience is gained.

## Program Organization:

185

1. All Fortran source file types are ".FOR".
2. All filenames must match the module name.
3. Only one module should be stored per filename.
4. All "INCLUDE" file types are ".TXT".
5. The main program is organized in the following order:
  - a. Main program declaration on 1st line
  - b. Library MEMBER line
  - c. Prolog/Header (which includes the PDL)
  - d. IMPLICIT NONE statement
  - e. Declare arguments
  - f. Data Base include statement
  - g. Global parameter include statements
  - h. Global common include statements
  - i. Local parameter include statements
  - j. Local common include statements
  - k. Local data type declarations (include dimensions)
  - l. Dimension statements
  - m. Local equivalence statements
  - n. Local data statements
  - o. Statement functions
  - p. Executable statements with comments
  - q. END or STOP or CALL SYS\$EXIT statement for main routine;  
RETURN for subprogram
  - r. FORMAT statements
  - s. END statement
6. All modules should be FUNCTIONS rather than SUBROUTINES. In most

cases the return should be a status value. The only exceptions are for routines like SQRT() which are intended to be "embedded" elsewhere and the user must anticipate error conditions.

#### Compiler Directives:

1. Compiler directives are enforced by the SLC .COM files only. Inline compiler directives are not used.
2. The /NOF77 qualifier is not used.
3. The /NOWARNINGS qualifier is not used.
4. The /NOOPTIMIZE qualifier is used only when testing with the /DEBUG qualifier.
5. The /CHECK=ALL qualifier is used on all modules during the test/debug/development phase, but not when the module is put into production.

#### Control Constructs:

1. The following constructs are not used:
  - a. the ASSIGNED GOTO statement
  - b. the PAUSE statement
  - c. the Arithmetic IF statement
  - d. the alternate RETURN statement
2. Every DO loop is terminated with an END DO or (NNN) END DO, though use of statement numbers for defining DO ranges should be minimized.
3. There is only one entrance and one exit from a subprogram. (e.g.: no ENTRIES and only one RETURN statement for a subprogram).
4. There are no jumps or GO TOs into the range of statements for a DO loop or into an IF block.
5. The use of backward reference GO TOs is minimized.
6. The use of CALL SYS\$EXIT or STOP is used only in main routines.
7. Shared DO-loop terminations should not be used.
8. Use of the EQUIVALENCE statement is minimized.
9. Use of GO TOs is minimized, being used mainly, if at all, for error handling.

981

#### Data Declarations:

1. All variables are explicitly data typed, and this is enforced by using IMPLICIT NONE.
2. Variables are used only for one functional purpose, with the exception of DO loop indices. Temporaries are allowed for intermediate mathematical results. Re-use of database access records is allowed.
3. INCLUDE files contain only the following types of statements:

- a. Comments
- b. COMMON statements
- c. DATA statements
- d. Structure definitions
- e. PARAMETER statements
- f. Global RECORD statements

Other types of statements are excluded, in particular:

- a. Executable statements
  - b. Statement functions
  - c. Allocation of local storage
  - d. INCLUDE statements
4. All attributes, such as accuracy, convergence, and timing, which control processing are specified as named PARAMETERS.
  5. The use of hard coded numbers should be minimized by using, for example, PARAMETER statements or resource management utilities (e.g: event flags, I/O unit numbers).

#### Commentary:

1. A prolog/header is provided for each subprogram and contains the following information (see Appendix):
  - a. Purpose
  - b. Calling sequence or context
  - c. Inputs
  - d. Outputs
  - e. Assumptions
  - f. Limitations and restrictions
  - g. Accuracy and precision requirements
  - h. Error recovery procedures
  - i. External modules called
  - j. PDL
2. Every local variable is described. This includes the variable name, its type, and a description of its use. Normally this will mean one variable per line, though similar variables may be grouped.
3. Comments are provided to explain the intent of key decision points and paths.
4. For every reference to machine, compiler, or operating systems unique features, comments are provided to that effect.
5. Comments are meaningful and not a repetition of the FORTRAN statement.
6. Comments are indented to match the indentation of the code being described.
7. Any relevant comments and parts of the header are to reflect any modifications done to existing code.
8. The letter "C" is used to identify full line comment statements. The "!" is used for in-line comments.
9. A (preferably inline) comment should be provided to describe why a particular INCLUDE file has been included.

#### Naming Reference:

1. Statement labels are in ascending order.
2. Language compiler keywords are not used as variable names.
3. Subprogram names must match the name of the file.
4. The first  $\geq 2$  letters of the module name should provide some identification of the type of software contained within. Use of the underscore is recommended, but not required.
5. All arguments in a calling sequence are clearly identified as input or output in the module commentary.
6. The first  $\geq 2$  letters of the labelled COMMON name should provide some identification of the family of suppliers of this COMMON.
7. To avoid the O/0 confusion, the number 0 without another digital is not used in a name.
8. Within the constraints on naming described under standards, names are chosen to be mnemonic.
9. Numerics should generally be avoided as part of the name.
10. Reserved statement label(s):  
    9999    RETURN

Language Usage:

188

1. VAX Fortran extensions are recommended over ANSI-standard Fortran.
2. Variables are explicitly initialized before their first use.
3. Equality tests are not performed on real variables or constants (except for checks against 0.0).
4. Parentheses are used to clarify expression evaluation.
5. The size of a module should not exceed about 100 executable statements.
6. A main program or subprogram does not modify itself or another subprogram.
7. DO loop indices are not modified within the loop.
8. Sections of code within a control block (DO-END DO, IF-ELSE-END IF) are progressively indented at least 2 spaces per level.
9. Non-loop dependent computations are kept out of the loop.
10. Compound expressions are defined once.
11. Functions are not duplicated.
12. For maximal flexibility, code should be database-, table-, or file-driven.
13. Block structures (IF, ELSEIF, ENDIF) rather than conditional branches (GOTO (1,2,...)) are used when possible.
14. When done with resources, they should generally be returned,

unless a routine is really used repeatedly.

15. Use of dynamic memory is encouraged for "large" variable-size arrays.
16. Blanks are considered significant and should not be inserted in keywords or variable names. END XXX is acceptable, where XXX is (DO, IF, MAP, ...).
17. It is recommended that every IF have a corresponding THEN and END IF. This is useful for making a program's block structure more apparent, and allows setting breakpoints on the condition.
18. When modifying code written by another, the modifications should follow the original author's style, providing the original style conformed to the standards.

Appendix -- Standard Program Header

```
INTEGER*4 FUNCTION MY_FUNC( ARG1, ARG2 )
```

```
**MEMBER**=SLCLIBS:xxxSHRLIB
```

```
Abs: This should be a real quick one-line abstract that *briefly* states the purpose of this routine.
```

```
Name: MY_FUNC
```

```
Args: ARG1      A real quick description indicating  
        Use: char-string    the reason for this argument. Note that  
        Type: longword      "Usage", "Type", "Access", and "Mechanism"  
        Acc: read-only      follow the standard VMS format found in,  
        Mech: reference      for example, the RTL documentation.  
        ARG2          Similar to ARG1, though this could start  
        Use: char-string    down one line if "ARG2" has an especially  
        Type: char-string    long name. It should be noted that this  
        Acc: write          is an optional argument.  
        Mech: descriptor
```

```
Rem: This function does such and such and so and so and blah blah  
      blah, etc. This should be an overview of the purpose, use,  
      underlying algorithms (or assumptions) of this routine.  
      References to other documentation and/or programs may be noted.
```

```
Side: Any known side effects, such as: gets/frees virtual memory;  
       prints something; create/deletes/modifies a file; modifies a  
       value in a common block; modifies an entry in the SLC  
       database; etc.
```

```
Ret: If successful I*4 XXX_OKOK  
      otherwise I*4 XXX_NFG, or a DB access error (for example)  
      (Return codes specifically generated by THIS routine should be  
      detailed, others can be summarized).
```

```
Auth: DD-NMM-YYYY, Author's Name
```

```
Rev: DD-NMN-YYYY, Reviewer's Name (.NE. Author's Name)
```



C Mod: DD-MMM-YYYY, My Name:  
C Changed such and such to so and so. etc. etc.  
C DD-MMM-YYYY, Your Name:  
C More changes ... The ordering of the revision history  
C should be such that the NEWEST changes are at the HEAD of  
C the list.

C-----  
C  
C PDL :  
C  
C=====

1 Appendix -- Standard Include Header

C=====

C  
C Abs: This should be a real quick one-liner that \*briefly\* states  
C the purpose of this include file (items are described one  
C per line as described in the standards).  
C  
C Name: FileName  
C  
C Auth: DD-MMM-YYYY, My Name  
C  
C-----

C Mod: DD-MMM-YYYY, My Name:  
C Changed such and such to so and so. etc. etc.  
C DD-MMM-YYYY, Your Name:  
C More changes ... The ordering of the revision history  
C should be such that the NEWEST changes are at the HEAD of  
C the list  
C  
C-----

**Appendix E.2: Examples of Documentation in Accelerator  
Department**

Things Pending for Operations Support (1)

Weekly Summary Report (1)

Mark II Move Downtime Schedule (1)

Control Systems Maintenance Memo (2)

Spare SLC Equipment Memo (1)

05-Nov-1987

Things Pending for Operations Support  
 Priorities are listed A, B and C for high and low respectively.  
 This file is SLC::DISK1:(DEW.NTCIOPS\_SW.DOC  
 It should be most up-to-date each Fri. evening

For the S/D (Spec/Design) column, the codes are as follows:

- means (not needed / not applicable)  
 N means does not yet exist  
 Y means does exist  
 ? means 1. may not be necessary, or  
 2. exists, but needs more work

## 0. Current projects

Pri	Work Est.	Work Rem.	Work Done	Est. Avail.	Code	Status	S/D	Description
A	0.4	0.4	0.4		OP-KL-021	RKJ	N/-	Provide solid-state sub-booster support for CID/Sector 1; may only require data base mods plus beam test time, without new code
A		~0		Done	OP-KL-011	RKJ	Y/-	Damping Ring RF control (including configuration save/restore). [RKJ should talk with HW people + spec -- only. HW to be installed 7/4/87? MCR: wouldn't have to be RKJ. MCR and JSheppard to talk with RKJ.]
			~8		OP-OP-019	JRM	Y/N	Offline interface to HISTBUF (scale control, ... a la SAMPLE). Consider using MATLAB for phase 1. [Functional spec in works]
AA	B	5	6		OP-OP-028	MICK	Y/N	CUD to provide BPM display service. Approx. once per minute. [see spec NCR & soon, MICK. Can use reference orbits from config]
AA		1-2		thinking	OP-BP-007	TEG	Y/N	Think about NPS-1, NPC, BPMs, SDD, etc. & regional PP's Use of the Single Beam Dumper magnet. In rate limit mode not all affected devices (BPMs, Profs, ...) are YY triggered. Want to kill downstream PP's (Step IV of FF 3 step phase-in). Want to keep high power devices cycling as much as possible. [see also FF-DP-015]
AA	12		17	11/02/87	OP-TR-001	RCS JST	Y/Y	Scheme to enter trouble report (SCP entry, or terminal entry, or ...). Information should be accessible by people without consoles, but also by people with CALFs etc. [SPIRES integration not needed on 1st pass. Pass 2 should integrate with CUD / displays / SLC Database / ... Moved to 8000; DEVSCP exists; for hardcopy will use printers on VAX ports; inheritors coming online.]
AA	3.0	2	2		OP-HW-005	MAF KKU	Y/N	Software to control console video monitors [see spec NCR. Needed in 2-3 months (from 7/20). Separate address/data IDOM strobes.]
AA	4.0				OP-FU-002	AXK	Y/N	Toroid calibration. [see spec NCR ... JRM to patch JFC's code. Ultimately needs timing fudge in DB (calib. diff. from data acq. Needs attention!! A JRM kludge exists, but not final solution.]
	0.2	0		Done	OP-NA-026	KKU	?/?	Turn on Blow Torch Guns through ACCESS (zero DAG first) [DM] [Exists ... needs checkout]
				Need imp.	OP-AD-003	KKU	N/N	Make an error if flow switch goes OFF (currently white). Problem ... this may cause a "flood" of error msgs if a pump goes out. [KKU to try a few like this. Found in DR, PRL, FF, ARC. e.g. Flowswitch girder 700 EPO2. Capability exists ... bits exist for color coding, logging, error msgs. Need info.]

## WEEKLY SUMMARY

Week of July 6 to July 10

By W. Asher &amp; R. Anderson

Date	Problem	Comments	Down Hours	Group	Follow-up
7/6 0141	S0/1 waveguide LCW still drained.	Many valves were closed which required effort to re-establish water system.	16	PEI	*****
1845	VV1A won't turn on.	No real problem found.	1.1	PEE	fixed
2033	K1-2 focus p.s. has failed.	Repaired p.s.	1.7	LS	
2250	K1-2 low power out.	Raised beam voltage.	.7	LS	
7/7 0045	NDR bend tripped many times.	Spent many hours trying to determine cause, trouble was in intlk. card.	8	LS	
5	NDR RF tripped on mag over/I.	Replaced remote pot.	1.4	CS	
2000	No output from NDR compressor klystron.	Replaced klystron.	18	KTF	
7/8 1457	Lost PPS power at FF.	Someone turned off breaker.	1.5	OPS	
1724	Lost vacuum in NARC.	Fixed vac. leak.	7.5	VAC	
1955	SDR Ext. kicker off.	Tripped on temperature installed fans.	3	CS	
7/9 0520	50B1 safe switch on, also SRBend valve not open.	Reset. Reset MPS for manual valve.	1	OPS	
0800	SDR RF tripped off due to focus O/I.	Focus p.s. was changed	3	CS	

TASK SUMMARIES

	WK 1 10/12	WK 2 10/19	WK 3 10/26	WK 4 11/2	WK 5 11/9	WK 6 11/16	WK 7 11/23	WK 8 11/30	WK 9 12/7	WK 10 12/14	WK 11 12/21	WK 12 12/28	WK 13 1/4	WK 14 1/11
CID - 01 [ SODJA ]														
CIDA	POLARIZED SOURCE													
CIDM	MISCELLANEOUS													
CIDY	OPERATIONS CHECKOUT													
DAMPING RINGS [ LINEBARGER ]														
DRA	INSTALL 2-BUNCH KICKER													
DRB	NRTL MODIFICATION													
DRC	REALIGNMENT													
DRM	MISCELLANEOUS													
DRX	OPERATIONS CHECKOUT													
POSITRON SOURCE [ LINEBARGER ]														
POSA	NEW LAMBERTSON INSTALLATION													
POSB	NEW LFS, SOURCE, ETC.													
POSC	WTA MODIFICATION													
POSM	MISCELLANEOUS													
POSX	OPERATIONS CHECKOUT													
LINAC UPSTREAM [ INMAN ]														
LIUB	ALIGNMENT													
LIUC	BEAMLINE 90													
LIUM	MISCELLANEOUS													
LIUX	OPERATIONS CHECKOUT													
LINAC DOWNSTREAM [ INMAN ]														
LIDA	NPAS													
LIDB	ALIGNMENT													
LIDM	MISCELLANEOUS													
LIDY	OPERATIONS CHECKOUT													
BSY [ INMAN ]														
BSYA	NPAS													
BSYB	POLARIMETER													
BSYC	INSTALL SL3													
BSYM	MISCELLANEOUS													
BSYX	OPERATIONS CHECKOUT													
NORTH ARCS [ GEARHART ]														
NRCM	MISCELLANEOUS													
NRCX	OPERATIONS CHECKOUT													
SOUTH ARCS [ GEARHART ]														
SRCM	MISCELLANEOUS													
SRCB	INSTALL SKY SOUTH													
SRCX	OPERATIONS CHECKOUT													
NORTH FINAL FOCUS [ GRAY ]														
NFFA	ELECTRONICS CABLE PLANT MOVE													
NFFC	NORTH ENERGY SPECTROMETER													
NFFN	INSTALL PC8Y													
NFFD	INSTALL C0X													
NFFT	INSTALL PC10X													
NFFQ	INSTALL PC10.5Y													
NFFR	INSTALL C1Y													
NFFS	INSTALL PC7.5													
NFFM	MISCELLANEOUS													
NFFP	PPS KEYBANK INSTALLATION													
NFFD	TUNNEL SHIELDING													
NFFX	OPERATIONS CHECKOUT													
SOUTH FINAL FOCUS [ GRAY ]														
SFFB	INSTALL PC3													
SFFD	INSTALL PC12													
SFFN	INSTALL PC8Y													
SFFO	INSTALL C0X													
SFFP	INSTALL PC10X													
SFFQ	INSTALL PC10.5Y													
SFFR	INSTALL C1Y													
SFFS	INSTALL PC7.5													
SFFE	ELECTRONICS CABLE PLANT MOVE													
SFFC	SOUTH ENERGY SPECTROMETER													
SFFM	MISCELLANEOUS													
SFFT	POLARIMETER													
SFFD	TUNNEL SHIELDING													
SFFX	OPERATIONS CHECKOUT													
MKII MOVE ON BEAM LINE [ GRAY ]														
MKII	MKII MOVE ON BEAM LINE													
MISCELLANEOUS [ VARIOUS ]														
MSCM	MISCELLANEOUS													

MEMO

March 19, 1988

To: Distribution

From: M. C. Ross and S. Ecklund

Topic: Control System maintenance

During the coming months, responsibility for exchange and repair of control system components will shift from 'Sector Ten Maintenance', 'MCC Maintenance' and 'Digital Maintenance' to accelerator and storage ring operators and the Accelerator Department Controls Section staff. There are several reasons for this change of responsibility. The primary reason is that, as we begin to make luminosity with the SLC, we need to bring more engineering manpower to bear on remaining control system problems. The best way to do this is to build engineering groups with full system responsibility extending from design to repair and preventative maintenance and it is for this reason that there will no longer be separate control system engineering and maintenance groups.

Engineers and Technicians in the Power Conversion Group will perform maintenance and diagnostic functions on power supply and klystron/modulator systems. They are responsible for magnet and power supply systems, including magnet protection interlocks, up to the CAMAC modules. They are also responsible for klystron modulator systems up to the CAMAC modules.

As a result of these changes, the following procedures will apply: (effective 3/18/88)

**Off Shift (Weekdays 16:00 – 08:00, Holidays and Weekends)**

1) In case of control system component failure serious enough to impact accelerator operation the MCC (or SPEAR/PEP) operators will carry out simple diagnostic tests and replace modular units. A set of system documents and a spares inventory will be located at MCC. Spares inventory appropriate for the PEP/SPEAR control systems will be located at SPEAR and PCR. During next few months, 'Sector Ten' based technicians will help show operators these tests and replacement techniques.

2) If the failure persists after these procedures are completed, the operator will call system specialists for telephone consultation. The system

specialist, if available, may be asked to come to SLAC to continue work on the problem.

3) If no system specialists are available, the operator will page the appropriate on-call Controls Section staff member. A senior staff member (or a pair of staff members) will be on call, 24 hours/day, 7 days/week, from each of the Controls Section Engineering groups; Software, Hardware and Beam Diagnostics. The on call schedule will extend from Monday 8:00 to Monday 8:00. Individuals who are on call will carry off-site, six Bay area county pagers similar to that carried by the program deputy.

If 'on call' personnel are summoned to the laboratory on off shifts, they are required to sign in and out at MCC. On signing out, they are required to document the action taken to solve the problem in the MCC log book. If they are unable to solve the problem, they are required to notify their supervisor or group leader as soon as possible.

4) In case of control system component failure not serious enough to impact accelerator operation, the operators will perform diagnostic tests, as time allows, in order to properly document the problem so that repair work can rapidly proceed the following work day.

#### **On Shift (08:00 – 16:00)**

1) In case of control system component failure serious enough to impact accelerator operation the MCC (or SPEAR/PEP) operators will carry out simple diagnostic tests and replace modular units.

2) If the failure persists after these procedures are completed, the operator will call system specialists to continue work on the problem.

3) If no system specialists are available, the operator will page the appropriate on-call Controls Section staff member.

4) In case of control system component failure not serious enough to impact accelerator operation, the operators will perform diagnostic tests, as time allows, and notify the appropriate system specialists. It is the responsibility of the operator to clearly and concisely log the problem.

March 16, 1988

To: Distribution  
From: Dave Hamilton *DH*  
Subject: Spare SLC Equipment

---

A stock of spare equipment that will be used as replacements will be kept in MCC. This list will obviously grow as needs dictate but will start off with a complement of the following that will reside in the "GOOD MODULE" locker next to the PDP-11s. A section of some room will be provided so the larger scale spares envisioned can easily be accomodated. THESE MODULES ARE ON AN EXCHANGE BASIS ONLY--- A GOOD ONE FOR A BAD ONE. NO LOANS OR GIVE AWAYS.

1. CAMAC Modules of all varieties.
2. CAMAC Crates with Power Supplies attached.
3. Multibus Cards of each type used.
4. Multibus Crates
5. Multibus Power Supplies
6. A Fluke DVM and tools that are commonly needed.
7. Special Fuses and a Fuse Puller for the ARC AC Power Distribution Feeders located behind the racks in the ARC's.

An ongoing effort has been made since the inception of the first SLC module to tag them with SLAC ID and serial numbers and to record their location each time they move in the LEP database. This effort will continue and will need the support of those changing modules, card, crates, etc. There will be a sign in/out sheet in the locker that will require entries to be made. The information required is as follows:

1. Module Type---SAM, DAC, PSC, etc.
2. SLAC ID #----- White bar-code # such as 160001234 or the older Red/White sticker # such as 12345
3. New Location of the Module. The general concept used is the physical location. Some of the key terms used are:
  - A) NARC and SARC for the SLC ARCs
  - B) S20-AL02 This means Sector 20, Alcove rack 02
  - C) S20-F5A This means Sector 20, Fiat rack 5A
  - D) DR-DAC51 This means Damping Ring rack DAC51
  - E) 751-R35 This means building 751, rack 35.
4. Users Name----Your Name
5. Loan Date---The date the transaction takes place.

The specific slot of a module or level location of a chassis is not needed, so do not include it.

Keep the above requirements in mind when using modules etc. from the spares.



APPENDIX F

Quality Assurance Policies and Standards in Research

APPENDIX G

Quality Assurance Policies and Standards in Purchasing

**Appendix G.1: Examples of Documentation In Purchasing**

Material Acceptance report (1)

Purchase Requisition (1)

Stores Material Requisition (1)

Typed 9/17/87 Recd 9/17/87

**STANFORD UNIVERSITY**  
 STANFORD LINEAR ACCELERATOR CENTER  
 P. O. BOX 4349, STANFORD, CALIFORNIA 94305

SUBCONTRACT OR  
 PURCHASE ORDER NO.

515-S-1192

**MATERIAL ACCEPTANCE REPORT**

DATE RECEIVED 9/13/87

V  
E  
N  
D  
O  
R

MARUBENI CORPORATION  
 MARBUENI AMERICA CORPORATION/

RECEIVING REGISTER NO. 57294	SHIPMENT NUMBER	PURCHASE REQUISITION NUMBER
---------------------------------	-----------------	-----------------------------

REJECTION  LIST THE ITEM(S) THAT ARE REJECTED AND TO BE RETURNED TO THE VENDOR FOR: REWORK  REPLACEMENT  CREDIT

ITEM NO.	QUANTITY REC'D	DESCRIPTION / SERIAL / DRAWING NO.	NO. ACCEPT.	NO. REJECT	REASON FOR REJECTION
	4	SLD LIQUID ARGON CALORIMETER  SUBCONTRACT NO: 515-S-1192 PACKAGE NO. GP-L-1/14 NET WEIGHT KGS GROSS WEIGHT KGS DIMENSION X X CM MADE IN JAPAN  4 Packages			Gross weight: 94.800 KGS Measurement : 648.031  REJECTION DISCOUNTS WHEN OFFERED

TIMELY ACCEPTANCE OR REJECTION ASSURES MAXIMUM DISCOUNTS WHEN OFFERED

ACCEPTANCE

- 1  ALL ITEM(S) OF THIS SHIPMENT ARE ACCEPTED AS ORDERED AND RECEIVED.
- 2  ALL ITEM(S) OF THIS SHIPMENT ARE ACCEPTED EXCEPT THOSE LISTED ABOVE.

REQUISITIONER *Robert G. Bell*

RELEASE DATE 9-17-87

FOR BUSINESS SERVICE ONLY VENDOR NOTIFIED AND AGREES TO RETURN THE REJECTED ITEM(S) BY \_\_\_\_\_ DATE \_\_\_\_\_

PROCUREMENT

PURCHASING/CONTRACT ADMIN

FORM # 37707 (11-74)

**PURCHASE REQUISITION**  
**STANFORD UNIVERSITY**  
**STANFORD LINEAR ACCELERATOR CENTER**

Order Date \_\_\_\_\_ Requisition No. **05227 E**

Originator	Bin No.	Phone Ext.	Group	Code
Gov't Authorization		Req'n. Date	Date Required	
Account title		Account No.	Work Order No.	
Specific Delivery Point	Object	Budget Approval	Approved By (Business Services Only)	

Reporting Code \_\_\_\_\_

Refer Inquires To Buyer  S  
 H to  2575 SAND HILL RD.  OTHER SPECIFY BELOW:  
 P

Telephone Authorization Purchasing \_\_\_\_\_

Does Requisition Involve Hazardous Material?  Yes  No **◀ Must Be Checked**

Explosives  Lasers  Radioactive Mat'l.  X-Ray Equip.  Toxic, Corrosive, or Flammable Material

Special Handling or Packaging Requirements  Inspection Required  Yes  No  Attach Terms Cond.  Yes  No

	Vendor Name	Delivery Date	Ship Via	F.O.B.		Confirming To	Terms	P.O. Number
				Dest.	Ship Pt.			
A								
B								
C								
D								

ITEM NO.	QUANTITY	UNIT	COMPLETE DESCRIPTION OF MATERIALS	ESTIMATED PRICE	UNIT PRICE	UNIT

GOV'T. Contract No. If Other Than "515"  
 List Suggested Vendors Below

---



---



---

REMARKS:

---



---

REQUISITION NO.  
**05227 E**

**Stanford Linear Accelerator Center  
Stores Material Requisition**

Requested by	Phone ext.	Department
Bldg.	Room	Material For: <input type="checkbox"/> Shop Stock. <input type="checkbox"/> Over Shop Stock Level

**Instructions:** To fill your order promptly and correctly, list items by SLAC stock groups. For example, arrange by group 40-59-62-etc. in numerical order. All items to be charged to same Account or Work Order number. No back orders, request considered complete when filled. Use this form only when ordering 10 or more items.

Item No.	Quantity Required	Unit of Issue	Acc't. Use Only	Description of Item (Not required if SLAC stock no. shown)	SLAC Stock Number	Quantity Issued

Account / Work Order No.				
Signature of Requisitor:		Issued by:		Date:
Date:	Staff No.	Posted by:		Date:

FORM 37708 (4-66)

Accounting / Stores / W / Material  
(White) (Pink) (Blue)

**APPENDIX H**

**Quality Assurance Policies and Standards in Experimental  
Facilities Department**

## **Appendix H.1: Examples of Documentation in EFD**

Hazardous Experimental Equipment Committee Operational Approval (1)

Earthquake Safety Committee Review (2)

Trim Code & Cabling Procedures (3)

SLC Cableplant Installation - Quality Assurance Check off List (11)

Instrument and Control Installations- Quality Check off List (3)

Procedure in Target Production (18)



# HAZARDOUS EXPERIMENTAL EQUIPMENT COMMITTEE

---

Case No.:

Date: *March 22, 1988*

Description:

Location:

Person in Charge:

Others Concerned:

---

## OPERATION APPROVAL

The Hazardous Experimental Equipment Committee has approved the equipment named above for operation. Hazards, unique to this experiment are:

The following restrictions apply, and a list of these restrictions must be placed near the apparatus, and at the apparatus control panel.

*Follow operating procedure.*

This approval is based on

Inspection: *Inspected by*

Schematic: *SD-*

Procedure:

Drawing:

H. DeStaebler, Chairman

by J. Mark, Secretary

### Distribution:

69	J. Cerino	96	H. DeStaebler	55	R. Gearhart
84	D. Gordon	55	J. Harris	84	I. Lin
95	R. Larsen	07	K. Lathrop	24	J. Mark
55	G. Nelson	21A	H. Petersen	15	J. Rees
80	B. Richter	20	S. St. Lorant	80	C. Prescott
84	G. Warren				

MINUTES OF THE SLAC EARTHQUAKE SAFETY COMMITTEE MEETING  
September 10, 1987, 9:30 am

Members present: F. Halbo, H. Lynch, M. Obergfell.

Visitors present: B. Denton, R. Haddock, DOE/SAN

The agenda for today's meeting was a review of the *MARK II* muon facade upgrade which was just installed last month.

Denton provided the Committee with a sketch of the *MARK II* assembly showing the general appearance and location of the added Upper and Lower Facades. A copy of this sketch is attached.

There are 4 facade assemblies, two upper and two lower, each weighing 30 ton, for a total of 120 ton. The facades are attached to the magnet and central detector assemblies which weigh about 350 tons. The 100 ton top hadron absorber is supported by the top of the magnet assembly. Thus the total weight of this assembly is 570 tons. A check of Ross Johnson's calculations indicated that he assumed the combined weight to be 555, ton so the committee was satisfied that the original calculations are still valid since the actual versus assumed weights only differ by 2.7%.

Denton explained that the isolation pads that are to be installed at the four corners of the detector once it has been moved into the beamline were designed to reduce earthquake induced input forces from .6g to .25g. His design for supporting each facade was conservatively based on the .6g, however.

The method of holding the individual 2-ton lead blocks together was reviewed next and appeared satisfactory for the lower facade. The upper facade is supported differently and it was not clear how the blocks are restrained in rotation.

The  $1\frac{1}{2} \times 18'$  array of 9 ea, 2' wide, 2 ton blocks is supported by a shelf supported from above. The bottom of this shelf is supported vertically by two gussets, but there is not enough weld to prevent the shelf from swinging out in case of earthquake induced forces. Denton was also asked to either calculate the forces on the upper bolts due to rotation or to restrain the baseplate, thus preventing rotation. There was also a question about the possibility of an individual block rotating sideways out of the shelf. He is to discuss his solutions with us when we inspect the Mark II installation on the beamline before beam is turned on.

There was no further business to discuss so the meeting was adjourned at 10:30 am.

Distribution:

COMMITTEE MEMBERS:


49 R. Byers  
20 F. Halbo  
94 H. Lynch  
22 M. Obergfell  
96 K. Skarpaas  
84 G. Warren

OTHERS:

22 C. Corvin  
84 D. Gordon  
22 J. Harm  
15 L. Kral  
07 K. Lathrop  
15 E. McKeen  
95 J. Dorfan

60 F. McLaughlin  
03 A. Simpson  
12 J. Rees  
60 R. Pedersen  
80 C. Prescott  
02 E.B. Rickansrud  
80 B. Richter

# MARK II AT SLC



5-87

5374A1

TABLE OF CONTENTS

BNC

TRIM CODE FOR  
RG-59  
RG-62

HELIAX

TRIM CODE FOR  
H5-50 UNJACKETED HELIAX 7/8  
HJ5-50 JACKETED HELIAX 7/8

HIGH VOLTAGE

TRIM CODE FOR  
RG-58 SHV  
REYNOLDS TYPE C SHV  
RG-59 SHV  
RG-58 10KV  
REYNOLDS TYPE C 10KV  
RG-213 20KV  
RG-214 20KV

KELLEMS

KELLEMS SPLIT SUPPORT GRIP LACE CLOSING INSTRUCTIONS  
KELLEMS SPLIT SUPPORT GRIP ROD CLOSING INSTRUCTIONS  
KELLEMS CABLE PULLING HARNESS PROCEDURE

K-LOC LEMO

TRIM CODE FOR  
LEMO - SWISS FYXI-405  
LEMO KINGS CONNECTORS

TYPE HN

TRIM CODE FOR  
RG-213  
RG-214

TYPE N

TRIM CODE FOR  
RG-214

MISCELLANEOUS

# CABLING PROCEDURE CP-400

CABLE RG-59

CONNECTOR BNC 59-81

STORES #59-299-014-62

CABLE RG-62








CONNECTOR BNC 59-294

STORES #59-299-014-52


TRIM CODE 401

DIE SIZE KTH 2002

TRIM CODE CHART				
CODE	A	B	C	D
401	$2\frac{5}{64}$	$\frac{3}{16}$	.468	$\frac{7}{64}$
402	$1\frac{3}{32}$	$\frac{3}{16}$	.375	$\frac{7}{32}$
405	$5\frac{1}{64}$	$\frac{3}{16}$	.871	$\frac{7}{64}$
406	$\frac{9}{32}$	0	.093	$\frac{3}{16}$
407	$1\frac{1}{16}$	0	.496	$\frac{3}{16}$
408	$4\frac{7}{64}$	$\frac{3}{16}$	.809	$\frac{7}{64}$
409	$2\frac{1}{64}$	$\frac{3}{16}$	.406	$\frac{7}{64}$
416	$2\frac{7}{64}$	$\frac{3}{16}$	.453	$\frac{5}{16}$
418	$4\frac{7}{64}$	$\frac{3}{16}$	.805	$\frac{7}{64}$
420	$2\frac{1}{32}$	$\frac{3}{16}$	.600	$\frac{1}{4}$
424	$\frac{3}{8}$	$\frac{3}{16}$	.450	$\frac{7}{64}$
425	$1\frac{9}{32}$	0	.316	$\frac{9}{32}$
431	$\frac{3}{16}$	0	.366	$\frac{3}{16}$



# CABLE PULLING HARNESS PROCEDURE



## \*NOTE:

DO NOT USE CABLE TIES  
ON THIS PROCEDURE

211

LOOP PULL ROPE THROUGH EYE ON PULLING GRIP AND WIRE IN THREE PLACES AS SHOWN. EACH PLACE SHOULD HAVE TWO LOOPS. CINCH WIRE DOWN TIGHT WITH PLIERS AND CUT OFF EXCESS BEND ENDS OF WIRE BACK TOWARD END OF CABLE AND TAPE WITH ELECTRICAL TAPE AS SHOWN.

PLACE PULLING GRIP ON CABLE AS SHOWN AND WIRE TRAILING END WITH TWO LOOPS OF WIRE LACING IT THROUGH THE END LOOPS OF THE GRIP. TIGHTEN WITH PLIERS AND CUT OFF EXCESS AND BEND ENDS OF WIRE BACK TOWARD CABLE REEL AND TAPE WITH ELECTRICAL TAPE. THE REASON FOR WIRING THE GRIP IS IF THE CABLE GETS STUCK IN THE CONDUIT AND HAS TO BE PULLED BACK YOU WILL NOT LOOSE THE GRIP FROM THE CABLE.

## MATERIAL NEEDED

- 1 Pulling Grip
- 2 Common Bailing Wire
- 3 Heavy Duty Pliers
- 4 Electrical Tape